

# Innovation Funding Incentive Annual Report

31<sup>st</sup> March 2015

IFI Projects April 14 – March 15



For SP Distribution plc. and SP Manweb plc.



## Foreword

This is SP Energy Networks (SPEN) last Annual Report under the Innovation Funding Incentive (IFI) mechanism following its inception in 2005. This mechanism has resulted in a range of successful innovation being applied across the electricity supply industry. We, consequently, welcome the opportunity to continue innovation development in RIIO ED1 under the new Network Innovation Allowance (NIA) for Distribution projects.



Over the reporting period our Future Networks Team has worked hard to develop and deliver new innovative technologies that

improve the way our network operates and brings benefits to our customers. This annual report for 2014/15 details forty two of these projects that embrace a range of technologies, and represent our highest ever IFI annual spend. These projects represent our commitment to seek opportunities to leverage associated research and development spend through collaboration with other Distribution Network Operators (DNOs), academia and several Small to Medium Enterprises (SMEs).

We have carried out extensive work to understand and manage the impact of low carbon technology on our network as well as the increasing role of mobile technology and advanced aerial surveying in our day to day activities managing the network. At the same time we have undertaken several projects that have the potential to deliver immediate benefits to customers and stakeholders, be it through low intrusions excavations or real time fault updates.

We now turn our attention to extract further value for our customers and stakeholders through the NIA for Distribution projects. This, alongside our Think Big, Start Small, Scale Fast approach will enable us to be at the forefront of innovative practice.

Going forward we will be seeking NIA innovation projects that align with our Innovation strategy, which is continually shaped through on-going customer, stakeholder and community engagement, and complement our RIIO ED1 Business Plan for 2015 (1<sup>st</sup> April) – 2023.

In closing, in our capacity as co-host with the Energy Networks Association (ENA) of the Low Carbon Networks and Innovation Conference (LCNI) in Liverpool on 24-26th November we look forward to welcoming all concerned to the UK's major smart grid event for 2015.

Dalin F. Tenglar

Colin Taylor Director of Engineering Services



# Contents

FORE	EWORD
1.	INTRODUCTION & BACKGROUND5
1.1	Context5
1.2	Innovation Funding Incentive (IFI)5
2.	SP ENERGY NETWORKS STRUCTURE
3.	OVERVIEW7
3.1	IFI Overview7
4.	SUMMARY TABLES
ACHI	EVEMENTS FOR 2014/159
4.1	Development of Partnerships9
4.2	Project Origins9
5.	HIGHLIGHTS FROM 2014/15 10
5.1	SPARC Project Summary (IFI 0615)10
5.1.1	Fault Prognostics using NOJA PMAR Data10
5.2	Smart Meter Enablement (IFI 1304) 12
5.2.1	Summary of Findings12
5.3	VTOL: Beyond Visual Line Of Sight Remotely Piloted Aircraft System (IFI 1318) 14
5.3.1	VTOL: Project Progress
5.3.2	VTOL: The Innovative Solution Being Developed15
5.3.3	VTOL: The Next Steps For The Project 16
5.4	Keyhole Trenchless Technologies (IFI 1417)17
5.4.1	Conventional Approach vs. Mini-Mole 17
5.4.2	Potential Benefits of the Mini-Mole18
APPE	ENDIX A – EXPENDITURE BREAKDOWN OF PROJECTS BETWEEN LICENCES



	Programme Management Costs	20
	Net Present Value (NPV) source	20
	Project Progress Curves	21
AP	PENDIX B – PROJECT REPORTS IFI PROJECTS	23
	IFI 0401 STP 2 – Overhead Lines	24
	IFI 0401 STP 3 – Cable Networks	26
	IFI 0401 STP 4 – Substations	28
	IFI 0401 STP 5 – Networks for Distributed Energy Resources	30
	IFI 0507 – Sensor Networks (Smart Dust) – Phase 2	31
	IFI 0509 – Superconducting Fault Current Limiter	33
	IFI 0515 – Power Network Demonstration Centre (PNDC)	35
	IFI 0615 – ScottishPower Advanced Research Centre (SPARC)	38
	IFI 0621 – 3 Live Alert/Energised Alert	40
	IFI 0701 – ENA IFI Projects	41
	IFI 1004 – Remote Access to Pole Mounted Auto Reclosers	44
	IFI 1102 – Energy Storage Project	46
	IFI 1104 – SF GB Electricity Demand Project	48
	IFI 1203 – Psymetrix ACAM Phase 1	50
	IFI 1207 – Smart 3 Phase Voltage Regulator	52
	IFI 1209 – Substation Earth Integrity Monitoring System	54
	IFI 1211 – Smart CCU Development	56
	IFI 1215 – Self Repair MV Underground Cables	58
	IFI 1216 – The Role of the Demand Side in Delivering Effective Smart Grids	60
	IFI 1218 – Impact of Residential Heating and Building Standards on Demand Profiles	62
	IFI 1219 – Substation Efficiency	64
	IFI 1302 – SUSCABLE 2	66
	IFI 1304 – Smart Meter Enablement	68
	IFI 1305 – Low Power Radio Alarm System	69
	IFI 1307 – Mobile Phone Application Prototypes	70
	IFI 1308 – HTIP	73
	IFI 1310 – Cable Paper Moisture Analyser	75
	IFI 1311 – Green Running	77
	IFI 1312 – V2G	79
	IFI 1315 – Ultrapole	81
	IFI 1316 – Upgrading Legacy GM NCP to Plexman 2	83
	IFI 1317 – Cable Core Temperature Monitoring	85
	IFI 1318 – VIOL	8/
	IFI 1401 – VONAQ	89
	IFI 1404 – Urban NCP Ennancement Project	91
	IFI 1405 – Augmented Reality: Proof of Concept	93
	IFI 1411 – egenius	95
	IFI 1412 - FIIdSE ID	97
	IFI 1414 DD MAY	99
	IFI 1414 - PU-VIVIX	101
	IFI 1410 - KUAIVIES-LIDAK	103
	1 + 1 + 1 = Keynole Trenchless Technologies	105



## 1. Introduction & Background

### 1.1 Context

Ofgem introduced the Innovation Funding Incentive (IFI) as a mechanism to promote and encourage network related Research & Development (R&D). The primary aim of the incentive is to encourage the electricity network operators to apply innovation in the way they pursue the technical development of their networks.

Ofgem recognised that innovation has a different risk/reward balance compared with a network operators' core business. The incentive provided by the IFI mechanism is designed to create a risk/reward balance that is consistent with research, development and innovation. The two main business drivers for providing this incentive at this time are the growing need to efficiently manage the renewal of network assets and to provide connections for an increasing capacity of renewable generation at all voltage levels. These are significant challenges that will both benefit from innovation.

## 1.2 Innovation Funding Incentive (IFI)

The IFI is intended to provide funding for projects focused on the technical development of distribution and transmission networks, to deliver value (i.e. financial, supply quality, environmental, safety) to end consumers. IFI projects can embrace any aspect of the distribution system asset management from design through to construction, commissioning, operation, maintenance and decommissioning. The detail of the DNO IFI mechanism is set out in the Special Licence Condition C3, Standard Licence Condition 51 (for the Distribution Licences), the Electricity Transmission Licensees' IFI mechanism is set out in the special licence condition J5 Part 3 or special licence condition D5 part 2, and standard licence condition B16 Part C.



# 2. SP Energy Networks Structure

SP Energy Networks (SPEN) is the part of Scottish Power UK plc, which owns and operates the electricity transmission and distribution network of southern Scotland and the electricity distribution network of Merseyside and North Wales. Day-to-day operation of our network, approaching 112,000 km, is conducted by SPEN, a wholly owned subsidiary of Scottish Power UK plc. Since April 2007 ScottishPower has been part of the Iberdrola Group.

Our transmission and distribution licence assets come under three wholly owned subsidiaries:

- SP Distribution: The electricity network of 33kV and below in southern Scotland
- SP Manweb: The electricity network of 132kV and below in Merseyside and North Wales
- SP Transmission: The electricity network of 132kV and above in southern Scotland

IFI activity is co-ordinated centrally on behalf of these licences, this report relates to R&D activity undertaken on:

- SP Distribution plc., referred to as SP-D in this report
- SP Manweb plc., referred to as SP-M in this report



Figure 1: UK Map showing the territory of (a) SP Distribution & SP Transmission and (b) SP Manweb



## 3. Overview

## 3.1 IFI Overview

A total of 42 IFI projects are being reported by SPEN on behalf of the two SPEN licence areas for the period  $1^{st}$  April 14 –  $31^{st}$  March 15.

The projects cover a breadth of R&D providers from academia, to consultants, to manufacturers with projects ranging in investment from £36k to £344k IFI input, and development timescales of between 6 months and 9 years.

Our R&D activity has increased significantly since the introduction of the IFI. We have continued to focus on leveraging our programme through collaboration with funding bodies, other network operators or external suppliers / manufacturers. In 2014/15 SP invested £3.9m of IFI money in a project portfolio with ~£1.2m invested in new projects during the period. Year-on-year spend is illustrated below with 2014/15 representing the highest innovation spend to date:

R&D growth in SPEN (SP-D, SP-M and SP-T*) since the introduction of the IFI					
	Expenditure	No. Of			
SP-D, SP-M and SP-T*	(Internal +	Reported			
	External)	Projects			
2004/05 (Early Start)	£223k	12			
2005/06	£546k	36			
2006/07	£1,282k	41			
2007/08	£1,793k	50			
2008/09	£1,978k	38			
2009/10	£1,462k	35			
2010/11	£1,621k	27			
2011/12	£1,975k	40			
2012/13	£2,582k	50			
2013/14	£2,017k	47			
2014/15	£3,939k	42			

\*SP-Transmission is included in IFI reporting up to and including 2012/2013. This is prior to the introduction of Ofgem's Network Innovation Allowance (NIA) for Transmission projects.



# 4. Summary Tables

The following tables have been adapted from the Regulatory Instructions and Guidance documents (RIGs).

IFI Summary - SP Distribution plc. Licence Area 14/15	
SP Distribution plc. Network Revenue	£356,000,000
IFI Allowance	£1,780,000
Unused IFI Carry Forward to 2014/15	£640,000
Number of Active IFI Projects	39
Summary of benefits anticipated from IFI projects 2014/15	1
External expenditure [2014/15] on IFI projects	£1,301,011
Internal expenditure [2014/15] on IFI projects	£446,942
Total expenditure [2014/15] on IFI projects	£1,747,953

IFI Summary - SP Manweb plc. Licence Area 14/15	
SP Manweb plc. Network Revenue	£432,000,000
IFI Allowance	£2,160,000
Unused IFI Carry Forward to 2014/15	£960,000
Number of Active IFI Projects	39
Summary of benefits anticipated from IFI projects 2014/15	1
External expenditure [2014/15] on IFI projects	£1,728,504
Internal expenditure [2014/15] on IFI projects	£462,461
Total expenditure [2014/15] on IFI projects	£2,190,965

<sup>1</sup> Further detail on these tables is provided in Appendix A of this report.



# Achievements for 2014/15

At the end of 2014/15 the highlights from the SPEN IFI portfolio included:

- Every IFI project undertaken by SPEN is taken before a panel of senior experts from across the business. Through this process we have:
  - 42 live projects
  - 9 new projects were authorised during the 2014/15 reporting period
  - Of the 42 projects, 33 are now complete and either awaiting adoption or formal closure. It is planned that the remaining projects will continue under NIA funding.

## **4.1 Development of Partnerships**

During the reporting period the programme consisted of the following collaborative projects:

- DNO specific Collaborative projects with some / all UK DNOs via EA Technology, ENA or through direct collaboration (see Appendix B for details).
- Direct university partnership ScottishPower Advanced Research Centre (SPARC) and Power Network Demonstration Centre (PNDC) with the University of Strathclyde.
- Energy Innovation Centre (EIC) A non-profit trust that oversees the management of the centre in collaboration with SPEN, Electricity North West, Scottish & Southern Energy, Northern Power Grid, UK Power Networks plus Northern Gas Networks, National Grid Gas, Scotia Gas Networks and Wales and West Utilities plus Offshore Renewable Energy Catapult.

## 4.2 Project Origins

As part of the overall strategy for the technology portfolio, SPEN aims to have a balanced mix of projects that originate from other sources and not just from within SPEN as illustrated below.





# 5. Highlights from 2014/15

This section provides details on a sample range of projects that have the potential to bring benefits in improvements to customer service, operational costs and energy usage/carbon emissions.

## 5.1 SPARC Project Summary (IFI 0615)

## 5.1.1 Fault Prognostics using NOJA PMAR Data

Fault diagnosis and prognosis are key parts of a control and protection engineer's role to ensure the effective and stable performance of electrical power networks. One challenge is to support the analysis and application of expert judgment to the, often, large data sets generated. To assist engineers with this task and improve network reliability, this research focuses on analysing previous fault activity on the overhead line, in order to obtain an 'earlywarning' report to assist fault diagnosis and fault prognosis.

This project aims to design an integrated system applying a fault diagnosis/prognosis algorithm to available Supervisory Control And Data Acquisition (SCADA) alarm data and 11kV distribution network data captured from Pole Mounted Auto-Reclosers (PMARs) (provided by SPEN). The developed system will be capable of diagnosing the nature of a circuit's previous fault activity, underlying circuit activity and evolving fault activity and the risk of future fault activity, and will provide prognostic decision support for network operators and maintenance staff. The project will improve network performance by:

- Informing and assisting maintenance staff to take appropriate preventative action before incipient and transient circuit events evolve to the point of semipermanent and permanent faults, thereby:
- Reducing the amount of nuisance tripping from semi-permanent faults.

This integrated decision support system consists of three analysis components:

- Fault diagnosis is achieved by:
  - SCADA alarm data analysis for anomaly detection and problematic circuit location
  - PMAR data analysis for identification of semi-permanent faults
- Fault prognosis is based on:
  - Semi-permanent fault activities analysis for fault prognostics

The anomaly detector and PMAR data visualisation tool search for and identify frequent unsolicited openings and potential relevant semi-permanent fault activities. The anomaly detector will identify the periods or circuits of frequent unsolicited openings with associated PMARs based on analysis of SCADA alarm data (stored in the PSALERTS database). The PMAR data visualisation tool will present extracted/derived information of fault activities based on analysis of PMAR data associated with previous identified frequent unsolicited openings in order to identify semi-permanent faults.

Identified semi-permanent fault signature will be classified in order to identify patterns and trends in their occurrence. These patterns will be then be used in order to provide prognostic and 'early-warning' information about the likely development of fault behavior



for the affected circuit. Timely intervention by maintenance staff to forestall the further development of semi-permanent and permanent faults can therefore be made.



## 5.2 Smart Meter Enablement (IFI 1304)

During the second half of 2014 the Smart Meter Test Bed was used to investigate 6 scenarios against the base functionality available in the SPEN Outage Management System (OMS), PowerOn. The test bed (shown below) provides the ability to simulate the anticipated meter messages for different network events and communicate them in a repeatable manner to test the OMS system.

The scenarios investigated ranged from a Single Premise call to a Primary Grid Loss. The current version of PowerOn only provides limited support for Smart Meter data as full functionality is expected in later releases, but the test environment has been invaluable in:-

> Identifying "issues" with the way that Smart Data will be presented to the



DNOs, specifically around the timing of messages.

- Identifying the changes needed to PowerOn to enable it to consume Smart Meter data robustly.
- Identifying the changes in the business processes to achieve meaningful business benefits.
- Identifying the changes needed to PowerOn to support the proposed business processes.

Meter Details									Top
Meter Number	Last Upda	te Time		Status In Progress			Ping	1	
1800025656073	10-444-20	10 10.10.04							
Audit Log									Top *
Time Des	scription		Operator Name			Control P	osition		
Call History									Top *
Time	Category	Priority	Zone	Address	Town	Post Code	Reference	Operator	
15-APR-2015 13:10:5	4 No Supply (Smart	1	GLASGOW NORTH	/2 22 GLAIVE ROAD	GLASGOW	G13 2HU	CALL-97674-k	USER	
27-MAR-2015	No Supply (Smart Meter)	1	GLASGOW NORTH	72 22 GLAIVE ROAD	GLASGOW	G13 2HU	CALL-97604-k	USER	
27-MAR-2015	No Supply (Smart Meter)	1	GLASGOW NORTH	72-22 GLAIVE ROAD	GLASGOW	G13 2HU	CALL-97539-k	USER	
27-MAR-2015	No Supply (Smart Meter)	1	GLASGOW NORTH	72 22 GLANE ROAD	GLASGOW	G13 2HU	CALL-97480-k	LER	
26-MAR-2015	No Supply (Smart Meter)	1	GLASGOW NORTH	72 22 GLAIVE ROAD	GLASGOW	G13 2HU	CALL-97406-K	USER	
15-OCT-2014 13:25	26 No Supply (Smart Meter)	1	GLASGOW NORTH	72 22 GLAIVE ROAD	GLASGOW	G13 2HU	CALL-80524-k	USER	
15-0CT-2014 12:44	42 No Supply (Smart	1	GLASGOW	12 22 GLANE	GLASGOW	G13 2HU	CALL-80461-k	USER	

## 5.2.1 Summary of Findings

As a result of this trial, our understanding of the impact of Smart Meter data has been significantly enhanced and has influenced our proposed approach to the integration of Smart Meter data into our business processes.

A summary of the findings are as follows:-

- 1. PING functionality (a check of smart meter energisation status) can help both confirm genuine no-supply calls and also add value during multiple restoration stages.
- 2. Power outage messages can allow PowerOn to rapidly predict the correct incident



scope significantly in advance of customer calls. However, delayed Power Outage messages that arrive after the network has been restored need to be managed to avoid spurious re-interruptions.

- 3. Smart Meter Data in extreme circumstances could swamp the Control system and the volume of messages will need to be managed by a separate system. This can limit some benefits but is essential to ensure control of the network.
- 4. Based on our findings we believe there are a number of relatively straightforward functional changes that would provide benefits and would likely be common to GB network operators:
  - a. Provide access to group PING functionality from various parts of the OMS user interface, in particular from Incident Scope screens.
  - b. Provide visibility of the meter energisation status from various parts of the OMS interface, and ensure the status is driven by Power Outage, Power Restoration or PING messages.
  - c. Support both the event time and the message arrival time for Power Outage messages.
- 5. The timing of Smart Meter messages needs to be raised with Ofgem to understand how they will affect regulatory reporting. For example, the event time within the message is always significantly earlier than the time when the message arrives from the DCC.

These findings have allowed us to more fully understand possible approaches to smart meter data management and the test environment will be maintained to allow further assessment of Smart Meter impacts.





## 5.3 VTOL: Beyond Visual Line Of Sight Remotely Piloted Aircraft System (IFI 1318)

Electricity distribution networks (steel tower and wooden pole circuits) and gas distribution networks (high pressure gas pipelines) require regular inspection in order to ensure that they remain fit for purpose and comply with HSE regulations. Emerging Unmanned Aerial Vehicle (UAV) technologies (such as small multi-rotor systems) are starting to be deployed, particularly for electricity asset inspections, for the inspection of steel towers in combination with the well proven approach of using manned helicopters. The benefits of such technology used for these types of inspection tasks are that they are relatively cheap to procure, are highly manoeuvrable, but they do have limitations with regards to payload carrying capacity, range, endurance as well as overall flight times. Repeatability of inspection data capture can also be an issue, as well as access to the assets and infrastructure that have been targeted for inspection.

This project is investigating the feasibility (from both a commercial, technical and regulatory perspective) of deploying similar, small Remotely Piloted Aircraft Systems (RPAS) but operating them Beyond Visual Line Of Sight (BVLOS) to augment and complement current asset inspection methods. If this can be achieved, then asset inspection costs have the potential to be substantially reduced, inspection tasks can be automated, such that truly repeatable inspection data can be not only gathered, but also analysed for different types of trend. One such example is degradation trend analysis of a specific asset or across assets of similar types - potentially automatically, using advanced software tools and techniques. If low-cost BVLOS operations can be achieved, then the electricity and gas distribution networks will have an additional asset and infrastructure inspection capability that they can deploy at a lower cost in most cases than current techniques, hence opening up new possibilities for increased frequency of inspection or a broader use of such technology in places where it is not used today for new asset inspection tasks such as inspecting wooden pole circuits from the air in addition to current steel tower circuits, or within the gas sector, inspecting difficult to access gas pumping stations.



### 5.3.1 VTOL: Project Progress

The first six months of the study were focused on establishing a clear and accurate confirmation of the industry's RPAS BVLOS operational requirements, combined with a high-level return on investment (ROI) analysis of each of the identified BVLOS asset inspection operations from a commercial, technical and regulatory perspective. The result of this work was the publication of a 209 page document that concluded that:

- The potential financial returns clearly outline the opportunity for either cost savings compared with current aerial inspection operations or for re-investing these savings into improving the inspection processes as the demands for energy increase and more demanding inspection capabilities are required by the regulatory authorities.
- Technically, the technologies required for RPAS operating BVLOS are accelerating and within the next couple of years will be mature enough to provide complete BVLOS solutions.
- The European Union and the UK Civil Aviation Authority (CAA) are working hard to establish a clear set of European regulations for light UAS (RPAS weighing <25kg) by 2016, paving the way for BVLOS operations within the next couple of years.

Following on from stage 1, VTOL Technologies developed three "Concept of Operation" virtual-reality environments in order to model and better understand the needs and requirements of inspecting steel tower (Ferrybridge, North Yorkshire), wooden pole (Isle of Wight) circuits and a high pressure gas pipeline (Inverness, Scotland) circuit. This work provided a brand new understanding of the options and techniques that could be successfully deployed for the identified inspection tasks. Key aspects of this work included looking at new camera technology techniques, optimal flight paths and flight inspection manoeuvres, flight safety procedures and presentation of safety case options to the CAA as well as evaluating inspection range and endurance requirements, as required by the DNOs and GDNs. What was truly surprising is that for one DNO alone, over 75% of their 132kV power line circuits are only 10km long, proving to be an excellent fit for the right type of RPAS to deliver successful BVLOS asset inspection data.

## 5.3.2 VTOL: The Innovative Solution Being Developed

Different types of RPAS architecture (multi-rotor, hybrid and fixed-wing designs) were also investigated to determine likely performance and ability to meet the Concept of Operation requirements. This work was achieved using advanced aircraft performance software analysis tools. What transpired from this work is that even with significant advances in power system technologies (battery systems, hydrogen fuel cell systems or other), it is unlikely that multi-rotor systems will be able to meet the range and endurance demands, since additional avionics systems such as longer range and therefore heavier communications technologies will be required, as well as additional collision-avoidance technologies siphoning off more of the on-board power. However, new RPAS hybrid aircraft designs, certainly at this stage, look as if they have the potential to meet the requirements demanded of true BVLOS operations, by substantially reducing RPAS power consumption, thus dramatically extending range and endurance.



## 5.3.3 VTOL: The Next Steps For The Project

The final stage of the project will be translating the confirmed Concept of Operation requirements into an industry standard BVLOS RPAS specification that can meet the GDNs and DNOs needs. This generic RPAS system specification(s) will consist of, but will not be specification limited to, data such as size, weight, range, endurance, airframe/energy/payload fractions, power consumption, etc., for an RPAS capability that is able to meet the categorised and prioritised Concept of Operation requirements. VTOL Technologies will also investigate the overall feasibility of the industry implementing the desired RPAS BVLOS operations, including the provision of an implementation roadmap.

Although the CAA can only certify actual physical systems for flight operations BVLOS, providing an accurate flight operation model and simulating possible failures will enable the CAA to provide a clear indication as to the 'certifiability' of BVLOS RPAS for each of the identified and prioritised inspection tasks/operations, significantly reducing downstream selection, development and system integration risks. At this point in time, it is anticipated that there might be two or even three complete system specification options that emerge.

Once this project has been completed, the electricity and gas distribution sector will have a difficult decision to make, should they wait for the right industry-specific solution to emerge that can truly meet their requirements or should they pro-actively invest in the development of such a solution and if so, how should this be achieved?



## 5.4 Keyhole Trenchless Technologies (IFI 1417)

Renewing and upgrading underground LV cables and service connections can be a costly and time consuming activity. The standard unit cost for this activity does not take into consideration different circumstances which can significantly increase costs and inconvenience to customers; such as increase excavation and reinstatements resulting from ornate or decorative paving. These types of excavations can be significantly more expensive and time consuming, removing limited resources from front line activities, and reducing efficiencies.

Although the merits of conventional open cut trenching are well known there is an intrinsic risk to home owners and members of the public. To develop an alternative solution to this problem SPEN has been working with R&D partner, Tracto-Technik (TT), to design an innovative trenchless technology system (Mini-Mole) which could be used as viable

alternative to traditional open cut trenching method current utilised for LV cable applications. The R&D phase, completed during IFI Keyhole Trenchless Technologies, will be manufactured into a full scale working prototype and extensively trialed to establish the benefit of the technique over conventional excavation methods for a variety of typical jobs.

Following field trials in December 2015 on an existing trenchless technology rig, more commonly used for larger cable applications, an extensive redesign has been completed. Working with TT along with both internal and external stakeholders, a number of innovative redesigns and modifications have been incorporated to improve flexibility of the rig, and importantly to reduce its size and footprint, which will allow it be utilised in a standard LV cable joint excavation. The resulting unit is expected to be available for trials in the summer of 2015 and Business as Usual application is expected in early 2016.



## 5.4.1 Conventional Approach vs. Mini-Mole

The pictures below illustrate the open trench work required in order to connect service cables.







The Mini-Mole has been designed to fit a standard excavation required for jointing LV cables, removing the need to complete costly and time consuming road crossings. The Mini-mole method will greatly reduce the footprint of the work, reducing excavation and reinstatement costs, improving the working environment and lead to a reduction on standard traffic management costs. In addition, a reduction of exposure to manual handling risk using this innovative Mini Mole Trenchless Technology is anticipated.

This new method of inserting new/renewing existing services will help to prevent costly reinstatement of footways, which during excavation/reinstatement can render the footpath off limits to some pedestrians, as well as restricting access and egress from properties.



The above diagram outlines the potential difference between the traditional method with road crossing and traffic management vs. the Mini-Mole method with no open excavation road crossings and limited excavation requirements.

## 5.4.2 Potential Benefits of the Mini-Mole

Below is a list of benefits that this project could realise:

- Reduced cost due to less re-instatement, and much less removal of spoil
- Reduced labour hours, especially on long lengths of track
- Increased safety to employees and the public
- Less disruption to pedestrians/customers
- Reduced use of barriers and traffic management equipment
- Reduced carbon footprint, hence environmental benefits

## Traditional Method

Mini-mole method

ropert



# Appendix A – Expenditure Breakdown of Projects between Licences



#### Summary Table Notes

During the collation of the 05/06 report we revised our methodology for NPV assessments for IFI projects. It is noted that the figures described in the tables should be interpreted with caution, as the figures quoted in the NPVs will only be realised upon completion of the project, and once fully adopted into the business.

## Cost Breakdown

As SPEN operate distribution licenses for the SP-Distribution and SP-Manweb areas, successful developments relating to distribution assets undertaken in one part of the business will equally apply to the other. Given the different sizes of each network area and associated annual turnover, costs have been split against each licence as follows:

Licence Area	Percentage Split Distribution
SP-Distribution	46%
SP-Manweb	54%

Projects identified as only applying to one licence, or ones that apply in favour of one licences have been scaled accordingly (See Table A1). This is defined when the project inception document is developed.

### Programme Management Costs

Internal costs for projects detailed in Appendix B are based on SPENs input to a project through meetings, correspondence, trials, etc. scaled by the appropriate hourly rate for an individual's grade.

## Net Present Value (NPV) source

It is noted that IFI projects address a range of issues, and the benefits achieved, and those accounted for in the NPV can be categorised into the following areas:

- Avoided cost A successful development may negate the need to spend money on network components. As an example the development of a high capacity circuit, would avoid the need for duplicate traditional circuits for a given network application.
- **Direct savings** Successful development could result in a direct financial benefit, e.g. through reductions in operating costs, reduced exposure to Regulatory penalties, etc.
- **Managing risk** A successful development would assist in reducing the risk profile of the company, either through greater understanding of causes / effects of actions on, or as a result of, network operation (equipment failure, etc.)
- **Strategic** These projects impact on the longevity of the network, either through external influences such as changes in load / generation patterns, the impact of climate change or even skills / resources.

NB. Whilst an NPV calculation if possible for any project, and across any of these areas, it is recognised that as the assessment looks further to the future (as is the case for strategic projects), the benefits are more susceptible to risk, more uncertain, and consequently less robust.

As of 31<sup>st</sup> March 2015 the status of the 42 projects reported as well as those that have stopped is detailed below.



IFI Project Status						
No.	Phase	Definition	External Cost			
9	Live projects	Projects continuing under NIA	Yes (if milestones have been met)			
33	Completed projects	Projects closed under IFI	Yes			

This breakdown accounts for reasons why not all projects have significant external spend.

### **Project Progress Curves**

Expenditure profiles are described below to give an appreciation of costs that will be required prior to a project realising a stated benefit through the development cycle. Figure A1 shows a hypothetical expenditure profile for a development project. Expenditure is defined as:

- **External** Money paid to 3<sup>rd</sup> parties for work (consultancy, purchase of equipment, monitoring, etc.)
- Internal SPEN' staff time on eligible IFI development work multiplied by the appropriate hourly rate. The success of a project is highly dependent on the levels of internal support a project is given.
- **Overall investment** The total cost of a project (predominantly external cost) of which the company is accessing through collaborative or external funding leverage. This is the combined investment from SPEN and other collaborative partners.

In line with sound project management, all IFI projects have been staged into milestones, i.e. the R&D provider will only receive payment upon successful completion of a defined stage.



Figure A1: Example Expenditure Profile for an IFI Project



		Percentage		£ split							
Project Description		split		SPD					SPM		
	SPD	SPM		External		Internal		External	h	nternal	
IFI 0401 - Strategic Tech Prog	46%	54%	£	104,150	£	37,116	£	122,263	£	43,571	
IFI 0507 Sensor Networks - Smart Dust	100%	0%	£	12,488	£	47,492	£	-	£	-	
IFI 0509 - Superconducting Fault Current Limiter	46%	54%	£	3,063	£	6,487	£	3,596	£	7,615	
IFI 0515 - Power Network Demo Centre	46%	54%	£	20,943	£	10,115	£	24,585	£	11,875	
IFI 0615 - SP Advanced Research Centre	46%	54%	£	67,808	£	8,581	£	79,601	£	10,073	
IFI 0621-3 Live Alert	46%	54%	£	5,375	£	6,487	£	6,309	£	7,615	
IFI 0701 ENA Small Value Projects	46%	54%	£	24,815	£	6,487	£	29,131	£	7,615	
IFI 1004 - Remote Access to Pole Mounted Auto Reclosers	100%	0%	£	6,659	£	25,358	£	-	£	-	
IFI 1102 - Energy Storage Project	46%	54%	£	5,115	£	6,836	£	6,004	£	8,025	
IFI 1104 - SF GB Electricity Demand Project	46%	54%	£	3,063	£	6,487	£	3,596	£	7,615	
IFI 1203 - Psymetrix ACAM Phase 1	0%	100%	£	-	£	-	£	54,659	£	14,102	
IFI 1207 - Smart 3 Phase Voltage Regulat	46%	54%	£	5,375	£	6,599	£	6,309	£	7,747	
IFI 1209 - Substation Earth Integrity Monitoring System	46%	54%	£	116,305	£	6,487	£	136,532	£	7,615	
IFI 1211 - Smart CCU Development	46%	54%	£	5,375	£	58,634	£	6,309	£	68,831	
IFI 1215 - Self Repair MV underground	46%	54%	£	35,609	£	7,010	£	41,802	£	8,230	
IFI 1216 - The Role of the Demand Side	46%	54%	£	3,063	£	6,487	£	3,596	£	7,615	
IFI 1218 - Impact of Domestic Heating	46%	54%	£	3,063	£	6,487	£	3,596	£	7,615	
IFI 1219 - Substation Efficiency	46%	54%	£	6,804	£	6,487	£	7,987	£	7,615	
IFI 1302 - SUSCABLE 2	46%	54%	£	25,296	£	7,534	£	29,696	£	8,844	
IFI 1304 - Smart Meter Enablement	46%	54%	£	78,453	£	11,607	£	92,097	£	13,626	
IFI 1305 - Low Power Radio Alarm System	46%	54%	£	5,375	£	12,348	£	6,309	£	14,495	
IFI 1307 - Mobile Phone Application Prototypes	46%	54%	£	116,348	£	36,625	£	136,582	£	42,994	
IFI 1308 - HTIP	46%	54%	£	39,118	£	7,162	£	45,922	£	8,407	
IFI 1310 - Cable Paper Moisture Analyser	46%	54%	£	18,683	£	6,487	£	21,932	£	7,615	
IFI 1311 - Green Running	46%	54%	£	39,705	£	6,487	£	46,610	£	7,615	
IFI 1312 - V2G	46%	54%	£	96,621	£	7,162	£	113,424	£	8,407	
IFI 1315 - Ultrapole	46%	54%	£	5,375	£	6,487	£	6,309	£	7,615	
IFI 1316 - Upgrading Legacy GM NCP to Plexman 2	46%	54%	£	5,375	£	10,952	£	6,309	£	12,856	
IFI 1317 - Cable Core Temperature Monitoring	46%	54%	£	5,375	£	6,487	£	6,309	£	7,615	
IFI 1318 - VTOL	46%	54%	£	31,671	£	6,487	£	37,179	£	7,615	
IFI 1401 - VONAQ	46%	54%	£	5,375	£	6,487	£	6,309	£	7,615	
IFI 1404 - Urban NCP Enhancement Project	0%	100%	£	-	£	-	£	234,057	£	14,102	
IFI 1405 - Augmented Reality: Proof of Concept	46%	54%	£	16,072	£	6,487	£	18,867	£	7,615	
IFI 1411 - eGenius	46%	54%	£	28,329	£	6,487	£	33,255	£	7,615	
IFI 1412 - Phase ID	46%	54%	£	10,396	£	6,487	£	12,204	£	7,615	
IFI 1413 - Portable RAFL	100%	0%	£	92,420	£	16,182	£	-	£	-	
IFI 1414 - PD-VMX	0%	100%	£	-	£	-	£	43,484	£	14,102	
IFI 1416 - ROAMES - LIDAR	46%	54%	£	106,320	£	6,487	£	124,811	£	7,615	
IFI 1417 - Keyhole Trenchless Technologies	46%	54%	£	145,630	£	12,865	£	170,957	£	15,103	

		SP	D			SPI	N	
Totals	External		Internal			External	Internal	
	£	1,301,011	£	446,942	£	1,728,504	£	462,461
Ratios	5 74% 26%		26%		79%		21%	

## Table A1: Overview of 14/15 projects showing application between licences

IFI Annual Report 2014/15



# Appendix B – Project Reports IFI Projects April 14 – March 15



Project Title	IFI 0401 STP 2 – Overhead Lines						
Description of project	A DNO research and development collaboration hosted by EA Technology						
Expenditure for financial year	Internal         £26,896           External         £54,339           Total         £81,235	Expenditure in (IFI) financial ye	previous ears	Internal External <b>Total</b>	£76,282 £439,67 <b>£515,9</b> 9	2 72 54	
Project Cost	£341,137	Projected 2015 for SPEN	/16 costs	Internal External <b>Total</b>	£0 £0 <b>£0</b>		
Technological area and / or issue addressed by project	The Module 2 programme for budget year 2014/15 aimed to improve operational performance, maximise potential benefits, improve financial performance, an minimise risk associated with overhead lines. A full list of projects and deliverable are available from SPEN or EA Technology.				ational e, and rables		
Type(s) of innovation	Incremental	Significant	Techr subs	nological titution	Radica	I	
involved	Yes	No		No	No		
Expected Benefits of Project Expected Timescale to adoption	If successful projects in this Module may increase the performance and reliability of overhead line networks Range 1-5 years - dependent on Duration of benefit once achieved				ndent		
	Bange 49-95% -	TRL	Developme	ent (Start – C	Current)		
Probability of Success	dependent on project	1 2 3	4	5 6	7 8	9	
Project NPV	(Present Benefits x Probability of Success) – Present Costs £42,652						
	With the decision mad undertaken in 2014/1 within this module as v	de to close STP at 5 have been cen vell as one new pr	t the end o tred on clo roject.	f DPCR 5 ar sing down a	nd IFI, the ac all existing pi	tivities ojects	
	Probabilistic Approach to Overhead Line Rating						
Project Progress March 2015	A test rig has been bu conductors over a ran determine a robust, applicable to UK distrik operation of the test ultimately lead to an u applicable to high volt Line Ratings).	ilt to monitor the ge of applied curr statistical metho pution networks. rig will continue of update of ENA AC age distribution s	temperatu rents and d odology for This STP pro under a new E 104 (deri ystems) and	res of a ran esign temper calculating oject is now w NIA proje ivation of ov d review of l	ge of overhea eratures in or g conductor complete, alt ct. The resu verhead line ENA P27 (Ove	ad line der to rating hough ts will ratings erhead	

٦



Г

Potential for achieving expected benefits	Over the course of DPCR5 Module 2 of STP has delivered a host of innovative projects, processes and techniques that the member DNOs can utilise to improve the management of overhead lines. A full list of projects and deliverables can be made available from SPEN or EA Technology.
Collaborative Partners	Other DNOs
R&D Providers	EA Technology



Project Title	IFI 0401 STP 3 -	- Cable N	letworks							
Description of project	A DNO research	n and dev	velopment	collabor	ration hos	sted b	y EA T	echnol	оду	
Expenditure for financial year	Internal £20 External £90 <b>Total £1</b>	6,896 4,663 <b>21,559</b>	Expenditi (IFI) finan	ire in pr cial yea	evious rs	Inte Exte <b>Tot</b>	ernal ernal <b>al</b>	f f f	89,485 518,44 6 <b>07,93</b>	7 2
Project Cost	£413,360	)	Projected 2015/16 costs for SPEN			Inte Exte <b>Tot</b> a	ernal ernal <b>al</b>	£0 £0 <b>£0</b>		
Technological area and / or issue addressed by project	The Module 3 programme for budget year 2014/15 aimed to improve operational performance, maximise potential benefits, improve financial performance, and minimise risk associated with cable networks. A full list of projects and deliverables are available from SPEN or EA Technology.									
Type(s) of innovation	Incrementa	Incremental Significant Technol substitu			nologi titutio	cal on		Radical		
involved	Yes		No			No		No		
Expected Benefits of Project	If successful projects in this Module may increase the performance and reliability of cable networks									
Expected Timescale to adoption	Range 1-2 yea dependent o project	ars - on	Duration o achieved	f benefi	t once	Raı	Range 3-5 years - dependent on project			
	Range 45-100	)% -	TRL Developme			ent (St	art – C	Current	)	
Probability of Success	dependent o project	on	1 2	3	4	5	6	/	8	9
Project NPV	(Present Benef Costs	its x Prol	bability of S	uccess)	– Presen	t	£42,0	13		
	With the decisi undertaken in within this mod	on mad 2014/15 ule as w	e to close have bee ell as one r	STP at t centre ew proj	he end o ed on clo ect.	of DPC sing	CR 5 ar down	nd IFI, all exis	the acti ting pro	vities ojects
	Improving the I	Perform	ance & Ma	nageme	nt of Cut	Outs				
Project Progress March 2015	This project investigated the reliability of service terminations, including failure modes, performance and asset management requirements. Several detailed recommendations have been made and the results will feed into a review of BS standard BS 7657:2010 – 'Specification for cut-out assemblies up to 100A rating, for power supplies to buildings'. This STP project is now complete, although some further long-term cut-out testing will continue under a new NIA project.									
Potential for achieving expected benefits	Over the cours projects, proces the manageme made available	e of DP sses and nt of cal from SP	CR5 Modu I technique ble networ EN or EA Te	e 3 of s that the s. A ful chnolog	STP has he memb I list of p gy.	delive er DN roject	ered a IOs ca ts and	host o n utilis deliver	of innov e to im ables c	vative prove an be



Collaborative Partners	Other DNOs
R&D Providers	EA Technology



Project Title	IFI 0401 STP 4 – Substations											
Description of project	A DNO research ar	d de	velopr	nent co	llabor	ation ho	osted b	y EA T	echnol	ogy		
Expenditure for financial year	Internal         £26,8           External         £77,4           Total         £104,	96 11 <b>307</b>	Expe (IFI)	enditur financi	e in pro al year	evious s	Inte Exte <b>Tot</b>	ernal ernal <b>al</b>	f f f	£77,995 £413,033 <b>£491,028</b>		
Project Cost	£345,174		Projected 2015/16 costs for SPEN				Inte Exte <b>Tot</b>	ernal ernal <b>al</b>	£0 £0 <b>£0</b>			
Technological area and / or issue addressed by project	The Module 4 pro performance, max minimise risk asso available from SPE	The Module 4 programme for budget year 2014/15 aimed to improve operational performance, maximise potential benefits, improve financial performance, and minimise risk associated with substations. A full list of projects and deliverables are available from SPEN or EA Technology.										
Type(s) of innovation	Incremental		Sig	nificant	;	Tech sub	inologi stitutio	cal on	Radical			
IIIvolved	Yes		No			No		No				
Expected Benefits of Project	If successful projects in this Module may increase the performance and reliability of substations											
adoption	dependent on project		achie	ved		once		on project				
	Range 30-95% -	_			TRL De	velopm	ent (S	ent (Start – Current)				
Probability of Success	dependent on project	-	1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits Costs	( Pro	babilit	y of Su	ccess)	– Presei	nt	£32,7	21	I	1	
	With the decision undertaken in 202 within this module	mad 4/15 as w	e to c 6 have vell as (	lose ST been one ne	P at th centre w proje	ne end d on cl ect.	of DP( osing	CR 5 ar down a	nd IFI, all exis	the act ting pr	ivities ojects	
	132kV Transforme	r Pos	st Mor	tems								
Project Progress March 2015	This project is now complete. The project carried out post-mortem examinations of 35 132kV transformers with a particular focus on relating mechanical strength of Low Voltage (LV) winding papers to transformer oil analysis and condition, in order to provide empirical evidence to establish a robust link between non-invasive tests and actual transformer condition. Based on this evidence, data thresholds have been modified to give a more accurate Health Index assessment. Greater confidence in the Health Index is expected to allow the serviceable life of 132kV transformers to be safely extended by between 5 or 10 years beyond their currently predicted End of Life (EOL).											

٦



Г

Potential for achieving expected benefits	Over the course of DPCR5 Module 4 of STP has delivered a host of innovative projects, processes and techniques that the member DNOs can utilise to improve the management of substations and their associated assets. A full list of projects and deliverables can be made available from SPEN or EA Technology.
Collaborative Partners	Other DNOs
R&D Providers	EA Technology



Project Title	IFI 0401 STP 5 – Networks for Distributed Energy Resources									
Description of project	A DNO research and de	evelopment co	llabora	ation hos	ted by EA T	echnolo	ogy			
Expenditure for financial year	Internal £0 External £0 Total £0	Expenditure (IFI) financia	e in pre al years	evious s	Internal External <b>Total</b> Internal	f f <b>f</b> f	78,709 458,450 5 <b>37,15</b> 9	0 9		
Project Cost	£349,243	for SPEN	015/16	o COSTS	External <b>Total</b>	£0 <b>£0</b>				
Technological area and / or issue addressed by project	The Module 5 program performance, maximis minimise risk associate of projects and delivera	The Module 5 programme for budget year 2014/15 aimed to improve operational performance, maximise potential benefits, improve financial performance, and minimise risk associated with networks for distributed energy resources. A full list of projects and deliverables are available from SPEN or EA Technology.								
Type(s) of innovation	Incremental	Significant Techno substi			ological itution		Radical			
involved	Yes	No		1	No	No				
Expected Benefits of Project Expected Timescale to adoption	If successful projects in of networks for Distribu Range 1-3 years - dependent on project	If successful projects in this Module may increase the performance and reliability of networks for Distributed Energy resources           Range 1-3 years - dependent on         Duration of benefit once achieved         Range 2-5 years - dependent								
	Range 51-100% -	1	rrl De	velopme	ent (Start – Current)					
Probability of Success	dependent on project	1 2	3	4	5 6	7	8	9		
Project NPV	(Present Benefits x Pro Costs	bability of Suc	cess) -	– Present	£28,8	41				
Project Progress March 2015	With the decision mac undertaken in 2014/1 within this module.	de to close STI 5 have been c	P at th centree	ne end of d on clos	f DPCR 5 ai sing down	nd IFI, all exis	the act ting pro	ivities ojects		
Potential for achieving expected benefits	Over the course of DI projects, processes and the management of deliverables can be ma	PCR5 Module d techniques t distributed er de available fr	5 of S hat th hergy om SP	STP has one member resource EN or EA	delivered a er DNOs ca s. A full l Technology	host on utilise n utilise ist of p y.	of innov e to imp projects	vative prove and		
Collaborative Partners	Other DNOs									
R&D Providers	EA Technology									



Project Title	IFI 0507 – Sensor Networks (Smart Dust) – Phase 2									
Description of project	<ul> <li>"Smartdust" is a concept developed by the University of California that is based on a self-configuring wireless sensor network, capable of transmitting low bandwidth information in a series of short hops. Data acquired and transmitted from sensors is relayed through a gateway for data interpretation. SPEN led a feasibility study into the use of this technology for detecting the passage of fault currents on 11kV overhead line networks.</li> <li>Following on from this work, a collaborative project has been scoped between EDF Energy, Central Networks and SPEN to develop a product based on this principle for the remote signalling of fault passage indication on overhead line networks.</li> </ul>									
Expenditure for financial year	Internal         £47,492           External         £12,488           Total         £59,980	Internal External <b>Total</b>	£113,741 £231,882 <b>£345,623</b>							
Project Cost (Collaborative + external + SPEN)	Phase 1 = £16k Phase 2 = £191k	Projected 15/16 co SPEN	osts for	Internal External <b>Total</b>	£0 £0 <b>£0</b>					
Technological area and / or issue addressed by project	This project considers indication data. A centreduce the time requir Customer Minutes Loc especially suited to trans Significant analysis has GSM/GPRS Fault Pass Distribution fault histor cost, deployment penetthat a cheap, low power • Allows a much than any othe • Offers SPEN a Owing to these factors, (from 10% for GSM de likelihood that they w performing circuits).	<ul> <li>This project considers a cheap and reliable method of collection of fault passage indication data. A centralised location for overhead line faults would significantly reduce the time required to resolve faults on the network and consequently reduce Customer Minutes Lost (CML) associated penalties. This technology would be especially suited to transitory fault location.</li> <li>Significant analysis has been undertaken on the deployment characteristics of GSM/GPRS Fault Passage Indicators Vs Radio communicating sensors, using SP Distribution fault histories. The analysis considering the relationship between sensor cost, deployment penetration and improvement to CML figures. The key conclusion is that a cheap, low power semi-mesh radio based system:</li> <li>Allows a much higher percentage of locations of be monitored economically than any other option, across all price points and time savings</li> <li>Offers SPEN a much higher NPV than any other option</li> <li>Owing to these factors, a significantly higher percentage of network can be monitored (from 10% for GSM devices to above 70% coverage for radio sensors), increasing the likelihood that they will be targeting faults (rather than solely focussing on worst performing circuits)</li> </ul>								
Type(s) of innovation	Incremental	Significant	Techi subs	nological stitution	Radical					
Involved	No	No		No	Yes					
Expected Benefits of Project	Sensor Networks implemented as a method of fault passage indication (FPI) could have an enormous effect on how faults on the overhead network are located. They could have a huge impact on CI/CML figures as the technology would be effectively pin pointing faults on the network. This results in a significant financial saving and improved customer service. The low power radio communication option will allow for greater flexibility on remote networks where traditional communications may not be viable due to poor coverage or service strength.									



Expected Timescale to adoption	5 Years	Duration of benefit once achieved				10 Years								
			Т	RL Dev	velopm	pment (Start – Current)								
Probability of Success	75%	1	2	3	4	5	6	7	8	9				
								>						
Project NPV	(Present Benefits x Probability of Success) – Present £554.5k Costs													
Project Progress March 15	A working prototype has been extensively tested on site on a poorly performing circuit in West Lothian. Following the full deployment and initial tests, several software and hardware changes were implemented designed to improve the reliability and consistency of the communications. The upgraded system has been extensively tested although it has not operated due to a fault on the system.													
Potential for achieving expected benefits	This new approach will allow within 1km, and hence rapidly allow linesmen to be sent direc having to patrol long lengths of a reduction in CML for perma the source of transient fault a the longer term, this system sent to specific wFPI locations.	v contr deduc ctly to of overl nent fa activity can be	ol eng e the l the aff nead n aults, i that o come	gineers best su fected tetwor t will r can car duples	s to ic ipply r area t k. Whi more i use m x, allo	lentify estora o inves ilst the mport ultiple wing c	the lo tion strigate overal antly b supply ontrol	rategy. the fai ll effec e able intern comm	of a It will ult, wit t shou to cap ruptior ands t	fault also hout ld be oture ns. In o be				
Collaborative Partners	WPD													
R&D Providers	Willow, E.ON Power Technolog	gy												



Project Title	IFI 0509 – Superconducting Fault Current Limiter										
Description of project	This project aims Current Limiting (SF	to desig CL) devic	n, dev ces on t	elop an three di	id tria fferen	al three it UK ne	e 12 etwo	kV Sup rks.	ercond	ucting	Fault
Free en eliterne fere	Internal £14,1	.02	<b>F</b>				I	nternal		£91,84	7
Expenditure for financial year	External £6,65	9	Exper (IFI) fi	iditure i nancial	n prev vears	vious	E	External		£474,1	93
	Total £20,7	61	()	nunciui	years		٦	Fotal		£566,0	42
Project Cost			Projected 15/16 costs for SPEN			1	nternal		£0		
(Collaborative +	£2,345,967					313 101	E	External		£0	
external + SPEN)							٦	Fotal		£0	
	The development series with a circuit	of a no breaker	n-linea for the	r 'high- clampii	-temp ng and	erature d cleara	e'su nce	percono of fault	ducting energy	ceram	nic in
Tashnaloziaslaraa	When the material is operated at below its critical temperature it loses all electrical resistance, thereby allowing load current to flow with negligible losses. Either the increased current density caused by fault current, or the loss of cooling medium (liquid nitrogen) causes the temperature of the superconducting material to rise and it reverts to a normal resistive state.										trical r the dium and it
Technological area and / or issue addressed by project	Being a solid state device, the SFCL has been proven to operate in a few milliseconds, after which the impedance remains high until the fault is cleared by conventional means (protection operated circuit breakers, fuses, etc.). The SFCL's operation is sufficiently fast to ensure that the first peak of the fault current is limited. The subsequent limited current can be set to suit a specific application.										
	Three devices (one applications: transf successful complet devices.	e per DN ormer ta ion of tl	O) will iils, bus his pro	be con sectior ject is	istruc n, inte likely	ted and erconne to pay	l ins cted ve th	talled c networ ne way	overing k conn for hig	g a ran ection. gher vo	ge of The Itage
Type(s) of innovation	Incremental	Si	gnifica	nt	Т	echnological substitution			Radical		
involved	No		Yes			No	)			No	
	To develop, unders 11kV fault current l	tand and imiting d	d addre evice t	ess the i o the ne	ssues etworl	associa k.	ated	with th	e conn	ection	of an
Expected Benefits of Project	Successful trials wil are capable of clam will open up anoth alternative to netw	l result in ping faul er optior ork reinfe	n the d It levels n for ta orceme	levelopr s to with ickling r ent.	nent nin ne netwo	of com twork c rk fault	merc lesig : leve	cially ava n limits. el, poter	ailable Once ntially	devices proven providir	s that I, this ng an
Expected Timescale to Adoption	3 years		Dura <sup>.</sup> achie	tion of t ved	oenefi	t once			20 ye	ars	
				TI	RL Dev	velopm	ent (	Start –	Current	t)	
Probability of Success	75%		1	2	3	4	5	6	7	8	9
-				•				I	$\geq$		
	(Drocont Ponofita y	Drobabi	ity of C			Droi	oct N	£-26	7,191	due te	the
Project NPV	Present Costs	FIUDADII	ity OI S	uccess)	-	PIOJ	low .	TRL / hi	gh cost	s upon	ne
								comme	nceme	nt	

1



Project Progress March 15	This project was effectively reported as being closed in the 2013/14 IFI Report, with only recovery of the SFCL planned for 2014/15. As of March 2015 the SFCL is yet to be recovered from site, any subsequent costs incurred removing the unit and having it recycled will be done outside of IFI.
Potential for achieving expected benefits	As reported in 2013/14, through undertaking this pilot trial SPEN has gained valuable knowledge and experience that has influenced our future strategy for the deployment of fault current limiting technology. At this time however it is unclear if fault current limiting technology will be readily adopted and this is largely down to the size, cost and complexity of the lifetime ownership of the systems presently available on the market. This project has been instrumental in encouraging the development of fault current limiting systems for the UK market, there are now several units available and either on trial or adopted as BaU by other UK DNOs.
Collaborative Partners	Electricity North West, Northern Power Grid, Applied Superconductor Ltd
R&D Providers	Applied Superconductor Ltd



Project Title	IFI 0515 – Power Network Demonstration Centre (PNDC)										
Description of project	Development of a f ground for active ne Whilst not a techno of technology, with developments acros	Development of a full scale 11kV and LV prototyping network as a test-bed / proving ground for active network management techniques and other 'high risk' technologies. Whilst not a technological development in itself, this project is a fundamental enabler of technology, with significant potential to accelerate adoption of significant / radical developments across a range of IFI projects.									
Expenditure for financial year	Internal£21,0External£45,0Total£67,0	990 527 <b>517</b>	Expenditure previous (IFI years	in ) financial	Internal External <b>Total</b>	£71,795 £532,853 <b>£604,648</b>					
Project Cost (Collaborative + external + SPEN)	£7,200,000		Projected 15/16 costs for SPEN		Internal External <b>Total</b>	£0 £0 <b>£0</b>					
	In partnership with	collabora	tors, this proje	ect aims to:							
	<ul> <li>Provide a demo 'real' network</li> </ul>	onstratio	n network to	allow the t	esting of nev	w technologies on a					
Technological area and / or issue addressed by project	• Offer a real network that will incorporate 11kV and low voltage equipment, containing real loads, real generation and test real technologies										
	<ul> <li>Create a facility which will be open to Academia, R&amp;D Establishments, Manufacturers, and Network Operators</li> </ul>										
	The vision is to create a physical scale model that can represent different urban, suburban and rural electrical networks. The proposed system will incorporate real network components: cables, overhead lines, switchgear, transformers, protection and control equipment, in order to ensure it is both representative and credible to the real thing. Real Time Digital Simulators (RTDSs) will be used in parallel to model an underlying, more comprehensive network, effectively expanding the scale of the system.										
	Technologies coming more prominently into play over the next 15 years, e.g. micro- generation, storage, fault current limiters, etc., will be included on the test network so as to test their effect, and vice-versa, on distribution systems.										
Type(s) of innovation	Incremental	Sig	nificant	Techno subst	ological itution	Radical					
Involved	Yes		Yes	Y	es	Yes					
	Benefits to DNOs fro	om such a	a facility includ	le:							
	<b>Safety</b> – A test network with dedicated staff will offer a facility to train staff in the operation of a more complicated network. Specific what-if scenario courses can be run through repeatable simulation, in the same manner as flight simulators are used to train pilots.										
Expected Benefits of Project	<b>Risk mitigation</b> – A and microGen will in manage the increase	v real tim ndicate th ed risk th	e simulator, v ne technologie is might pose	with likely es that will to the netw	penetrations need to be d vork and/or c	of high volume DG eveloped in order to our customers.					
	Acceleration of trials / increased adoption rate – The ability to operate the whole network through a vast range of loading conditions in a short period of time, will lead to the end of long duration (12-24mth) network trials of new technologies.										



Expected Timescale to adoption	1 Years	Durat once	tion of achiev	benefit ed	t	20 Years						
Probability of				TRL De	velopn	nent (	Start – C	Current	:)			
Success	90%	1	2	3	4	5	6		8	9		
Project NPV	(Present Benefits x Probability of Success) – Present Costs £709,171											
	Activity April 2014 - March 2015 Working with fellow PNDC members SPEN have undertaken several projects under 5											
Project Progress March 15	<ol> <li>Asset Management         <ul> <li>Tower condition a</li> <li>Asset data collecti</li> </ul> </li> <li>Network &amp; Demand Sii         <ul> <li>Dynamic LV networe</li> <li>Evaluation of emb</li> </ul> </li> <li>Power Electronics &amp; Di         <ul> <li>Demonstration of</li> </ul> </li> <li>Protection &amp; Control         <ul> <li>Development of a</li> <li>1kV and 33kV ne</li> <li>Investigation into</li> <li>Testing of fault pa</li> <li>Testing of locomo</li> </ul> </li> <li>Sensors &amp; Measureme         <ul> <li>Development of a</li> <li>Testing Tollgrade</li> </ul> </li> <li>Following on from the en generate proposals that h         <ul> <li>technologies to the UK D</li> <li>either funded as Business a</li> <li>that are fully compliant with</li> </ul> </li> </ol>	a soluti tworks SEF pro ne mor ssage i tion SA ents metho Lightho NOs, h as Usua ch any a	ent estigati nageme se reba genera ed Ene quality ion for on for otection ndicato Sensor dology ouse Se i the I progro oweve al (BaU	on ent alancin ition ex rgy Res rissue	g (port lin sources associ tomation function function asure N Core Rice e develor of the ll be re ing me	mitors ated verhe ic det on /T free propo	s with PV ad line ection c ch them ent and osals tak red as a sms, e.g	grid pe (OHL) of live respon nes wil integr ken for standa . NIA, f	enetrati collisic cross a se I contir ation o rward v alone pr VIC.	on In and Irms in Inue to of new will be rojects		


Potential for achieving expected benefits	During 2014/15 SPEN has been able to utilise the unique test environment at the PNDC to expedite the development and delivery of new technology to our network. SPEN utilised the PNDC for the IFI projects listed below, in doing so proven the benefit of the PNDC to the UK. IFI 1209 Substation Earth Integrity Monitoring System: For this project the PNDC was utilised to carry out a trial installation of the Cresatech Copper Theft System (CuTS) and several simulated theft events to prove the unit was fit for purpose. In doing so both SPEN and Cresatech were able to address practical issues encountered during the installation ahead of rolling out the solution to the network. Subsequently a live demonstration was given to internal stakeholders to demonstrate the devices performance which resulted in a business buy-in to proceed to a field trial of 80 CuTS units. IFI 1404 Urban NCP Enhancements For this project the PNDC was utilised to develop and deliver a test programme to assess the performance of Nortech's Directional Fault Passage Indicators (dFPIs). Through this test programme SPEN were able to gain sufficient confidence in the performance of the dFPI to progress to field trials. IFI 1308 HTIP For this project the PNDC was utilised to develop and deliver a test programme to assess the performance of HTIP's Voltage Optimiser (VO). Through this test programme SPEN and HTIP were able to identify a number of areas where the VOs performance needed to be enhanced prior to field trials being undertaken.
Collaborative Partners	Scottish & Southern Energy, Scottish Enterprise and University of Strathclyde
R&D Providers	See Collaborative Partners



Project Title	IFI 0615 – ScottishPowe	r Advanced	Resear	ch Ce	ntre (S	SPAR	C)				
Description of project	<ul> <li>Asset Engineering: Field based activities, concentrating on the technologies used to gather and interpret data then control and manage individual assets.</li> <li>Asset Strategy: Office, desktop, PC based analytical activities including the analysis of data, concentrating on underlying trends of asset populations (from asset ageing to network performance).</li> <li>System Development: Forward looking network design activities considering the connectivity between the assets. It should consider both the medium term (5 years) and longer-term trends (&gt;10 years), which will affect the design of the network (e.g. load, generation, standards, regulations, Ofgem incentives/penalties).</li> <li>A number of related projects have been developed within each work stream.</li> </ul>										
Expenditure for financial year	Internal         £18,654           External         £147,409           Total         £166,066	9 Exper (IFI) f	nditure i inancial	in pre years	evious s		Intern Exterr <b>Total</b>	al Ial	£52 £86 <b>£92</b>	,311 9,76! <b>2,07</b> (	5 6
Project Cost (Collaborative + external + SPEN)	£460,083	cted 15/16 costs for N			or	Internal External <b>Total</b>		£0 £0 <b>£0</b>			
Technological area and / or issue addressed by project	<ul> <li>Asset Engineering research stream focuses on methods and technologies that enable better use of individual assets.</li> <li>Asset Strategy research stream focuses on methods and tools that enable better management of populations of assets.</li> <li>System Development research stream focuses on analytical techniques that</li> </ul>						that tter that				
	Incremental	Significa	nt	1	Fechno substi	ologio itutio	gical Radical			al	
lype(s) of innovation involved	No	Yes		No		lo			No		
Expected Benefits of Project	Research activities will including system perfor the SPARC proposal, wh programme of deliverab	seek to re mance, OPI ich are bein le projects.	ealise b EX and g used t	usine CAPE to for	ss be X. Ke m the	nefit y are basi	s acros eas hav s of a i	ss a ra ve bee more c	ange n ider ompre	of a ntifie ehen	reas d in sive
Expected Timescale to adoption	3 Years		Durati once a	ion of achiev	f bene <sup>.</sup> ved	fit		10	Years		
Probability of Success	Varies per proje	ect	1	TRL 2	Devel 3	opm 4	ent (St 5	art – C	urrent 7 >	:) 8	9
Project NPV	(Present Benefits x Prob Success) – Present Costs	TBC In development for the core projects in each work stream									



Project Progress March 15	<ul> <li>'Asset Technology' Theme: Develop an intelligent decision support system for overhead line fault prognosis utilising available Pole Mounted Auto-Reclosers (PMAR) data.</li> <li>This research assesses the feasibility of data mining techniques to identify 'interesting' data patterns and trends that are indicative of anomalous current activity, and where possible distinct modes of network behaviour representative of specific network defects (e.g. cracked insulators). The initial feasibility study is being taken forward as a PhD research project.</li> <li>Two tools have been developed to support the identification and diagnosis of fault events.</li> <li>An Anomaly Detector analyses SCADA alarm data stored in a SP Energy Networks database in order to identify circuits and periods of time for which there are frequent unsolicited circuit breaker openings. This guides the selection of PMARs of interest for more detailed analysis</li> <li>A PMAR Data Visualisation Tool extracts data from PMAR sources, and derives and presents information about fault behaviour based on an analysis of previous PMAR data associated with protection activity and unsolicited openings.</li> <li>On the basis of this work, trends and patterns in transient event data are now being analysed to identify means of predicting the nature of a subsequent permanent fault, as well as how soon it is likely to occur.</li> <li>A conference paper ("Automatic analysis of pole mounted auto-recloser data for fault prognosis to mitigate customer supply interruptions") has been presented at the 2014 Universities Power Engineering Conference. A paper has been submitted to the 2015 Intelligent Systems Application to Power Systems (ISAP2015) conference.</li> </ul>
Potential for achieving expected benefits	The 'Fault prognosis utilising available Pole Mounted Auto-Reclosers (PMAR) data' PhD will enable SP to predict and classify future fault activity to allow maintenance staff to take appropriate preventative action; and ultimately improve network reliability, protect expensive plant, reduce the number and duration of outages, and improve customer service, avoiding regulatory penalties arising from unplanned network interruptions. Key SPEN personnel have been engaged at technical and strategic levels though regular project meetings and SPARC strategy meetings to ensure that research is progresses along the TRL development scale towards deployment within the organisation. In addition, a key function of these strategy meetings (involving all SPARC personnel, and held bi-annually) has been to ensure that the pipeline of prospective research projects is maintained and that they remain relevant to the strategic objectives of SPEN. This project is now closed. Project outcomes will be reviewed upon completion of the Closed Down Report.
Collaborative Partners	N/A
R&D Providers	University of Strathclyde



Project Title	IFI 0621 – 3 Live Alert/Energised Alert									
Description of project	<ul> <li>The Energised Alert is a high voltage detection device, currently capable of detecting voltages of above 2kV. The project's objectives are to:</li> <li>To extend the voltage sensing range downwards from 2000 Volts</li> <li>To undertake a full market appraisal</li> <li>To undertake full evaluation of technology whilst in operation</li> <li>This project aims to take the Energised Alert from TRL4 to 8.</li> </ul>									
	Internal £14,102	_				Inte	ernal	£	33,344	
Expenditure for financial	External £11,684	Expe	Expenditure in prev			Ext	ernal	£37,811		
year	Total £25,786	(111)	manci	ai yeai	3	Tot	al	£	71,155	
		Duci		01 5 /1	Casata	Inte	ernal	£	0	
Project Cost	£ 65,815	for 9	ectea 2 SPEN	015/1	6 COSTS	Ext	ernal	£	0	
						Tot	al	£	0	
Technological area and / or issue addressed by project	The Energised Alert senses any increase in electrical potential, above a predetermined threshold, of devices to which it is attached. Once triggered it is linked to an audible alarm, allowing the recognition and management of this potentially deadly hazard in a controlled manner. Its use will, therefore protect the operator, other employees and any members of the public in the vicinity from casual, but more importantly, avoidable electrocution.									
Type(s) of innovation	Incremental	Incremental Significant Techi subs					Technological substitution			
Involved	No	Yes				No	No			
Expected Benefits of Project	<ul> <li>Successful development of the Energised Alert would:</li> <li>Help prevent electrocution accidents and fatalities</li> <li>Ensure 'live line' maintenance can be carried out in a safe manner</li> <li>Allow operators to proactively respond to incidents on their network</li> </ul>									
Expected Timescale to adoption	1 Year	Durat achie	tion of l ved	penefit	tonce			25 Yea	rs	
				TRL De	velopme	ent (S	tart – C	(urrent		
Probability of Success	75%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Pro Costs	babilit	y of Suc	ccess) -	– Present	t	-£49,4	120		
Project Progress March 2015	Stage Four extension prototype units ready f Stage Five was added t now been cancelled du	was a or live o the p e to th	greed a trials. project o e IFI fur	and ha during nding c	the stag	been e 4 ex	comple	eted; t n; how	here a	re 10
	This project is now clos	ed.								
Potential for achieving expected benefits	The project is on target	to ach	ieve th	e expe	cted ber	efits.				
Collaborative Partners	Northern PowerGrid, E	lectrici	ty Nort	h West	t, SSE					
R&D Providers	Live Alert									



Project Title	IFI 0701 – ENA IFI Projects											
Description of project	The Energy Netwo Several projects ha funded through the	he Energy Networks Association (ENA) represents all the UK network operators. Several projects have been initiated by the ENA R&D Working Group and have been unded through the IFI.										
- 10	Internal	£14,102	Expe	nditure	e in		Inter	nal	£3	32,224		
Expenditure for	External	£53,946	previ	ous (IF	I) finar	ncial	Exter	nal	£9	96,000		
iniariciai year	Total	£68,048	years	5			Total		£1	128,22	4	
							Inter	nal	£C	)		
Project Cost	c£50,00	0	Proje	cted 2	015/16 FN	0	Exter	nal	£C	£0		
				101 51			Total		£C	)		
Technological area and / or issue addressed by project	The projects listed I groups as significar number of projects that reason these p <b>Reactive Power (RI</b> managing voltage I shown that the roo to active power. W the last 5 years, re 2012 show that th better understand to plan for addit understanding of th <b>DS2030:</b> The DECC/ and Climate Change low carbon, afforda Smart Grid Forum challenges as they p Grid Forum has es aspects of future ne	The projects listed below address issues which have been identified by the ENA working groups as significant – requiring technical investigation and development. There are a number of projects that have been completed and reported in previous IFI years and for that reason these projects are not reported here. <b>Reactive Power (REACT)</b> : In the last 2 years, there have been significant difficulties in managing voltage levels during minimum demand periods. Analysis of this issue has shown that the root cause is related to the significant decline in reactive power relative to active power. Whilst minimum active power demands have fallen by around 15% in the last 5 years, reactive power has declined by 50% in this time. Current trends for 2012 show that this reduction is continuing, broadly, across the country. In order to better understand the challenge of manage voltage levels within licence standards and to plan for additional future reactive compensation requirements, a thorough understanding of the reactive power trend needs to be developed. <b>DS2030:</b> The DECC/Ofgem Smart Grid Forum was created by the Department of Energy and Climate Change (DECC) and Ofgem to support the UK's transition to a secure, safe, low carbon, affordable energy system. The main issue discussed within the DECC/Ofgem Smart Grid Forum is how electricity network companies will address significant new challenges as they play their role in the decarbonisation of electricity supply. The Smart Grid Forum has established a number of Work Stream (WS) to examine particular										
Type(s) of	Incremental	Si	gnifica	int	Te s	echno substit	logical ution		R	adical		
innovation involved	Yes		Yes			N	D			No		
Expected Benefits of Project	These projects have the potential to provide a wide range of benefits. In some cases, they will help to understand developing network related issues and allow design and operations to be altered to address them. In other cases they will allow us to better understand risks to our network.											
Expected Timescale to adoption	1 - 10 Yea	ars	Dura once	ation o e achie	f benef ved	fit		10	– 20 Ye	ears		
				Т	RL Dev	elopm	ent (S	tart –	- Curren	t)		
Probability of Success	25 - 759	%	1	2	3	4	5	6	7	8	9	
									$\geq$			



Project NPV	(Present Benefits x Probability of Success) – Present Costs	£100,000						
	<b>Reactive Power (REACT):</b> The objectives corresponding to the First Year Report Stage 1 and the Second Year Six-month Report have been met within the last 12 months and the corresponding reports delivered. Two additional brief project status reports have also been delivered.							
	It is important to highlight that the project was initially planned to start in May 2013 but it actually did in August 2013. The Second Year Final Report Stage 2 is on track and will be completed by August 2015.							
	The outcomes of the project are in accordance with the initial objectives of the project proposal. More specifically, the following tasks have been accomplished:							
	<ul> <li>Identification of historic r</li> <li>Quantification of effect: different distribution-bas network changes, penetr</li> <li>Assessment of future rea of different DNOs.</li> </ul>	network and demand changes and trends. s on reactive demand during minimum load from ed factors (i.e., demand trends in primary substations, ation of photovoltaics). active demand at transmission-distribution interfaces						
	<ul> <li>Production of improved network models, which unlike original DNO models mimic transmission-distribution interfaces during periods of minimum load, to be used for further studies</li> </ul>							
Project Progress March 15	<b>DS2030:</b> Works during the second half of 2014 focussed on defining the four representative networks that will be used for the study and the future scenarios that will be applied. The base networks were finalised and agreed in November 2014 and, following additional development work, the scenarios were finalised in early 2015.							
	In addition, an international review was conducted to capture learning from work in other countries and this was concluded in September 2014. An updated version will be produced towards the end of the study to ensure any more recent work is identified.							
	Towards the end of 2014, the ker reviewed. Minor revisions were February 2015.	y questions the DS2030 project aims to answer were agreed with the project Steering Group and WS7 in						
	Since the start of 2015, efforts have be used in the network analysis st papers which were reviewed and largely concluded and studies are	ve focussed on defining the detailed methodologies to tudies. These were presented as a series of discussion agreed by the Steering group and WS7. This stage is now commencing.						
	Both projects have been transitior	ned to the NIA scheme.						
	Further information is available at	the Smarter Networks Portal, please see links below						
	http://www.smarternetworks.org	/Project.aspx?ProjectID=1460#project-details						
	http://www.smarternetworks.org	/Project.aspx?ProjectID=1623#downloads						



	<b>Reactive Power (REACT):</b> The objectives corresponding to the First Year Report Stage 1						
	and the Second Year Six-month Report have been met within the last 12 months (May						
	2014 to May 2015) and the corresponding reports delivered. Two additional brief						
	project status reports have also been delivered. The progress on the project includes:						
Potential for achieving expected	<ul> <li>The methodology to improve original DNO network models in order to mimic in time-series simulations the GSP behaviour during periods of minimum load.</li> <li>The identification of historic changes and trends using DNO network and monitoring data.</li> <li>The quantification of effects on reactive power from PV penetrations, network changes and demand trends in primary substations.</li> <li>The assessment of future reactive demand at GSPs of 4 DNOs for different trend-based scenarios.</li> </ul>						
	<b>DS2030:</b> The DS2030 project is expected to achieve its intended benefits. It will provide a set of generic nodal distribution network models that have been demonstrated to be						
benefits	technically viable to meet the needs of 2030 users. These models have now been						
	developed and their viability will be demonstrated in the coming months.						
	The models will be used to show how specific methods/solutions can be used to ensure technical viability of the networks and when particular methods/solutions may need to be applied. This analysis will be provided in the Stage 4 &5 results report.						
	The final Stage 6 report for the project will use the outcomes of the studies to address the questions posed by the Smart Grid Forum about future distribution system operation, including a discussion of the roles and responsibilities of a DNO in 2030 in terms of supporting whole system optimisation, contrasted with the position today.						
	Where appropriate this will highlight further specific development work that could be carried out						
Collaborative	National Grid; SPEN; Scottish and Southern Energy; Electricity North West: Western						
Partners	Power Distribution and Northern Power Grid						
	TNEI; Engage Consulting Limited; Imperial College London; Met Office;						
R&D Providers	EA Technology Ltd (and partners); Earthing Solutions; KEMA and Redpoint Energy;						
	Inertek; CAPCIS.						



Project Title	IFI 1004 – Remote A	IFI 1004 – Remote Access to Pole Mounted Auto Reclosers									
	The Noja pole mou MPM, which can be protection activity a	nted aut e access nd statis	to reclo ed to r stical m	oser (PI retrieve etering	MAR) i e activ g.	ncorpo e and	orates histor	a prote ical dat	ection i a relat	module ing to	e, the both
Description of project	This can only be a mounted below the climber. Access to t advantage if addition to ascend the pole.	This can only be accessed via an RS232 port within the Noja Control Panel that is nounted below the Main Tank, out with the Safety Distance, and above the Anti- limber. Access to this panel requires a specialist skill. It would a business and safety idvantage if additional functions of this equipment could be accessed without having o ascend the pole.									
	remote access of the data within a Noja would be possible.							rtoju,			
	Nortech has proved in an operational sit	that the uation.	e ENVO	Y can t	alk to	the NC	JA, bı	ut this n	eeds t	o be pr	oved
Expanditura for	Internal £25,3	58	Evnon	dituro	in nro	vious	Ir	nternal	i	E49,70	5
financial year	External £6,65	9	(IFI) fi	nancial	years	vious	E	xternal	i	E40,90	7
,	Total £32,0	18	· ·				Т	otal	ł	E90,61	2
Project Cost		Projected 15/16 costs for				lr	nternal	t	EO		
(Collaborative + external + SPEN)	£76,800		SPEN			E	External		EO EO		
								otai	1	EU	
Technological area and / or issue addressed by project	The project aims to address the issue of safe and automated remote access to active and historical data from SPEN's population of Noja PMAR. The project will enable circuits to be ranked accordingly to agreed performance indicators e.g. circuits with most trips which could inform operational and							active nance and			
Type(s) of innovation	Incremental	Si	gnifica	nt	L I	Techno substit	logica ution	I	R	adical	
involved	Yes		No	No N			No			No	
Expected Benefits of Project	<ul> <li>Health and Safety benefit realised by negating the need to climb PMAR poles to access information</li> <li>Automatic collection of all Noja PMAR event logs, removing the need to drive to site and consequent delays in getting data</li> <li>Summary analysis of PMAR activity with dashboard showing league table of operations</li> <li>Central storage of event logs</li> </ul>										
Expected Timescale to Adoption	3 years		Durat achie	tion of ved	benefi	t once			10 yea	ars	
				1	RL De	velopm	ient (S	Start – C	Current	)	
Probability of Success	90%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – £343,820 Present Costs										



Г

Project Progress March 15	Development of a browser dashboard has enabled a summary of the available data is in use and has introduced additional features that have been added at the request of operation users. The Dashboard can be configured to provide for automated alerts, by either email or text message, for user defined parameters or conditions arising. This project is now closed.
Potential for achieving expected benefits	The Envoy units are installed in the field on an as-required basis by the districts with key staff trained to install, commission, and analyse the recovered data. There have been many successes from using this equipment to monitor transient activity that is all too often very difficult to determine the cause. Having access to Envoy data in almost real time allows the field crews to be directed to possible fault locations knowing the actual affected phase and level of fault current that has passed, is a good start to identifying the cause.
Collaborative Partners	None
R&D Providers	Nortech



Project Title	IFI 1102 – Energy Stor	IFI 1102 – Energy Storage Project								
Description of project	The aim of this project smart grids. The need to investigat governmental level. T (PRASEG) inquiry into storage as a 'possi generation' and high development' and 'cle Low Carbon Transition of key elements of a l	The aim of this project is to investigate the role of energy storage systems (ESS) in smart grids. The need to investigate the role of electrical energy storage has been identified at governmental level. The Parliamentary Renewable and Sustainable Energy Group PRASEG) inquiry into 'Renewables and the grid: access and management' cites storage as a 'possible solution for addressing variable renewable energy generation' and highlights the need for 'Long term, further research and development' and 'clear political and regulatory signals' (PRASEG, 2010). In the UK Low Carbon Transition Plan (HM Government, 2009) storage is included in the list								
Expenditure for financial year Project Cost	Internal         £14,861           External         £11,119           Total         £25,980           £326,000	Expe (IFI) Proj	enditur financi ected 2	e in pre al year 015/16	evious s 5 costs	Internal Externa <b>Total</b> Internal Externa		f f <b>f</b> f	29,147 61,677 <b>90,824</b> 0 0	
		tor :	for SPEN			Total		£	0	
Technological area and / or issue addressed by project	<ul> <li>Economic assessin</li> <li>Identification of a</li> <li>Consideration of systems</li> <li>Determine approp</li> <li>Understand the estorage systems</li> <li>Evaluate the curr to generate reven</li> <li>Investigate the resystems by DNOs</li> </ul>	<ul> <li>Economic assessment with respect to traditional reinforcement options</li> <li>Identification of appropriate locations for energy storage systems</li> <li>Consideration of most appropriate sizes and capacities for energy storage systems</li> <li>Determine appropriate operating strategies for energy storage systems.</li> <li>Understand the effects of operating strategies on the ageing of the energy storage systems</li> <li>Evaluate the current and future value of operating an energy storage system to generate revenue through energy market arbitrage</li> <li>Investigate the regulatory issues surrounding the ownership of energy storage systems by DNOs</li> </ul>								
Type(s) of innovation	Incremental	Sig	nificant	Ī	Tech subs	nological titution			Radical	
	Yes		Yes			Yes			No	
Expected Benefits of Project	Produce learning outcomes and decision support information which can be disseminated within the DNO community which will enable the cost effective and beneficial adoption of energy storage systems.									
Expected Timescale to adoption	3 Years	Durat achie	tion of l ved	penefit	once			20 Yea	rs	
			1	TRL De	velopme	ent (Start ·	- Cı	urrent		
Probability of Success	50%	1	2	3	4	5 6	>	7	8	9



Project NPV	(Present Benefits x Probability of Success) – Present Costs	Not known at this stage						
	Recent outputs have been produced in a number of a below.	Recent outputs have been produced in a number of areas and are summarised below.						
	Papers produced on the decisions and influencing factors that determine sizing and location of electrical energy storage systems:							
	Crossland AF, Jones D, Wade NS. Planning the locatio energy storage in LV networks using a genetic annealing. <i>International Journal of Electrical Power</i> & 103-110.	Crossland AF, Jones D, Wade NS. Planning the location and rating of distributed energy storage in LV networks using a genetic algorithm with simulated annealing. <i>International Journal of Electrical Power &amp; Energy Systems</i> 2014, 59, 103-110.						
	Anuta OH, Barteczko-Hibbert C, Wade NS. Future low carbon technologies, impacts and energy storage solutions on UK distribution networks. <i>CIRED workshop</i> 2014, Rome.							
	Paper on the ageing considerations which must be incloperating energy storage systems:	Paper on the ageing considerations which must be included when deploying and operating energy storage systems:						
Project Progress March 2015	Wang L, Liang DH, Crossland AF, Taylor PC, Jones D, Wade NS. Coordination of Multiple Energy Storage Units in a Low Voltage Distribution Network. <i>IEEE Transactions on Smart Grid</i> 2015.							
	Paper with potential application of energy storage looking at the present day but also at likely future changes:							
	Crossland AF, Wade NS, Jones D Extraction of 9,163 real LV network models from DNO GIS database to assess overvoltage from PV and consequent mitigation measures. <i>CIRED</i> 2015, Lyon.							
	Paper with recommendations for how the regulatory regime could be changed to facilitate the cost effective adoption of energy storage systems:							
	Anuta OH, Taylor PC, Jones D, McEntee T, Wade NS. the implications of regulatory and electricity m emergence of grid scale electricity storage. <i>Renewal</i> <i>Reviews</i> 2014, 38, 489-508.	An international review of arket structures on the ole and Sustainable Energy						
	This project is now closed.							
Potential for achieving expected benefits	The adoption of energy storage systems in distribution held back by the lack of validated business cases that generating potential in comparison to the costs. This im against particular future scenarios, energy storage can of network reinforcement. The full potential of energy st realised when the effects of increases in distributed ger of transport and heat present greater effects in developments in the provision of home energy stor Daimler and Tesla are likely to make the findings from relevant as storage is added to the network by consume	networks continues to be show a sufficient income vestigation has shown that compete with conventional orage is more likely to be neration and electrification in the networks. Recent age systems from Moixa, in this project increasingly rs.						
Collaborative Partners	Electricity North West							
R&D Providers	Newcastle University							



Project Title	IFI 1104 – SF GB Electricity Demand Project							
	This project will potential resour market.	l identify rce whic	<pre>/ practical solutions / flexible electricity</pre>	s, incentiv y load cou	es and path Ild offer int	ways to realise the o the GB electricity		
Description of project	The project will evaluate and understand potential GB electricity dema response as a resource across all sectors (including how micro-gen fits in); a clearer understanding of the economic value and potential of this reso different market actors and to different customers over the next 10-15 ye systematically evaluate the key consumer, commercial, regulatory and issues and interactions.							
Expanditura for financial	Internal £14	ernal £14,102			Internal	£16,976		
year	External £6,	,659	(IFI) financial year	rs	External	£29,226		
	Total £20	0,761			Total	£46,202		
		_	Projected 2015/1	6 costs	Internal	£0		
Project Cost	£348,895	5	for SPEN		External	£0		
					lotal	£U		
	Key Themes for	r the pro	ject include:					
	<b>Customer Response &amp; Consumer Issues</b> – A key focus for the project has been to understand successful and cost-efficient demand-side participation from the various customer groups perspective. This includes gaining experience through LCNF trial and other similar initiatives in the UK and beyond.							
Technological area and /	are likely to play in the future electricity market, the nature of the commercial agreements required and the kind of information sharing that is necessary to make it work effectively all require to be explored.							
or issue addressed by project	<b>Regulatory</b> – The workstream focuses upon the regulatory factors (current and future) that impact upon the development of an active electricity demand side market within GB. This includes a review of current agreements between market participants, interaction with industry and statutory codes, incentives in price controls, settlements and third party requirements.							
	<b>Public Policy Issues</b> – This work package will consider the likely economic value and potential contribution of demand-side to greater cost efficiency across the electricity sector, security of supply, carbon reduction, business and market models, interactions with electricity market reform, smart metering as well as energy efficiency schemes such as CRC Energy Efficiency Mechanism, Green Deal and Energy Company Obligations.							
Type(s) of innovation	Incremental	I	Significant	Techno subst	ological itution	Radical		
IIIVUIVEU	Yes		No	Ν	10	No		
Expected Benefits of Project	Co-ordinated through a Smart Demand Forum, the project is expected to develop a substantive knowledge-base and provide thought-leadership and visibility for GB electricity demand–side issues, by bringing together three key strands: practical demand-side and load-management experiences, including from Low Carbon Network Fund projects; a top-down technical and economic overview; and, expert analysis of the key consumer, commercial, regulatory and policy issues.							



Expected Timescale to adoption	<2 Years	Duration of benefit once achieved					15 Years								
	TRL Development (Start – Current)									ent (Start – Current)					
Probability of Success	75%	1	2	3	4	5	6	7	8	9					
								$\land$							
Project NPV	(Present Benefits x Pro Costs	obabilit	y of Su	ccess) -	– Prese	nt	твс								
Project Progress March 2015	<ul> <li>The project has made significant progress through the publication of several papers on issues associated with GB Electricity Demand and Use of Demand Side Response which are available at <u>www.sustainabilityfirst.org.uk</u> (GB Electricity Demand Project). The following papers were published during the reporting year:</li> <li>Paper 12 - The household electricity demand-side &amp; the GB electricity markets : realising the resource published July 14</li> <li>Paper 13 - Realising the Resource: GB Electricity Demand Project Overview published in October 14</li> </ul>														
Potential for achieving expected benefits	The project is now closed.														
Collaborative Partners	BEAMA Cable & Wireless Consumer Focus British Gas EDF Energy Elexon E-Meter (a Siemens Business) E.ON UK National Grid Northern Powergrid Ofgem														
R&D Providers	Sustainability First														



Project Title	IFI 1203 – Psymetrix ACAM Phase 1										
Description of project	The objective Management Management scheme capab Distributed Ge	The objective of this project is to prove the concept of an Active Network Management (ANM) approach known as Angle Constraint Active Management (ACAM). Then initiate its development into an operational scheme capable of facilitating the connection and management of additional Distributed Generation (Phase 2).									
	Internal £1	4,102	Ex	nendit	ıre in		Inte	ernal	£61,119		
Expenditure for	External £5	4,659	pre	evious	(IFI) fi	nancial	Ext	ernal	t	E152,2	87
linancial year	Total £6	8,761	ye	ars			Tot	al	ŧ	E <b>213,</b> 4	06
							Inte	ernal	ł	EO	
Project Cost	£320,65	5	Pro	ojecteo sta for	2015 CDEN	/16	Ext	ernal	ł	EO	
			0	515 101	SPEN		Tot	al	ł	E <b>O</b>	
Technological area and / or issue addressed by project	The project w greater peneti	The project will contribute to the UK environmental targets by enabling a greater penetration of renewable generation on to the electrical network.						ling a rk.			
Type(s) of innovation	Incrementa	Incremental Significant			Significant Techno substit			ical on	Radical		
Involved	Yes			No			No			No	
Expected Benefits of Project	<ul> <li>To prove and quantify the additional capacity that an ACAM scheme could introduce</li> <li>To prove the correlation of modelled ACAM angles against network PMU measurements</li> <li>To identify the operational requirements of an ACAM scheme</li> <li>To gain the necessary evidence to justify an operational trial of the ACAM scheme</li> </ul>										
Expected Timescale to adoption	2 Years		Dura once	tion of achiev	bene ved	fit			10 Yea	ars	
			TRL Developme			ent (S	tart –	Currer	nt)		
Probability of Success	50%		1	2	3	4	5	6	7	8	9
								$\geq$			
Project NPV	(Present Bene Present Costs	efits x Pro	obabi	ility of	Succe	ss) —			£18	7,974	
Project Progress March 2015	This project is now completed. During 2014/15 Psymetrix were able to overcome several technical issues with the communication to the installed PMUs to gain sufficient network data to analyse the potential performance and capacity increase that would be ascertained by an ACAM scheme.										
Potential for achieving expected benefits	This project w phase was ain capacity and	vas envis med at <sub>l</sub> could be	sageo provi e tec	l to be ng the hnicall	e deliv ACAI y viab	vered in M cond ole solu	n two cept v ition.	Phase vould In del	es, this delive livering	s initia r addi g their	l first tional final



	report on Phase 1, Psymetrix have provided SPEN with sufficient evidence to decision on whether to progress to Phase 2. At the time of writing this report no decision has yet been made on the progression to a Phase 2 Pilot trial under NIA.
	Aside from the proving the ACAM concept the project has also delivered invaluable DNO experience in operating PMUs at distribution voltages and utilising GPRS communications at remote geographical locations.
Collaborative Partners	Psymetrix
R&D Providers	Psymetrix



IFI 1207 – Smart 3 Phase Voltage Regulator								
g has s the								
An active series voltage regulator to be developed by Gendrive Ltd (supported by EA Technology) aims to provide a more stable and smarter local supply. The unit proposed will in effect prevent or at worst delay the cost of reinforcing problematic distribution circuits.								
Although voltage issues in rural/urban areas are not currently a major issue, ongoing work in a number of Low Carbon Network projects suggests that the increasing load scenario (particularly heat pumps) that will develop in the next 20 years will generate increases in customer supply problems. The smart voltage regulator unit offers the potential to solve issues in problem feeder circuits as well as providing an opportunity to moderate harmonic and to a certain extent power factor issues that are also anticipated to grow.								
No								
, and upled oltage								
• Distributed Generation on the customer side will suffer fewer loss-of-mains trips whenever voltage rises above the permitted voltage range, as the effective network voltage (load-side) can be reduced								
or will								
9								
£76,055								



Project Progress March 2015	This project is now closed. As reported in 2013/14 this project was placed on hold due to the R&D provider going into administration. Over the course of 2014/15 the Collaboration Partners agreed to close this project at its present point.
Potential for achieving expected benefits	This project demonstrated that there were limitations in the technological solution being developed by GenDrive on the basis of its size and suitability for being located on LV feeders. This project has delivered negative learning and has identified further requirements for the specification of any future LV feeder voltage regulators. It is likely that the learning generated in the early stages of this project will be utilised in a future project(s) that look to develop solid state devices.
Collaborative Partners	Scottish Hydro Electric Power Distribution plc, Electricity North West Limited, Northern Powergrid Limited, UK Power Networks (Operations) Limited and Energy Innovation Centre Limited
R&D Providers	Gendrive Ltd, (supported by EA Technology)



Project Title	IFI 1209 – Substation Earth Integrity Monitoring System												
Description of project	This aim of this project is to develop a system for monitoring the removal/theft of earth straps from Transmission and Distribution substations or other installations												
Expenditure for financial year	Internal         £14,102           External         £252,837           Total         £266,939	, Ex (IF	Expenditure in previous (IFI) financial years				Inte Ext Tot	Internal External <b>Total</b>		Internal External Total		20,293 148,01 168,30	1 <b>4</b>
Project Cost	£189,347	Pr fo	Projected 2015/16 costs for SPEN					ernal ernal :al	f f f	23,000 26,000 <b>49,000</b>			
Technological area and / or issue addressed by project	<ul> <li>The project will explo</li> <li>1) Use of RFID tech monitored (pinged) b</li> <li>2) To prove the cc radio/antenna optimactivity.</li> <li>3) Develop the Creapplication at SPEN suggestion</li> </ul>	<ul> <li>The project will explore three separate work streams</li> <li>1) Use of RFID technology using RFID tags bonded to earth straps that are monitored (pinged) by a monitoring unit on site to detect their presence.</li> <li>2) To prove the concept of using SWR (Standing Wave Ratio) as used in radio/antenna optimisation to provide detection of real time "earth tamper" activity.</li> <li>3) Develop the Cresatech Copper Theft Sensor (CuTS) prototype unit for application at SPEN substations.</li> </ul>								t are ed in nper" t for			
Type(s) of innovation	Incremental	S	Significant Techr subs		nnolog stituti	nological stitution		Radical					
Πνοινεα	No			No			Yes		No				
Expected Benefits of Project	There is no off the substation which can detection. Expected benefits of t Potential av accidents or Help to ensu (ESQCR) are Notification to Deterrent to	<ul> <li>There is no off the shelf product available for permanent installation in a substation which can detect the presence of adequate earthing and real time theft detection.</li> <li>Expected benefits of the project include: <ul> <li>Potential avoidance of a 'Danger of Death' incident, major or minor accidents or ill health</li> <li>Help to ensure that Electricity Safety, Quality and Continuity Regulations (ESQCR) are met</li> <li>Notification that earthing Copper or other infrastructure has been stolen</li> <li>Deterrent to thieves if coupled with sound/light alarm on site</li> </ul> </li> </ul>											
Expected Timescale to adoption	1 Year	Dur ach	rati niev	ion of l /ed	benefit	once			15 Yea	ars			
Probability of Success	75%	1		2	TRL De <sup>.</sup> 3	velopm 4	ent (S 5	tart – C 6	Current	8	9		
Project NPV	(Present Benefits x Probability of Success) – Present Costs £71,378												



	RFID Tags and SWR						
	This project has been closed as it was decided to concentrate efforts on the Cresatech CuTS units as they were at a higher Technology Readiness Level and consequently represented a greater likelihood of success.						
	Cresatech CuTS Prototype Unit						
	Over the past 12 months the following outputs have been achieved;						
Project Progress March 2015	<ul> <li>Limited roll-out of units to primary and secondary substation sites</li> <li>Development of an online portal to remotely evaluate and update all installations</li> <li>Evaluation of the effectiveness of the monitors at detecting copper theft and tampering of key infrastructure</li> <li>A programme for a pilot roll-out of 80 units has been developed</li> <li>Evaluation of how the monitors interact with substation environments</li> <li>Evaluation the of monitor performance and how they could be developed further has been undertaken</li> </ul>						
Potential for achieving expected benefits	The potential for achieving expected benefits of the Cresatech CuTS prototype unit is being evaluated during the pilot roll-out phase of this project.						
Collaborative Partners	Scottish & Southern Energy (Cresatech Project), Energy Innovation Centre						
R&D Providers	Nortech Online Ltd and Cresatech						



Project Title	IFI 1211 – Smart CCU Development									
Description of project	To enable retrieval of complex data from Network Controllable Points (NCP) Intelligent Electronic Device (IED), for example the Noja Pole Mounted Auto Recloser (PMAR), it is necessary to develop a digital radio that will interrogate the DNP3 mapping and transmit the information to the relevant source primary substation. In tandem with this, the project will also develop a new style Central Control Unit (CCU) to accept the data and display it locally as well as sending it via an IEC 86870-5 -104 com-link for remote display.									
Expenditure for financial year	Internal         £127,464           External         £11,684           Total         £139,148	Exp (IFI)	Expenditure in previous (IFI) financial years Total					£ £ £	159,02 96,556 <b>255,57</b>	1 7
Project Cost	£88,000	£88,000 Projected 2015/16 costs for SPEN		Projected 2015/16 costs for SPEN			ernal ernal <b>al</b>	£ £ <b>£</b>	0 0 <b>0</b>	
Technological area and / or issue addressed by project	<ul> <li>The project will:</li> <li>Develop a new CC</li> <li>Develop a digita protocols.</li> </ul>	<ul> <li>The project will:</li> <li>Develop a new CCU for accepting complex digital data and analogue values.</li> <li>Develop a digital radio to interrogate IED devices operating with DNP3 protocols.</li> </ul>								es. DNP3
Type(s) of innovation	Incremental	Sig	Significant Techi subs			nologi stitutio	cal on	Radical		
involved	Yes		No	No			No No			
Expected Benefits of Project	<ul> <li>This project will interrogation of D transfer.</li> <li>Recovering details imbalance will he may provide addit for this.</li> </ul>	<ul> <li>This project will ensure the retrieval of complex data from NCPs and interrogation of DNP3 mapping which will consequently improve knowledge transfer.</li> <li>Recovering detailed information on secondary network HV loading and phase imbalance will help to ensure the system is optimally configured. This data may provide additional insight into network behaviour and assist in preparing</li> </ul>								and ledge ohase data paring
	• This project will provide immediate access to data to understand fault modes and provide the ability to model the network in real time and load it dynamically, or improve efficiency.									
Expected Timescale to adoption	<1 Years	Dura achie	tion of l ved	penefit	once			10 Yea	rs	
				TRL De	velopme	ent (St	art – C	urrent	)	
Probability of Success	90%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present Not determined at this Costs stage							his		



Project Progress March 2015	Much work has been carried out on this development project. A field trial has commenced at St Andrews for digital control and recovery of analogue data from IEDs. IEC SCADA link remains outstanding, which is reliant upon the installation of an 86870-5-104 comms link to complete the project. This work is behind schedule. Mapping the CCMU into SCADA also remains outstanding. There is an overlap with the RIIO-ED1 programme, which has resulted in creep in specification with a corresponding reduction in time allocated to this project. Control points have been successfully commissioned into PowerOn via the legacy protocol for this work stream. This project is now closed.
Potential for achieving expected benefits	The potential for achieving expected benefits is considered to be very high
Collaborative Partners	SmartGridNetworks
R&D Providers	SmartGridNetworks



Project Title	IFI 1215 – Self Repair MV Underground Cables								
Description of project	There is a recognised need in the UK electricity distribution network for extrude polymeric cables to be capable of self-repair if the protective outer sheath damaged during installation and operation. In-situ cable self-repair would b valuable as the damage is likely to be localised and not obvious from inspection of the cable because it is usually impractical and/uneconomic to inspect a underground asset.							ruded ath is Id be ion of ct an	
Description of project	An initial study will review, rank and laboratory-trial a number of new candidate materials technologies. This would be followed by laboratory trials on one or more candidate repair technologies. If successful, commercial development of an improved performance Medium Voltage (MV) cable system could follow in collaboration with one or more cable companies to produce MV cables that would be suitable for installation in the UK power network								
Funenditure for finensial	Internal £15,240	Fun en ditune in a		Inte	ernal	f	11,208		
year	External £77,411	(IFI) financial yea	rs	Exte	ernal	f	106,50	8	
	Total £92,651			Tota	al	f	E117,71	6	
Droiget Cast	(202.270	Projected 2015/1	l6 costs	Internal		1	£U £O		
Project Cost	1302,270	for SPEN	Total		f	-0 -0			
Technological area and / or issue addressed by project	New developments in self-repairing polymers and reactive chemical technologies could potentially be capable of providing a repair function for a variety of cable sheath defects and damage that may occur. This would reduce the necessity to repair damaged underground cables, reduce customer disruption from premature cable failure and nuisance trips.							cable educe	
Type(s) of innovation	Incremental	Significant	Significant Technologi substitutio				Radical		
involved	No	Yes	1	No		No			
	Critical review of cable self-repair	existing self-repair	technolog	gies t	o mee	t the I	needs c	of MV	
Expected Benefits of	• Second stage trialling of top candidate self-repair technologies and selection of system(s) for MV cable development								
riojeci	Recommendations on commercial development of the IP generated within the cable industry								
	• To patent at least of	one and possibly tw	o candida	te sel	lf-repa	ir tech	nologies	5	
Expected Timescale to adoption	4 Years	Duration of benefi achieved	t once			20 Yea	ars		
		TRL De	evelopme	nt (St	art – C	Current	:)		
Probability of Success	25%	1 2 3	4	5	6	7	8	9	
Project NPV (Present Benefits x Probability of Success) – Present £15,340									



Project Progress March 2015	<ul> <li>4 specific repair technologies have been identified and tested</li> <li>A number of cable manufacturers have shown significant interest in the project including the provision of material samples and cable samples</li> <li>Several material suppliers have engaged positively in the project including the provision of material samples</li> <li>3 test rigs have been built and used for testing</li> <li>The project has made good progress and identified further work with a new stage 4 to be carried out. This looked at the merging of two different repair technology classes to gain the best possible self-repairing mechanisms.</li> <li>All stages of the project are now complete with the Final Report Issued detailing the following:         <ul> <li>Results of the trialling and evaluation of land-based and undersea cable self-repair technologies</li> <li>Economic assessment on what technologies to adopt</li> <li>Recommendation on best route to commercialise and deliver self-repair cables to DNO's</li> <li>Best approach to exploit the technology for wider adoption in global markets</li> </ul> </li> </ul>
Potential for achieving expected benefits	Project is now complete and met all expected benefits of the project
Collaborative Partners	SSE and Energy Innovation Centre
R&D Providers	Gnosys Ltd



Project Title	IFI 1216 – The Role of the Demand Side in Delivering Effective Smart Grids							
	An International Energy Agency Project commenced in June 2012 with four international participants, namely, Korea, Netherlands, Norway and Sweden to investigate the role of consumers in delivering effective Smart Grids. EA Technology has been appointed to lead a UK team which will include Distribution Network Operators, Energy Suppliers and others.							
Description of project	ription of project Customers have a key role to play in ensuring the successful transition to Grid environment with energy production and demand integrated, when demand response to end users is no longer provided, and renewables op whilst minimising fossil fuelled generation and network reinforcemen consequence customers will be required to adopt new approaches to the w consume electricity.							
	Internal £14,102		Internal	£25,736				
Expenditure for financial vear	External £6,659	(IFI) financial year	rs External	£23,726				
<i>y</i> co.	Total £20,761	(,	Total	£49,462				
		Projected 2015/1	Internal	£0				
Project Cost	£19,925	for SPEN	External	£O				
			Total	£0				
Technological area and (	Whilst there is a considerable focus on the technological aspects of delivering smart grids, little is understood of the extent to which consumers are willing embrace new technologies and initiatives that enable their use of energy to actively managed. There is a real risk that if customers do not adopt ne approaches to the way that they consume electricity, Smart Grids may not be at to achieve their full potential							
or issue addressed by project	This project will enable SPEN to understand the factors that influence customer reactions and attitudes towards Smart Grids; gain an independent view of risk and rewards of Smart Grids from the customers' perspective; understand how customer needs can be aligned with those of industry stakeholders; understand the importance of the demand side in ensuring effective Smart Grid delivery; identify measures and tools that could be used to ensure customers are willing and able to contribute to successful Smart Grid deployment; and design customer propositions that allow and enhance the use of the 'smartness' of a grid.							
Type(s) of innovation	Incremental	Significant	Technological substitution	Radical				
involved	Yes	No No No						



П

	• Understand the ir delivery of Smart G	nporta irids	nce of	the d	emand	side	in ens	uring t	he eff	ective	
	Gain an independed     customers' perspect	ent vie ctive	w of th	ne risks	and re	eward	s of Sm	nart Gr	ids froi	m the	
Expected Benefits of Project	• Understand how the needs of the customers can be aligned with the needs of the industry stakeholders										
	<ul> <li>Identify measures and tools that could be used to ensure customers are willing and able to contribute to the successful deployment of Smart Grids</li> </ul>										
	• Establish Best Practise guidelines to ensure the demand side contributes to the delivery of effective Smart Grids.										
	<ul> <li>The outputs from the project are likely to lead to incremental changes to processes as this is more likely to be acceptable to demand side customers</li> </ul>								ges to rs		
Expected Timescale to adoption	<2 Years	<2 Years Duration of benefit once 10 Years									
				TRL De	velopm	ent (S	tart – C	urrent	)		
Probability of Success	50%	1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x Pro Costs	bability	y of Suc	cess) –	- Preser	nt	N/A				
Project Progress March 2015	This project is now clos	ed									
Potential for achieving expected benefits	There is real potential to level of activity being u to engage effectively transition to Smart Gric	There is real potential for achieving the expected benefits based upon the current level of activity being undertaken to determine the role and appetite of customers to engage effectively in the delivery of Demand Side activity to enable the transition to Smart Grids.									
Collaborative Partners	EON, ENW and NG										
R&D Providers	EA Technology										



Project Title	IFI 1218 – Impact of Residential Heating and Building Standards on Demand Profiles										
Description of project	There are a number of changes to the built environment that will impact on the way that domestic properties are heated and constructed. Government policy is that all new homes will be constructed to net zero carbon standard by 2016 and housing providers are carrying out a process of refurbishment on existing multi- occupancy residences. There will be a greater reliance on electricity to provide heating in the future and low carbon heating will become more common in domestic properties. This project will examine the impact of heating technologies and building standards on low carbon homes at the BRE Innovation Park at Ravenscraig and representative multi-occupancy residences in the central belt.										
Expenditure for financial year	Internal         £14,102           External         £6.659           Total         £20,761	E (	Expenditure in previous (IFI) financial years					ernal ernal t <b>al</b>	f f f	20,571 3,801 2 <b>4,372</b>	
Project Cost	£96,000	F	Proje for S	ected 2 PEN	015/16	ernal ernal :al	f f f	20 20 20			
Technological area and / or issue addressed by project	This project will exam and demand profiles achieved through mor properties and throug for different combina technology.	nis project will examine the impact of and provide a range of up to date ADMD nd demand profiles to allow for more appropriate network design. This will be chieved through monitoring the power flows and demand profiles at the various roperties and through using this data to model demand profiles and ADMD values or different combinations of heating type, building standard and low carbon echnology.									
Type(s) of innovation	Incremental	Incremental Significant Technological Rad						Radical			
Involved	No			No			Yes			No	
	<ul> <li>Successful project required to carry zero carbon home</li> <li>Improved data on tools, designs and</li> </ul>	et co out d es an buil	ompl desig nd m Iding	letion gn for a nulti-oc gs and	will br areas w cupanc techno	ing abo vith high cy home: llogies b	ut in take s. eing a	nprover -up of l	ments low car d will f	to the bon he	time ating, e new
Expected Benefits of Project	<ul> <li>Significant impro multi-occupancy developing the gr</li> </ul>	vem resi id fo	ents iden or the	s in ne ces w e futur	etwork hich v e	design vill con	for l tribu	low car te tow	rbon b vards	uilding: the go	s and al of
	<ul> <li>Project will impr values, improving</li> </ul>	ove accı	on urac	accura y of ca	cy of ble size	cable si es for do	zing mest	throug ic prop	h impr erties.	oved A	DMD
	<ul> <li>Use of monitore different combination technology</li> </ul>	d da natio	ata ons	to mo of he	del de ating,	emand p buildin	orofile g sta	es and andard	ADMI and	D value low ca	es for arbon
Expected Timescale to adoption	3 Years	Di ac	urat chiev	ion of l ved	penefit	once			15 Yea	ars	
					TRL De	velopme	ent (S	tart – C	Current	)	
Probability of Success	50%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present Costs										



Project Progress March 2015	<ul> <li>Gridkey monitors installed at Toryglen site covering high concentration of heat pump installations on site.</li> <li>Project has taken advantage of data captured at high density PV site in Wrexham. Modelling undertaken by Strathclyde University and applied to designs in recent PV cluster applications to SPEN in ARC trial area.</li> <li>Ravenscraig low carbon homes development did not progress as planned to produce sufficient data. Data capture is proposed if site matures, analysis to be undertaken internally in SPEN, outcomes may revise design guidance.</li> <li>Housing build delayed at proposed CHP heating high rise site in Glasgow.</li> <li>Profiles captured and ADMD values have been quantified for CHP in flatted properties.</li> <li>Tool developed to calculate ADMD value based on data captured.</li> </ul>
Potential for achieving expected benefits	High
Collaborative Partners	Building Research Establishment (BRE)
R&D Providers	University of Strathclyde



Project Title	IFI 1219 – Substation E	fficien	су							
Description of project	Substations are critical SPEN maintains thouse age and construction high operation costs efficiency savings for so lack of control, lighting reduced asset life, bat energy waste.	ibstations are critical to the successful operation of the distribution network. PEN maintains thousands of substations as part of the network, ranging in type, ge and construction quality. Given the drive for carbon reductions and current gh operation costs of substations means that there is a need to find energy ficiency savings for substations. Current issues include; over and under heating, ck of control, lighting defects and the need to install ventilation. This can lead to educed asset life, battery effectiveness reduction, sticky breakers, high costs and hergy waste.								
Expenditure for financial year	Internal         £14,102           External         £14,792           Total         £28,894	Exp (IFI)	enditur financi	e in pre al year	evious s	Inte Exte <b>Tot</b>	ernal ernal <b>al</b>	£ £ £	29,115 91,289 <b>120,40</b>	4
Project Cost	£139,800	Projected 2015/16 costs for SPEN					ernal ernal <b>al</b>	f f f	0 0 <b>0</b>	
Technological area and / or issue addressed by project	Monitoring and meter and electrical auxiliary make an assessment o operating substations will be carried out at 2 applicability to the net	Monitoring and metering will be used to carry out an assessment of the thermal and electrical auxiliary loads required by substations. Modelling will be used to make an assessment of the entire Scottish network and will allow the total cost of operating substations to be quantified. Substation trials of innovative technology will be carried out at 10 Primary Substation sites to assess their effectiveness and applicability to the network as a whole.								
Type(s) of innovation	Incremental	Sig	Significant Techr subs			hnological bstitution			Radical	
Involved	Yes		No		,	Yes		No		
Expected Benefits of Project	<ul> <li>Use of monitored of substation netw</li> <li>Successfully trial e with learning from</li> <li>Increased asset lif the need to replace</li> <li>Lowered heating a substations</li> </ul>	<ul> <li>Use of monitored data to develop extrapolated model to make an assessment of substation network as a whole</li> <li>Successfully trial energy efficiency measures at 10 Primaries on the network with learning from trials to direct future rollout</li> <li>Increased asset life due to improved environmental control which will reduce the need to replace assets</li> <li>Lowered heating and lighting bills and reduced maintenance requirements for substations.</li> </ul>								
Expected Timescale to adoption	<2 Years Duration of benefit once 10 Years									
Probability of Success	75%	1	2	TRL De 3	velopme 4	ent (S 5	tart – C 6	urrent) 7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present Costs £850,809									



Project Progress March 2015	<ul> <li>Tinytag monitors installed to cross section of SPEN substation estate, data captured and collected</li> <li>Analysis of data carried out with assistance from University of Strathclyde</li> <li>At 19 substations metering installed to capture electrical consumption</li> <li>Work started on installing improved heaters and control to these substations</li> <li>Future work focussed on assessing outcomes of substation improvements and cost benefits from rollout</li> <li>Review of current substation light and power installation specification to be undertaken</li> </ul>
Potential for achieving expected benefits	High
Collaborative Partners	None
R&D Providers	University of Strathclyde



Project Title	IFI 1302 – SUSCABLE 2	2									
Description of project	SUSCABLE 2 project is design of high operat was to develop new environmental impa- sustainability (increas supply in urban and e was new polymer bl electrical performanc performance.	USCABLE 2 project is the second phase of a project for the development of a new esign of high operating temperature power cable. The objective of SUSCABLE 1 vas to develop new power cable material technologies with reduced whole-life nvironmental impact, increased power system efficiency with enhanced ustainability (increased peak-load thermal tolerance) and increased security of upply in urban and environmentally sensitive areas. The outcome of SUSCABLE 1 vas new polymer blends with high thermal stability materials with enhanced lectrical performance, reduced production costs and improved environmental erformance.									
Expenditure for financial year	Internal         £16,378           External         £54,992           Total         £71,370		Expe (IFI)	enditur financ	re in pr ial year	evious 's	ln Ex Tc	ternal ternal o <b>tal</b>	:	£6,401 £2,108 <b>£8,510</b>	
Project Cost	£143,333	Projected 2015/16 costs for SPEN							:	£15,000 £70,000 <b>£85,000</b>	
Technological area and / or issue addressed by project	The project aims to day in place the design for the 35kV cable. First generation PVC cross linking (XLPE) to 90°C while the new the operating range of 120 (lower conductor cross)	The project aims to deliver a 35kV cable based on the new materials and also put in place the design for a 400kV cable based on the experience built up in making the 35kV cable. First generation PVC insulation restricted cable ratings to 60 - 70°C, subsequent cross linking (XLPE) to prevent the plastic melting offered a continuous rating at 90°C while the new thermo plastics under consideration offer the prospect of an operating range of 120°C to 150°C which would lead to significantly cheaper cables (lower conductor cross section for equal rating).									
Type(s) of innovation	Incremental		Significant Techr subs				hnolo bstitu	gical tion	Radical		
Involved	No			Yes			No			No	
Expected Benefits of Project	<ul> <li>Design, develop continuous opera</li> <li>Materials refiner production proces</li> <li>Cable manufactu experience that w</li> <li>Having cable ins emergency rating</li> </ul>	<ul> <li>Design, develop and test a 35kV MV cable that is compatible with 120°C continuous operating temperature and 150°C conductor emergency rating.</li> <li>Materials refinement to achieve the MV design, processing and cable production processes.</li> <li>Cable manufacturing and testing with structured development to generate experience that will be of value in 400kV design, manufacture and testing.</li> <li>Having cable insulation that is thermally stable at higher continuous and emergency rating offers significant safety benefits.</li> </ul>									
Expected Timescale to adoption	<2 Years	[ a	Durat achie	ion of ved	benefit	once			10 Ye	ars	
Probability of Success	50%		1	2	TRL De	velopr 4	nent ( 5	Start – C	Curren <sup>-</sup> 7	t) 8	9
Project NPV	(Present Benefits x Probability of Success) – Present Costs £71,499										



Project Progress March 2015	The project began in June 2014 and has made significant advance in the 9 months to March 2015. The original bi-polymer polypropylene blends from SUSCABLE 1 have been reproduced with materials sourced from multiple suppliers globally and found to perform equally well electrically and thermally as the best blends from SUSCABLE 1. Multi-sourcing has also been achieved for new tri-polymer blends and the first tripolymer blends have been formulated. Anti-oxidant packages to protect the materials in processing and use have also being selected and are being sourced. Trial blends at volume levels large enough for cable manufacturer process trials have been produced and are being evaluated by the cable makers.
	MV cable designs have been finalised and cable rating studies begun for underground cable deployment. Review work has also been completed on the deployment options for both MV and HV cable designs for potential deployment in distribution and transmission networks and offshore applications. The response of materials suppliers to requests for materials took much longer than planned but the results have been worthwhile. This delay has created some knock-on delays to later tasks but good progress is being made across the whole project. The cooperation and commitment of the cable companies who are co-funding the project is high. Project continuation under NIA funding is under consideration.
Potential for achieving expected benefits	The prospects look good for achieving the original objectives, and possibly more, as the electrical assessment of the materials and their ease of processing indicates they would also suit HVDC applications in addition to HVAC beyond the MVAC cable development being pursued in this project. It is noted that the additional objective to achieve a MVAC cable core to support HVAC cable development is also being achieved.
Collaborative Partners	National Grid, ORE Catapult, Nexans, General Cable Silec, University of Southampton and GnoSys Global
R&D Providers	GnoSys Global Ltd and University of Southampton



Project Title	IFI 1304 – Smart Meter	r Enabl	ement									
Description of project	The overall goal of t processes required to management systems requirements for conn	e overall goal of the project is to determine the basic infrastructure and ocesses required to innovatively store and use Smart Meter data within SPEN anagement systems and to ensure SPEN is capable of meeting its regulatory quirements for connecting to smart meter infrastructure.										
Expenditure for financial year	Internal         £25,233           External         £170,550           Total         £195,782	Expo (IFI)	enditur financi	e in pr al yeaı	evious rs	Inte Exte Tot	ernal ernal <b>al</b>	f f f	20,892 114,42 <b>135,32</b>	9 <b>1</b>		
Project Cost	£383,000	83,000 Projected 2015/16 costs for SPEN					Internal£0External£0Total <b>£0</b>					
Technological area and / or issue addressed by project	The project aims to tak the way network m appending additional in	e project aims to take an innovative view of how Smart Meter data can enhance e way network management and operations can work rather than just opending additional information to the existing processes										
Type(s) of innovation	Incremental	Incremental Significant Techr subst					ical on	Radical				
Involved	No No				Yes			No				
Expected Benefits of Project	<ul> <li>Readiness for the Smart Energy Code</li> <li>Ability to innovative</li> </ul>	<ul> <li>Readiness for the implementation of smart meters and accession to new Smart Energy Code</li> <li>Ability to innovatively use smart meter data</li> </ul>							new			
Expected Timescale to adoption	<2 Years	Durat achie	tion of l ved	penefi	t once			10 Yea	rs			
				TRL De	velopm	ent (S	ent (Start – Current)					
Probability of Success	75%	1	2	3	4	5	6		8	9		
Project NPV	N/A at this trial stage		1		1 1		1	1 -		1		
Project Progress March 2015	<ul> <li>The smart meter</li> <li>The smart meter</li> <li>Some learnings a alternative smart</li> <li>This project is now cl</li> </ul>	test be simulat are alre meter osed as	d has b tor is in ady ide process s the sn	een de the fir entifie sing in nart m	eployed nal stage d and w PowerC eter test	and is es of a e hav On t bed i	functio cceptar e enga s now	oning nce tes ged wi busines	ting th GE ss as us	to try ual		
Potential for achieving expected benefits	We have begun to use from smart meter info information is most like	e the si rmatio ely to g	mulato n. We e enerate	r to as expect e bene	ssess the the tria fits.	e pote I resul	ntial fo ts will	or realis help id	sing be entify	nefits which		
Collaborative Partners	Kyria, potentially GE, A	MT-Syl	bex oth	er DN(	D.							
R&D Providers	Kyria, potentially GE ar	nd AMT	-Sybex.									



Project Title	IFI 1305 – Low Power	Radio	Alarm S	ystem						
Description of project	This project is to de existing NCP radio c recover single digital control up to three ob a way to utilise the c NCP asset could be us	his project is to develop a low cost simple radio that will interface into the xisting NCP radio communications infrastructure using spare I/O channels to ecover single digital data alarms. Although a ground mounted NCP RTU is able to pontrol up to three objects, in many installations only two are used. By developing way to utilise the digital channels of the un-used control channel, the existing CP asset could be used as a route for remote alarms into SCADA.								
Expenditure for financial year	Internal         £26,843           External         £11,684           Total         £38,527	Exj (IF	penditur ) financi	e in pr al yea	evious rs	Int Ext	ernal ernal	t t	E21,969 E110,77 F <b>132.74</b>	6 5
Project Cost	£104,277	£104,277 Projected 2015/16 costs for SPEN							£0 £0 £0	
Technological area and / or issue addressed by project	HV secondary substat largely blind to SCAI alarms is not cost effe watchdog alarms, fa secondary network systems.	IV secondary substations equipped with basic monitoring, or sensing devices, are argely blind to SCADA as the infrastructure required to recover a few digital alarms is not cost effective. Returning single digital data points for battery alarms, vatchdog alarms, fault passage indications, etc. would give visibility of the econdary network and ensure such conditions were reported into central systems.								
Type(s) of innovation	Incremental	Incremental Significant Technological Rad						Radical		
Involved	Yes		No			No			No	
Expected Benefits of Project	<ul> <li>Development of a</li> <li>Development of low-bandwidth data</li> </ul>	a low p an inte ata app	ower rac erface in dication:	dio for to an s exter	last-mile RTU in a nal to th	e com a seco e NCI	munica ondary <sup>o</sup> syster	ntion S/S fo m	r recove	ery of
Expected Timescale to adoption	1.5 Years	Dura achi	ation of eved	benefi	t once			10 Ye	ars	
				TRL De	evelopme	ent (S	tart – C	Current	:)	
Probability of Success	90%	1	2	3	4	5	6	7		9
Project NPV	(Present Benefits x Pr Costs	obabili	ty of Su	ccess)	– Presen	t	-£15,7	760		
Project Progress March 2015	Prototypes have been business has been co of the radio onto the Susbstations. This pro	n deliv nducte e netwo ject is i	ered and d. Fund ork initia now clos	d a we ing ha ally foi sed.	orkshop s been se r recover	trial ecure y of	and de d via R alarms	monst IIO-ED from	ration t 1 for ro HV cust	o the II-out omer
Potential for achieving expected benefits	The potential for achie	eving e	xpected	benef	its is con	sider	ed to b	e very	high.	
Collaborative Partners	Smart Grid Networks									
R&D Providers	Smart Grid Networks									



Project Title	IFI 1307 — I	IFI 1307 – Mobile Phone Application Prototypes								
	This project concept of b	: has two d business appl	istinct sub-projects that an lications on the SPEN mobile	re designed to e phone platform	prototype the 1.					
	Incident Dispatch & Status Management (IDSM)									
Description of project	The current based, time solution whi using a Win platforms ar manner.	Ine current process for identifying incident status of jobs is inefficient, phone based, time consuming and not customer focused. This project will provide a solution which will allow field staff to enter status updates directly into PowerOn using a Windows 8 mobile phone application. The project will use core SPEN IT platforms and will provide a greatly improved customer service in a more efficient manner.								
	The purpose of this project is to provide the Zone team leaders / OCC Incident Controllers the ability to assign incidents to 300 field crews (North and South) during operational hours / outwith normal working hours and monitor status updates without incurring direct communication delays. These staff will use Geofield Central to allocate and track the status of incidents.									
	In the field, the frontline staff will utilise GeoField TouchBase on a Windows 8 Mobile phone. This will provide them the ability to provide updates directly into PowerOn in or near Real time to provide updates without incurring delays or requiring secondary input. In addition, they will be able to capture photographic evidence of incidents (e.g. Fire Damage, or Third Party Damage) and send to the SharePoint document management solution. In the event of Mobile phone signal not being available due to location, the field staff will revert to the existing voice status update process.									
	Cable Head Register and Service Position Inspection Application (CHR & SPIA)									
	Under the legislation, inspected. approximate asset regist operatives t mobile app as ensuring issues arisin be develope asset health inspections a	Electricity all service For SPEN ely 3.4 millic er. This pro- co replace p will be devel SPEN has a g through th ed that will s h and give and audits.	Safety, Quality and Cor positions and internal mu- this represents the insp on premises as there is no oject will focus on provid aper-based asset surveys w loped to make filling in surv an automated means of co ne accumulation of paperwo serve as an asset register ar greater control over the	ntinuity Regulat ains require to bection and cla existing inspect ing a solution with a mobile a reys simple for the blecting data, e bork. A associated and hold asset da management of	tions (ESQCR) be routinely assification of tion regime or to allow field lternative. A ne user as well eliminating the d database will ta such as the of cable head					
	Internal	£79,619	- III	Internal	£13,324					
year	External <b>Total</b>	£252,930 <b>£332.549</b>	(IFI) financial years	External <b>Total</b>	£276,784 <b>£290.109</b>					
		,• ••		Internal	£0					
Project Cost	£360	.936	Projected 2015/16 costs	External	£0					
	2000,		for SPEN	Total	£0					



	Incident Dispatch & Sta	atus Ma	anagen	nent (II	DSM)					
Technological area and /	This prototype will do updates into the incid the incident controller.	evelop ent ma	a mol inagem	oile ap ient sys	plicatio stem (G	n that iE Pow	: will i verOn)	immed that a	iately i ire visit	insert ble to
	Cable Head Register and Service Position Inspection Application (CHR & SPIA)									
project	Cable Head Inspection will ensure ESQCR compliance by providing a simple survey form to capture critical cable head data and store it in a central database. The solution will firstly be rolled out to IQA (external contractor) who will use their own Windows 8 tablet devices to capture the cable head survey data. A new VPN connection has been set up, to allow the survey data to be returned from the contractor devices to ESRI and SharePoint via Geofield Exchange.									
Type(s) of innovation	Incremental	Sig	nifican	t	Tech subs	nologi stitutic	cal on			
involved	No		No			Yes		No		
Expected Benefits of Project	<ul> <li>Incident Dispatch &amp; State</li> <li>Introduction of Incident terms of a reduction in Incident Control teams</li> <li>3 people would be maresulting from increase</li> <li>Cable Head Register are</li> <li>Ensure ESQRC com</li> <li>Hold all cable head</li> <li>Ensure readiness for Enhanced product forms.</li> </ul>	<ul> <li>Incident Dispatch &amp; Status Management (IDSM)</li> <li>Introduction of Incident Dispatch work status messaging will deliver benefits terms of a reduction in telephone calls and updates required to be handled by telephone control teams in the OCC and NMC. It is anticipated that an FTE saving 3 people would be made and these resource would be re-deployed on LV Contresulting from increased work coming from the LV Control Project.</li> <li>Cable Head Register and Service Position Inspection Application (CHR &amp; SPIA)</li> <li>Ensure ESQRC compliance for service inspections</li> <li>Hold all cable head data centrally in ESRI</li> <li>Ensure readiness for SMART meter roll out</li> <li>Enhanced productivity by replacement of paper based surveys with electro former.</li> </ul>							its in by the ing of pontrol )	
Expected Timescale to adoption	<2 Years Duration of benefit once 8 Years achieved									
				TRL Dev	velopme	ent (St	art – C	urrent	)	
Probability of Success	75%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present N/A at this stage									



	Incident Dispatch & Status Management (IDSM)									
Project Progress March 2015	<ul> <li>Application development complete and obser Acceptance Testing (OAT) carried out</li> <li>Initial concept demonstrated and tested with pilot users</li> <li>Training carried out with all users</li> <li>IDSM rolled out to all zones</li> <li>IDSM now in operational support</li> <li>Project complete</li> <li>Project closedown</li> </ul> Cable Head Register and Service Position Inspection Application (CHR & SPIA)									
	<ul> <li>Sigma Seven Survey Form and server side components released – UAT commenced</li> <li>ESRI auto update development release – UAT commenced</li> <li>Sharepoint sites set up - UAT commenced</li> <li>VPN created – UAT commenced</li> <li>Geofiled release installed on 4 tablets and released to the business for testing/training</li> <li>End – to – end testing commenced</li> </ul>									
Potential for achieving expected benefits	IDSM realising benefits and being used by the business.									
Collaborative Partners	Incident Dispatch & Status Management (IDSM) IRW Cable Head Register and Service Position Inspection Application (CHR & SPIA) IQA									
R&D Providers	Sigma Seven									


Project Title	IFI 1308 – HTIP	IFI 1308 – HTIP										
Description of project	<ul> <li>This project will devel technology for voltage premises initially - h transformer technolog footprint suitable for Advanced Photonics at technology and confirm of the size and cost.</li> <li>The aim of this project 1. Continue the developting optimiser.</li> <li>2. Produce several pressional content of the several pression.</li> </ul>	<ul> <li>Incorrection develop a microprocessor controlled, sincer based solid state schoology for voltage regulation, suitable for voltage optimisation for small remises initially - homes and small businesses. The technology replaces ansformer technology with low cost electronics, active solution and small botprint suitable for meter box installation. Initial work at the Centre for dvanced Photonics and Electronics, University of Cambridge, has validated the schoology and confirmed the potential for transformer replacement at a fraction f the size and cost.</li> <li>Continue the development of a low cost, small footprint, high efficiency voltage optimiser.</li> <li>Produce several prototype models for pre-commercialisation testing.</li> </ul>										
	3. Produce a technica	Produce a technical specification for manufacture.										
Expenditure for financial year	Internal£15,569External£85,040Total£100,610							ernal ernal t <b>al</b>	t t t	E7,011 E31,156 <b>E38,167</b>	,	
Project Cost	£76,516 Projected 2015/16 costs for SPEN							ernal ernal tal	: :	eo eo <b>eo</b>		
Technological area and / or issue addressed by project	<ul> <li>Overvoltage is inherent in the supply of electricity as suppliers all transmission losses and periods of high demand, add to this distributed gent then the result is that the voltage tends towards the higher end of the perange. This is wasteful and results in additional energy consumption and c reduced equipment reliability and lifespan due to higher operating temper. The problem is worldwide.</li> <li>The UK domestic and small business sectors alone represent over 30 premises for which cost-effective solutions are not readily available as all solutions are based on transformers with corresponding size, weight, high c no-load losses.</li> </ul>								rs allov ed gene he pern and cos empera er 30 n as all ex high cos	w for ration nitted st and tures. nillion st and		
Type(s) of innovation	Incremental	Si	ign	nificant	t	Techr subs	nolog tituti	ical on		Radica		
involved	No		,	Yes			No			No		
Expected Benefits of Project	The benefit of such a p market which is afforda customers who may be them energy savings w device might provide th	orojec able a affe vhilst nem v	et v and ecto pr vit	will be d will t ed by rotecti h a de	e to del pe easy over v ng vuli vice to	liver a vo to be re oltage to nerable optimise	oltag etrofi o obt equip e the	e optim itted. Ti tain a d pment. voltage	nising he dev levice For th e at a l	device t rice will that wi ne DNO ocal lev	to the allow Il give 's the el.	
Expected Timescale to adoption	2 Years	Dura achi	ati ev	on of l ed	penefit	once			20 Ye	ars		
Probability of Success	75%	1	-	2	TRL De 3	velopme 4	nt (S 5	itart – C 6	Current 7	t) 8	9	
Project NPV	(Present Benefits x Probability of Success) – Present Costs £340,000											



П

Project Progress March 2015	Initial prototype developed and tested at the PNDC
Potential for achieving expected benefits	The potential for HTIP to deliver an affordable, compact solid state, 'Voltage Optimiser' is very high. They have demonstrated that the technology is viable and that it can be built to a compact size using an affordable bill of materials. The next iteration of the HTIP VO will be close to being market ready at which point UK customers and DNOs can assess its performance and the benefit it provides.
Collaborative Partners	DECC and Energy Innovation Centre
R&D Providers	HTIP Ltd



Project Title	IFI 1310 – Cable Pap	IFI 1310 – Cable Paper Moisture Analyser									
	Most of the HV cab insulation medium. In external shielding of present in surroundin the paper maintains i water. The level of environment, oil ava jointers need to mak and to ensure that th moisture in the paper	les in service in the many cases fault ene the cable. This quite g air, soil or even wa ts hygroscopic prope absorption will dep ilability in the cable, e sure the remaining e paper will provide a is too high faults are	UK and ergy in the e often ex- ter in duc rties which bend on time, te g moisture appropria likely to c	Worldwide ese cables w xposes the ts. Despite ch means it the water emperature e level in th te HV insula occur in the	e use paper as an ill create a break in paper to moisture being soaked in oil will rapidly absorb availability in the etc. In such cases he cable is minimal ation. If the level of same place.						
Description of project	There are two main problems that jointers face. The first is to establish the level of moisture content in the cable at the point of the joint as this is undefined currently. The second is to decide how much of the cable needs to be replaced as a result of moisture ingress. This decision is very important as any further cuts in the cable significantly increase the price of repair due to the cost of excavation and customer minutes lost (CML).										
	A 'hot oil bath' method is currently utilised to determine the moisture content, this method is time consuming in the field and potentially hazardous, additionally it is not objective and has no clear standard. The project will establish if an alternative method can be developed using a multi frequency capacitance approach.										
Expondituro for financial	Internal £14,102	Expondituro in pr	ovious	Internal	£5,140						
year	External £40,615	(IFI) financial year	rs	External Total	£21,207						
				Internal	£0						
Project Cost	£231,450	Projected 2015/1	6 costs	External	£O						
,	,	for SPEN		Total	£0						
Technological area and / or issue addressed by project	<ul> <li>The project consists o</li> <li>Stage 1 will de environment to e and try to establis</li> <li>Stage 2 will devel</li> </ul>	f two stages: evelop the measur stablish proof of prin sh an objective standa op a number of proto	ement m cipal for t ard for pa otype insti	nethodology he multi caj per moistur ruments for	v in a laboratory pacitance approach e measurement DNO trial						
Type(s) of innovation	Incremental	Significant	Techn subst	ological itution	Radical						
Involved	No	Yes	١	No	No						
Expected Benefits of Project	<ul> <li>Successful completion of the project will result in:</li> <li>Improved reliability of cable jointing so reducing a fault re-occurring</li> <li>Replacement of a hazardous method</li> <li>Reduced environmental impact through reduced excavation as a result of fault re-occurrence</li> <li>Reduced CI and CMLs occurring from a more reliable repair</li> </ul>										



Expected Timescale to adoption		2 Years	Duration of benefit once 10 Years achieved							irs		
		TRL Development (Start – Currer								t)		
Probability of Success		50%		2	3	4	5	6	7	8	9	
								$\geq$				
Project NPV		(Present Benefits x Probability of Success) – Present Costs £505,000										
Project Progress March 2015	Th te of Th te Te	ne project had successful schnology and system ha sensitivity whilst also be ne project did not contir erms which had been sig schnology have therefore	Ily com s been eing sm nue to gned u e decid	pleted identif all and stage 2 p to ir ed to ce	the firs ied tha portab due t the D ease th	st stage It can o De for e o a disa Direct Ir e proje	and is perate ase of agreer nvestn ct at t	s showi e with t f use by ment w nent Ag he end	ng goo he nec cable ith the greeme of stag	d prom essary jointers comm ent (DIA ge.	iise. A levels 5. ercial 4). EA	
Potential for achieving expected benefits Collaborative	EA sta a fro re	EATL has progressed well with the project and many of the concerns present at earlier stages have been addressed. Outputs from experimentation have been promising with a clear correlation between moisture content and impedance through multi- frequency scanning. Further stages will build on this promising start and is showing a real potential to deliver the expected benefits identified at the start of the project.									earlier g with multi- ving a t.	
Partners	E١	ENW, NPG, UKPN, EA Technology Limited, Energy Innovation Centre										
R&D Providers	EA	A Technology Limited										



Project Title	IFI 1311 -	IFI 1311 – Green Running										
Description of project	The press ahead. Th smaller sc informing This proje energy ma	ure on LV re ne ability to ale Distribute network rein ect seeks to magement pr	esource unders ed Gen forcem prove rofessio	es and tand theration ent de wheth	capab he nat n (DG) ecision her a t work s	ility will ure of lo ) will bec s, outage technolog successfu	grow ads c come plan gy de illy in	v conti on the increa ning, a evelope identif	nually netwo singly nd rec ed for fying no	in the rk as w importa onfigura the bu etwork	years ell as ant in ation. ilding loads	
	and energ	y sources on t	the dist	tributio	on net	work	1					
Evpanditura far financia	Internal	£14,102	- Even		. in nr		Inte	ernal	£	4,906		
vear	External	£86,315	(IFI)	financi	e in pr al veai	evious	Ext	External		36,615		
year	Total	£100,417	()	mane	ur yeu	5	Tot	al	£41,52			
							Inte	ernal	£	0		
Project Cost	£16	£163,000		Projected 2015/16 costs				ernal	£	0		
,					TOR SPEN				£	0		
Technological area and or issue addressed by project	/ Load and their harm	bad and DG detection, being able to identify types of load on a netwo heir harmonic signatures.							etwork	from		
Type(s) of innovation	Incren	nental	Sig	nifican	t	Techr subs	nolog tituti	ical on				
involved	N	0	No			,	Yes			No		
Expected Benefits of Project	Load and their signa	DG detectior tures.	n, bein	g able	to ide	entify typ	es of	fload	on a n	etwork	from	
Expected Timescale to adoption	3 Y	ears	Durat achiev	ion of ved	benefi	t once			20 Years			
					TRL De	evelopme	ent (S	tart – C	Current	)		
Probability of Success	2	5%	1	2	3	4	5	6	7	8	9	
						🛑						
Project NPV	(Present E Costs	Benefits x Pro	bability	y of Su	ccess)	– Present	t	£1.8m	ı			
	Stage 1 – Ling	rade prototy	ne svst	em usi	ng rea		ta co	mnlete	h			
			nd dire					, inpicto				
	Stage 2 – DNC Stage 3 – Dev	velop a proto	ind dire itype (i	.e. cus	tom so	oftware,	FPGA	solutio	on or u	ising ex	isting	
Project Progress March 2015	Stage $4 - 1^{st}$	Stage prototy	' vpe – tr	rial dev	elopm	ent of a	numl	ber of p	orototy	pes for	each	
	DNO, complet	ted										
	Stage $5 - 2^{10}$ S	Stage prototy	pe DN	O trials	, comp	oleted						
	Project is now	complete.										
Potential for achieving expected benefits	The system h develop their be successful.	as been used prototype fo	l in bui r DNO	lding n so the	nanage re is a	ement se good lev	ttings el of (	s alread confide	dy and ence th	is seeki e syster	ng to n will	
Collaborative Partners	SSEPD, Energy	y Innovation (	Centre									



R&D Providers

Green Running



Project Title	IFI 1312 – V2G										
	With consu automotive alternatively seen a num	mer and go manufactu y-fuelled vel ber of manu	overnm rers a hicles. factur	nental are spe Electri ers' pro	pressu ending c Vehi oducts	re to re vast su cles (EV launche	duce Ims d s) and d or a	transp of mor d assoc bout to	ort CO ney or ciated o be lau	D₂ emis devel hybrids unched.	sions, oping have
Description of project	One of the potential to	additional b assist the g	enefit rid in le	s of ha	iving in d frequ	icreasing ency ma	gly lai anage	rge nur ment.	nbers	of EVs i	is the
	The aim of to use their response to	this project excess rech peak load d	is to in nargea emano	nvestig ble ba ds.	ate the ttery ca	e potent apacity f	ial of to pro	batter ovide p	y-pow ower t	ered ve the g	hicles rid in
	Internal	£15,569	_				Inte	ernal	f	8,180	
Expenditure for financial	External	Expe	enditur financi	e in pre al vear	evious	Ext	ernal	f	2,108		
year	Total	£225,614	(IFI) IIIalicial years			Tot	al	f	10,288		
			Drai	+  <sup>-</sup>	01 5 /1/	+ -	Inte	ernal	f	20	
Project Cost	£813,000		for SPEN			Ext	ternal £0		£0		
							Tot	al	f	20	
Technological area and / or issue addressed by project	EV integrati	EV integration with the grid.									
Type(s) of innovation	Increme	ental	Sig	nifican	t	Tech subs	nolog tituti	ical on		Radical	
Involved	No			Yes			No		No		
Expected Benefits of Project	If successfu the effects connected v	l, DNOs will of EV cha without the r	be ab rging need f	le to c on pe or netv	ontrol ak der vork re	EVs in a nand a inforcen	man nd he nent.	ner tha ence e	it help nsure	s to mit EVs ca	tigate in be
Expected Timescale to adoption	3 Years Duration of benefit once 20 Years										
					TRL De	velopme	ent (S	tart – C	urrent	:)	
Probability of Success	355	%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present Costs £7,709										



	Project progress with respect to identified learning outcomes was as follows:
Project Progress March 2015	<ol> <li>Assess the suitability of a bi-directional charger/inverter for mounting within the car.         <ul> <li>The equipment in a laboratory bench environment performed in line with expectations.</li> <li>The testing at Southampton University of the actual charger/inverter operation was successful.</li> </ul> </li> <li>To investigate communication with vehicle equipment to direct charge/discharge regimes in a safe manner.         <ul> <li>Communications integration was demonstrated over the internet. The equipment has been installed into the prototype vehicle and operated correctly.</li> <li>Following installation in the prototype vehicle full testing of the vehicle system is due for testing around mid-May 2015.</li> </ul> </li> <li>To investigate the effect of a charge/discharge cycle on battery life.         <ul> <li>Results of the 153 automated test cycles undertaken to date reveals no deterioration of the battery.</li> </ul> </li> <li>To ascertain the efficiency of the charge/discharge cycle applied to automotive lithium ion batteries.         <ul> <li>No data received to date.</li> </ul> </li> </ol>
Potential for achieving expected benefits	<ul> <li>High, due to the significant potential of this technology as a form of energy storage to complement the increasing development of renewable technologies.</li> <li>In addition, the desire to delay or avoid the construction and operation of fossil fuel powered plant increases the potential for this technology to be implemented.</li> <li>SPEN has decided not to progress this project to the next phase. Consequently we will be closing this project.</li> </ul>
Collaborative Partners	SSEPD, WPD, UKPN
R&D Providers	Future Transport Systems / University of Southampton



Project Title	IFI 1315 – Ultrapole	FI 1315 – Ultrapole									
	Wooden poles are used extensively throughout the utility networks to carry LV and HV overhead networks across open countryside and in rural areas. Current Health & Safety legislation demands that risk assessments are regularly undertaken to assess their health status in terms of the remaining load bearing strength of the pole, which is usually buried to a good depth in soil or tarmac. The pole may extend to several metres in height.										
Description of project	Currently, this assess assess the state of the its length) and at the some risk to the ope structure.	ment requires the us pole close to its mai root of the pole. Th rative, either in clim	e of ladde n load bea is is both bing or d	ers and clim aring area ( time consi igging arou	nbing equipment to the top one third of uming and involves nd the base of the						
	There are currently several invasive instruments on the market for detecting wood rot, based on both acoustic (hammer in nail, tap and listen) and ultrasonic (slice shadow) technologies. Ultrasound works in this environment by detecting changes in wood density which results in an acoustic path impedance variation between different wood densities. This change can be caused by rotted fibres within the pole, or other features such as drilled holes etc. This density change produces a discernible energy reflection at the boundary which can be analysed and visualised in an instrument.										
Even and its una fam financial	Internal £14,102	Internal	£4,906								
year	External £11,684	(IFI) financial year	rs	External	£26,541						
•	Total £25,786			Total	£31,447						
		Projected 2015/1	6 costs	Internal	£25,000						
Project Cost	£75,000	for SPEN	0 00505	External	£10,000						
				Total	£35,000						
Technological area and / or issue addressed by project	Testing of wood poles in nature and result in the result of testing is the length of the pol overhead line under a for the company.	by existing methods the inappropriate re localised to the poin e can go undetected adverse weather con	such as l placemer t of test, d which c ditions le	nammer tes at of poles v abnormaliti an result ir ading to CI	st can be subjective with residual life. As ies elsewhere along in the failure of the and CML penalties						
Type(s) of innovation	Incremental	Significant	Techn subst	ological itution	Radical						
Πνοινέα	No	No	Y	'es	No						
	The ability to sca anomalies' such a	n very rapidly long po is the presence of rot	ole length in the po	s for the pr le.	resence of 'acoustic						
	<ul> <li>Increased knowle targeted mainten</li> </ul>	dge and understandi ance and replacemer	ng of con nt based o	dition of w	ood poles, allowing of asset.						
Expected Benefits of Project	Reduced costs or assessment (scan	f surveying poles (no ning whole pole) ther	o climbing efore less	g of pole). s waste fror	More accurate rot n misdiagnosis.						
	Reduced failure of lines and improve	of wood poles leadir ed network performar	ng to redunce.	uced Cls/Cl	MLs from overhead						
	<ul> <li>If this non-intrusive testing methodology is proven it will reduce risk exposure for linesmen, operational staff and third parties.</li> </ul>										



Expected Timescale to adoption		3 Years	Duration of benefit once 25 Years						ars		
					TRL De	velopm	ent (S	tart – Current)			
Probability of Success		35%	1	2	3	4	5	6	7	8	9
							$\land$				
Project NPV		(Present Benefits x Probability of Success) – Present Costs £802,753									
Project Progress March 2015	The ma Sta Sep We sub	e project started in Janu Iterial established and to oge 1 Exploration, Scio otember 2014. There we est and Northern Pow osequent delays in movi oge 2 of this project will	uary 20 est equ ence f ere de erGrid ing to S be con	014. Init lipment Review, lays wit no lor Stage 2. tinued	tial kick t ordere /Techne th the L nger w under	c off me ed. ology / egal ag vished -	eeting Assess greem to be ding.	comple ment ent wh part o	eted. S was co en Elec of the	upply c omplete ctricity projec	of test ed in North t and
Potential for achieving expected benefits	Pro pro	oject started in January 2 obability of success.	2014, p	otentia	al for ad	chieving	g expe	cted be	enefits	as per a	above
Collaborative Partners	SSE	SSEPD and UK Power Networks									
R&D Providers	Αсι	uity Products Ltd									



Project Title	IFI 1316 – Upgradin	FI 1316 – Upgrading Legacy GM NCP to Plexman 2										
	Smart Grid Networks NCP control and com network behaviour (P	(SGN) and SPEN have munication system th lexman system).	e togethe nat provid	er developed des an incre	d a 2nd-generation eased awareness of							
	One of the key comp protocol that is comp NCP RTU (NMS100).	onents in this system atible with all legacy	is the Rf NCP equi	O150 radio	with an enhanced er than the RADIUS							
Description of project	The majority of 1st-ge and therefore canno employed to suppo generation equipmen	eneration NCPs on the ot take advantage of rt the communication t.	e networl f the ne on syste	k are fitted ew system, em of any	with NMS100 RTUs nor can they be surrounding 2nd							
	SGN have been approached to develop an inexpensive solution to interface the RFO150 radio into the NMS100 RTU to enable the legacy system to benefit from the significant enhancements offered by the new system at a very low capital cost. The new Plexman system is likely to be the model for the 2nd-generation NCP to be deployed across the network via the RIIO-ED1 NCP asset expansion program. To facilitate deployment, it is important that the system is backward compatible with the legacy NCP asset base.											
For an ditum for firms in t	Internal £23,808	ernal £23,808 Internal £8,552										
year	External £11,684	(IFI) financial years	s s	External	£44,707							
	Total £35,492			Total	£53,259							
		Projected 2015/16	5 costs	Internal	EU EO							
Project Cost	£33,166	for SPEN		Total	£0 <b>f0</b>							
Technological area and / or issue addressed by project	The aim of the proj RFO150 radio into th the significant enhanc	ect is to develop an e NMS100 RTU to ena ements offered by the	inexpen able the e new sys	sive solutio legacy syste stem at a ve	n to interface the em to benefit from ry low capital cost.							
Type(s) of innovation	Incremental	Significant	Techn subst	ological itution	Radical							
involved	Yes	No	1	No	No							
	The system will provid	le the following benef	its:									
	• Enable the 2n legacy NCP ass	d-generation system et base.	to be fu	lly compatil	ble with the entire							
	An inexpensive functionality to the second sec	ve solution to prov the legacy system inc	vide all cluding:	2nd-genera	ation NCP system							
Expected Benefits of	Significantly er	hanced radio commu	nications	i								
Project	Analogue data	recovery										
	Enhanced digit	al I/O										
	Remote radio	and IED programming										
	Increased robu	istness of any future P	Plexman r	adio system	1							
Expected Timescale to adoption	1 Year	1 Year Duration of benefit once 10 Years										



					TRL De	velopm	nent (S	tart – C	Current	)		
Probability of Success		90%	1	2	3	4	5	6	7	8	9	
											>	
Project NPV		(Present Benefits x Pro Costs	babilit	y of Su	ccess) -	- Prese	nt	£2,796,290				
Project Progress March 2015	Th RI Th Us	he workshop trial was successful and the device will be rolled out onto the syste IIO-ED1 investment programmes. his project is now closed and the technology has now been adopted as Busines Isual									em in ess As	
Potential for achieving expected benefits	Tł	he potential for achieving expected benefits remains very high										
Collaborative Partners	N	lone										
R&D Providers	Sr	Smart Grid Networks Limited										



Project Title	IFI 1317 – Cable Core Temperature Monitoring										
Description of project	DNOs need to know the cooperation at its limit – its current transformer (CT) has some drawbacks, part requires that the supply physically separated at the each phase. This potential the CT technology is related to the monitoring at many points.	DNOs need to know the current flowing in a cable in order to assess how close it is to operation at its limit – its "ampacity". The commonly used existing method utilises a current transformer (CT) applied around each signal phase. However this approach has some drawbacks, particularly when used with three-phase underground cables. It requires that the supply to the customer is interrupted and that the phases are obysically separated at the measurement point, so that the CT can be placed around each phase. This potentially restricts where measurements can be made. Furthermore the CT technology is relatively costly for large scale deployment, particularly for monitoring at many points in a more distributed generation network or a "smart grid".									
Expenditure for financial year	Internal         £14,102           External         £11,684           Total         £25,786	ternal£14,102Internal£4,90kternal£11,684Expenditure in previous (IFI) financial yearsExternal£52,7otal£25,786Total£57,6									
Project Cost	£206,000 Projected 2015/16 costs for SPEN						ernal ernal al	f f f	:0 :0 : <b>0</b>		
Technological area and / or issue addressed by project	There is a need for a low cost substitute for a CT that can be easily retro-fitted without supply interruption. There is a strong relationship between cable current and its operating temperature, so it is proposed to provide a simple, low cost retro-fit temperature sensor, for instance applied in the same way as a cable tie, that can be used by a DNO to easily deduce cable current to a reasonable accuracy level (e.g. +/-5 to +/-10%).										
Type(s) of innovation	Incremental	Si	gnifican	t	Techn subst	iolog tituti	ical on	Radical			
Involved	No		No		٢	Yes		No			
Expected Benefits of Project	<ul> <li>The expected benefit retro-fitted sensor for a 3-phase electricity n</li> <li>Using cable temperate this approach to prov transformers. It also temperature sensing</li> </ul>	of thi meas etwor ure to ide a li o pro	is proje uring a k powe infer th ower co vides	ct is tl nd/or o r cable e curre ost, mo a retr	ne validat deducing ent in a ca ore easily o-fit alte	tion the t able o insta	of a co empera offers tl alled alt ive to	he posi ternativ fibre	for an of the co sibility t ve to cu -optic	easily ore of co use urrent cable	
Expected Timescale to adoption	3 Years	3 Years Duration of benefit once 25 Years									
				TRL De	evelopme	nt (S	tart – C	urrent	)		
Probability of Success	35%	1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x Probability of Success) – Present Costs £194,965								I		



Project Progress March 2015	<ul> <li>The project started in December 2013. Stage 1 – (Analytical and experimental proof of principle work) has been completed. The direct temperature measurement technique has been adopted as the favoured method.</li> <li>Stage 2 (Proof of Concept Laboratory Prototype) was successfully completed in July 14. Stage 3 (Proof of Concept &amp; Live Trial) began in Sept 14 with a Site trial in March 15.</li> <li>Project is now complete.</li> </ul>
Potential for achieving expected benefits	The project has shown that cable core temperature can be predicted with reasonable accuracy from easily accessed measurements of the cable exterior, and there may be techniques to improve the impacts of thermal lag so that a temperature sensing method can provide a range of useful measurements to assist with network management.
Collaborative	Scottish Hydro Electric Power Distribution, Electricity North West, Northern
Partners	Powergrid, UK Power Networks and Energy Innovation Centre
R&D Providers	The Technology Partnership plc



Project Title	IFI 1318 – VTOL							
	The use of helicopters to inspect overhead line assets is an expensive exercise and significant cost savings could be realised by the deployment of unmanned aerial systems. A number of the UK DNOs are already successfully using unmanned aerial systems (UAS) for inspection tasks. However these systems are not suited to Beyond Visual Line Of Sight [BVLOS] operations.							
	To achieve this demanding goal of BVLOS, requires an expert approach to addressing the following three critical issues for electricity overhead-lines:							
Description of project	<ul> <li>Clearly defining B (CAA) can be soug</li> </ul>	VLOS operations for ht and secured.	which Civil	l Aviation	Authority Approval			
	<ul> <li>A financial analysi BVLOS operations DNOs and be viab</li> </ul>	s that can provide a s will provide the be le for current and/or	clear indica st Return as yet unde	ation as to On Invest efined futu	where categorised ment [ROI] for the ire operations.			
<ul> <li>Specifying a Remotely Piloted Aerial System (RPAS) that can provendurance capability and fly BVLOS as well as meeting CAA requirements.</li> </ul>								
Funenditure for finencial	Internal £14,102	Funda dituna in an		Internal	£9,583			
Expenditure for financial vear	External £68,851	(IFI) financial year	evious	External	£11,541			
1	Total £82,953	(,	•	Total	£21,124			
		Projected 201E /1	6 costs	Internal	£15,000			
Project Cost	£416,000	for SPEN	0 00313	External	£10,000			
				Total	£25,000			
Technological area and / or issue addressed by project	The goal of this proj specification for Remo Sight for electricity die the UK Civil Aviation a position to decide wh fund acquisitions or introduce such system close co-operation wi	ect is to be able to otely Piloted Aircraft stribution network ac Authority. By the end nether it wants to in development as nec- ns into service for BV th and as agreed by th	define an Systems op erial inspect I of the provest in suc essary and LOS operat	industry perating Be tion opera oject, the i ch systems with the tions in a s	standard electricity eyond Visual Line Of tions, confirmed by ndustry will be in a a and if affirmative, goal of starting to tepwise manner, in			
Type(s) of innovation	Incremental	Significant	Techno substit	ological tution	Radical			
IIIVOIVEU	No	No	N	0	Yes			



	A UAS offers significant cost savings when compared to helicopter deployment. Being able to operate beyond the visual line of sight will result in significantly more circuit kms being surveyed during inspection periods.									
	Other benefits that un	manneo	d aerial	system	ns will b	oring ir	nclude:			
	Minimising en	Minimising environmental impact with greatly reduced fuel consumption.								
Expected Benefits of	<ul> <li>Minimised dis inspection.</li> </ul>	ruption	n to lan	d owne	ers, live	stock	and loo	cal resi	dents c	luring
Project	• Reduced risk to life and limb by using un-manned apparatus to retrieve data.									
	• Reduced Civil Aviation restrictions in the vicinity of airports, chemical plants, MOD land etc.									
	Limit the effect	ct of sta	ind dov	vn time	due to	bad v	weathe	r or str	ong wir	nds.
	Reduced num railways or ho	bers of using e	"misse states	ed towe etc.	ers" by	not h	aving to	o avoid	motor	ways,
Expected Timescale to adoption	3 Years	3 Years Duration of benefit once 30 Years								
		TRL Development (Start – Current)								
Probability of Success	10%	1	2	3	4	5	6	7	8	9
	(Present Benefits y Pre	hability	y of Su		Drocor	<b>h</b> t				
Project NPV	Costs	babiiit	y 01 50		TTESET	it.	£624,4	442		
Project Progress March 2015	Stages 1 was successfully simulation environments) currently in Phase 3 (Devi paths within the simulatio This project will be contine	comple starte elop the n envire ued und	eted in d in O e ConC onmen der NIA	Sept 1 ct 14 a ps inco t for ev	L4, Stag and co orporat aluatio g.	ge 2 (l mplete ing flig n and	Establis ed Jan ght mai test)	h base 15. Tł noeuvr	e opera ne Proj es and	tional ect is flight
Potential for achieving expected benefits	The approach of this prostage in order increase the	ject is o e poten	designe tial for	ed to a achievi	ddress ng exp	the C ected	AA req benefit	uireme s.	ents at	every
Collaborative Partners	SHEPD, UKPN, Northern P Networks plc., Southern G	owergri as Netv	id Limit vorks p	ed, No lc.	rthern	Gas Ne	etworks	s, Scotl	and Ga	s
R&D Providers	VTOL									



Project Title	IFI 1401 – VONAQ							
	As per IFI 1315 Ultra	pole	:					
	Wooden poles are used extensively throughout the utility networks to carry LV and HV overhead networks across open countryside and in rural areas. Current Health & Safety legislation demands that risk assessments are regularly undertaken to assess their health status in terms of the remaining load bearing strength of the pole, which is usually buried to a good depth in soil or tarmac. The pole may extend to several metres in height.							
Description of project	Currently, this assess assess the state of the its length) and at the some risk to the op structure.	smei ie po e ro erati	nt requires the us ble close to its mai ot of the pole. Th ive, either in climi	e of laddo n load be is is both bing or d	ers and clim aring area ( 1 time consi igging arou	nbing equipment to the top one third of uming and involves nd the base of the		
	There are currently s rot, based on both a shadow) technologie	evei acou s.	ral invasive instrur stic (hammer in n	nents on Iail, tap a	the market nd listen) a	for detecting wood nd ultrasonic (slice		
	This project differs to Ultrapole by utilising a different type of sensing technology that has already been deployed in an off the shelf solution for the European Telecommunication Industry. The VONAQ product utilises an acoustic sensor head that provides a quantifiable score for telecommunication pole health. This project will look to identify if the VONAQ product can be calibrated to provide the same function for electrical distribution poles. This will require significant field trials given the range of poles and their associated furniture on UK networks.							
	Internal £14,102				Internal	£0		
Expenditure for financial	External £11,684		Expenditure in pr	evious	External	£0		
year	Total £25,786		(IFI) financial year	rs	Total	£0		
					Internal	£15,000		
Project Cost	£266,525		Projected 2015/1	6 costs	External	£70,000		
			IOI JI EN		Total	£85,000		
	As per IFI 1315 Ultrapole:							
Technological area and / or issue addressed by project	Testing of wood pole in nature and result the result of testing the length of the po overhead line under for the company.	es by in th is loo ole c adv	y existing methods le inappropriate re calised to the poin can go undetected verse weather con	s such as placemer t of test, d which c ditions le	hammer tes nt of poles v abnormaliti an result ir ading to Cl	st can be subjective with residual life. As les elsewhere along in the failure of the and CML penalties		
Type(s) of innovation	Incremental		Significant	Techn subst	ological	Radical		
Involvea	No		No	١	/es	Yes		



	•	• The ability to scan wooden distribution poles for the presence of 'acoustic anomalies' such as the presence of rot in the pole.										
	•	<ul> <li>Increased knowled targeted maintena</li> </ul>	lge and nce an	l under d repla	standir cemen	ng of co t based	nditic on co	on of w ndition	ood po of asse	oles, allo et.	owing	
Expected Benefits of Project	•	<ul> <li>Reduced costs of assessment (scann</li> </ul>	survey ing wh	ing po ole pol	les (no e) there	climbii efore les	ng of ss was	pole). ste fron	More n misdi	accurat agnosis	e rot 5.	
	•	<ul> <li>Reduced failure of lines and improved</li> </ul>	f wood I netwo	l poles ork per	leadin; forman	g to reo ce.	duced	CIs/CN	ЛLs fro	om over	rhead	
		If this non-intrusive testing methodology is proven it will reduce risk exposure for linesmen, operational staff and third parties.									re for	
Expected Timescale to adoption		2 Years	Durat achie	ion of ved	benefit	once		>8 Years				
					TRL De	velopm	nent (Start – Current)					
Probability of Success		75%	1	2	3	4	5	6	7	8	9	
									$\geq$			
Project NPV		(Present Benefits x Pro Costs	babilit	y of Su	ccess) –	- Presen	t	See co NIA_N Regist	ost ben IPG 000 tration	efits in 01 Docum	ent	
Project NPV Project Progress March 2015	As c and com See	(Present Benefits x Pro Costs of March 2015 this pro a full project plan de ppliant agreement the o NIA_NPG 0001	babilit oject ha velope official	y of Sud ad bee d, how start o	ccess) - n fully ever gi f this pi	- Presen specifie iven the roject ha	t d by e dela as bee	See co NIA_N Regist the Col ys in tl en held	IPG 000 IPG 000 cration laborat ne sign back u	efits in 01 Docum tive Par ing of a ntil ED1	ent rtners a NIA 1.	
Project NPV Project Progress March 2015 Potential for achieving expected benefits	As c and com See As t requ exp dist	(Present Benefits x Pro Costs of March 2015 this pro a full project plan de ppliant agreement the o NIA_NPG 0001 this project looks to con uirements of DNOs, th ected benefits. Howev ribution wood poles wi	babilit oject ha velope official nvert a nere is ver, it Il rend	y of Sud ad been d, how start of n exist a high is still er this	ccess) - n fully rever gi f this pr ing mai proba unclea solution	- Presen specifie iven the roject has rket pro bility the n unfeas	d by e dela as bee duct nat th tensi sible.	See cc NIA_N Regist the Col ys in tl en held and con is projution and	laborat in sign back u	efits in 01 Docum tive Par ing of a ntil ED1 to mee I delive nt place	ent rtners a NIA 1. et the er the ed on	
Project NPV Project Progress March 2015 Potential for achieving expected benefits Collaborative Partners	As c and com See As t requ exp dist	(Present Benefits x Pro Costs of March 2015 this pro a full project plan de ppliant agreement the of NIA_NPG 0001 this project looks to con uirements of DNOs, th ected benefits. Howev ribution wood poles wi	babilit oject ha velope official nvert a nere is ver, it Il rend	y of Sud ad bee d, how start o n exist a high is still er this	n fully ever gi f this pr ing mai proba uncleai solution	- Presen specifie iven the roject he rojec he rojec he rojec he roje he rojec he rojec he rojec he rojec he rojec he rojec he rojec he roje he roje rojec he rojec he rojec he roje he roje he rojec he rojec he rojec he rojec he roje roje roje roje roje roje roje roj	d by e dela as bee duct tat th tensi sible.	See cc NIA_N Regist the Col ys in tl en held and con is proj-	Dest ben IPG 000 ration laborat he sign back u hvert it ect wil I weigh	efits in 01 Docum tive Par ing of a ntil ED1 to mee I delive nt place	ent thers a NIA L. et the er the ed on	



Project Title	IFI 1404	– Urban NCP	Enhancement Project						
	In DPCR across th tele-swit that con have be- custome schemes not have	In DPCR5 SPEN rolled out multiple Network Controllable Point (NCP) scheme across the rural 11kV networks. These NCP schemes utilise remote fault sensor an tele-switching technology to quickly identify and switch out the zone of the circu that contains the fault and restores supplies to all the other zones. The scheme have been proven to be effective in improving the security of supply for ou customers, as such; In ED1 SPEN is giving consideration to rolling out further NC schemes but this time focussing in on our meshed 11kV urban networks that d not have unit protection already							
	This proj that coul	ect focusses on d potentially en	the development and trial thance the performance of a	of two emergin In Urban NCP sch	g technologies neme.				
	1.	Directional Faul	It Passage Indicators (dFPIs)						
Description of project		Identifying the more challengi Indicators (FPIs doing so requi benefits of a mo	faulty 'zone' on an 11kV n ng than on a radial circuit ) to work it would require t ires additional reinforceme eshed network.	neshed network . For traditional SPEN to un-mes ent and loses tl	is significantly Fault Passage h the network, he operational				
		dFPIs have the potential to locate faults without the requirement to un- mesh the network, as such one part of this project looks at the development and trial of a low cost dFPI that could facilitate the rollout of Jrban NCP schemes.							
	2.	Automated Link	K Box Sectionalisers (ALBS)						
		NCP schemes s circuit (Primar automatically s customer suppl Low Voltage (LV the one with a existing links operational SPE LV network whi	segregate 11kV circuits int y – Primary) into four witched in/out to remove 1 lies. To do so effectively it i /) path for the fault current fault in it. Where the meshe between zones, prior to EN has to undertake signific ich may preclude the schem	te 11kV circuits into 'zones' typically breaking a imary) into four zones. These zones can be in/out to remove 11kV network faults and restore do so effectively it is important that there is not a or the fault current to flow from a healthy zone to t. Where the meshed LV network means there are n zones, prior to the NCP scheme becoming o undertake significant reinforcement work on the preclude the scheme.					
	The development of LV automation products in DPCR5 now means that it may be possibly to install LV ALBS on the network that automatically un- mesh and re-mesh LV networks during faults and restoration. If this proves to be the case then this technology will open the rollout of Urban NCP schemes to circuits previously precluded. This project looks to develop and trial several ALBS devices to see if they can perform this function reliably without the need for communications.								
	Internal	£14,102		Internal	£0				
Expenditure for financial vear	External	£234,057	Expenditure in previous	External	£0				
, ·	Total	£248,159	. ,	Total	£0				
Project Cost	£2	248,159	Projected 2015/16 costs for SPEN	Internal External Total	£50,000 £250,000 <b>£300,000</b>				
Technological area and / or issue addressed by project	This proj automat and resto	Total£300,000This project looks at the development and application of emerging sensor and automation technologies in a novel arrangement to speed up the location of faults and restoration of customers.							



Type(s) of innovation	Incremental Significant S					nolog stituti	ical on	Radical		
involved	Yes		No			No			Yes	
Expected Benefits of Project	<ul> <li>Reliable low speed up the</li> <li>Proven ALBS LV networks</li> </ul>	<ul> <li>Reliable low cost dFPIs that can be applied across UK 11kV networks to speed up the location and restoration of faults.</li> <li>Proven ALBS that can be utilised by UK DNOs to reliably auto-sectionalis LV networks without the need for communications.</li> </ul>								rks to nalise
Expected Timescale to adoption	2 Years	Durat achie	tion of ved	benefit	once			7 Year	ſS	
				TRL De	velopm	ent (S	tart – C	Current	)	
Probability of Success	75%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x P Costs	robabilit	y of Su	ccess) –	- Preser	nt	See co NIA_S Regist	ost ben SPEN 00 tration	efits in 107 Docum	ent
Project Progress March 2015	The dFPIs developed by the PNDC and their per- with the trial of 50 units and will be ready for dep SPEN has worked with th and EA Technology) to doing so SPEN has gaine of tailoring the function schemes. As such all thre trial in Q3 of 2015. This project will be con dFPIs and ALBS are trialle	Nortech formance out on t bloyment nree man outline t d confid ality of t ee manu tinued u ed appro	have b have b he network t in Q3 o nufacture the fun ence th their pr facture under N priately	veen te iven SF vork. Ti of 2015 rers of ctional tat all t oducts rs are t IIA fund /.	sted in PEN cor hese un 5. LV auto ity requ hree m to me now ma ding fro	severa nfiden nits are omatio uired f anufac et the anufac om Q3	al oper ce eno e now b on proo from th cturers requir turing 3 2015	ational ugh to being m ducts (E he ALB: have ti ements devices to ens	scenar press a anufac PS, Kel 5 devic he capa 5 of the 5 for SP ure tha	ios at ihead tured vatek es. In ability e NCP EN to at the
Potential for achieving expected benefits	The dFPIs developed has confidence in their pote Network trials are still performance. Working with the man confidence in the technol able to identify if ALBS te	ave been ential to I requir ufacture ology, ho echnolog	n teste perforn ed tho rs of t owever cy is rea	d at th m as re ough to he LV until n dy for I	ne PND equired o fully automa network BaU dep	C, so and t unde ation trials oloym	SPEN therefo erstand produc take p ent.	has alr re deli and ts has lace w	eady g ver ber assess given e will n	ained nefits. their SPEN oot be
Collaborative Partners	Electricity North West (S	upplying	EPS AL	.BS dev	ices to :	SPEN)				
R&D Providers	Kelvatek, EA Technology	, EPS and	the PN	NDC.						



Project Title	IFI 1405 – Augmente	d Reality: Proof	of Concep	ot								
Description of project	<ul> <li>The proof of concept augmented reality with determine whether ner provide benefits for feasibility testing, two</li> <li>In-situ display of customers how an</li> <li>With currently av augmented reality</li> </ul>	In a proof of concept that was conducted to investigate the use of mobile ugmented reality within SPEN for the display of utility assets. It was designed to etermine whether new technology and existing asset data could be integrated to provide benefits for both internal and external stakeholders. To guide the easibility testing, two primary use cases were identified; In-situ display of planned above ground to demonstrate to land owners / customers how an area of interest would look once the assets were built With currently available technology and existing internal data would an augmented reality application be a viable addition or alternative to mobile GIS for the location and identification of buried assets by field-based staff										
	for the location an	for the location and identification of buried assets by field-based staff										
Expenditure for financial	Internal £14,102	Expenditure in r	revious	Inte	ernal	£	20					
year	External £34,939	(IFI) financial ye	ars	Ext	ernal	£	20					
	Total £49,041			Tot	al	£	0					
		Projected 2015	Inte	ernal	£	0						
Project Cost	£28,280	for SPEN	10 00505	Ext	ernal	£	20					
				Tot	al	£	20					
Technological area and / or issue addressed by project	relevant digital inform predominantly capture Two main types of 'mo 'smart' devices such Computer Vision (CV). The proof of concept primarily for delivering	Augmented Reality (AR) is a common term for the process of taking context relevant digital information and overlaying it on live images of the real-world, predominantly captured through a video camera. Two main types of 'mobile' augmented reality exist and are possible using modern 'smart' devices such as phones, tablets and wearable devices; Spatial and Computer Vision (CV). The proof of concept project utilised the Awila Cloud API which was developed primarily for delivering Spatial AR visualisations (a 'scene').										
Type(s) of innovation	Incremental	Significant	Techr subs	nolog tituti	ical on	Radical						
IIIvolveu	No	Yes		No			No					
Expected Benefits of Project	The project expected t can be viewed for the applications including finding, asset tracking a	o aid our learning e benefit of our c but not limited t and the visualisatic	and under ustomers o, land o n of propo	stand and wner osed o	ling int employ negot develop	o how rees fo iations oments	our GIS r a ran , cable	S data Ige of fault				
Expected Timescale to adoption	Not applicable at this stage	Duration of bene achieved	fit once			N/A						
		TRL	Developme	ent (S	tart – C	Current	)					
Probability of Success	5%	1 2 3	4	5	6	7	8	9				
Project NPV	(Present Benefits x Probability of Success) – Present N/A											



Project Progress March 2015	The project has successfully identified and analysed the technical challenges involved in creating an augmented reality scene from GIS data. It facilitated the development of solutions for these challenges, whilst breaking new ground in both disciplines in the process. The in-situ display of existing and planned assets was been successfully demonstrated and was shown that available technology could be a viable addition or alternative solution to for current mobile GIS solutions. However the overriding conclusion to this project is without significant investment in R&D there are elements of the solution that cannot be fully automated, even if the required hardware is currently available on the market. From this perspective we have identified cost-effective semi-automated processes which would suffice in the vast majority of cases, and satisfied the use cases defined for the pilot. Accuracy in both device and object positioning, as well as scaling, are of paramount importance in creating and trusting the scene being rendered on screen. The pilot solution was unable to accurately represent existing data, therefore further experimentation and validation under controlled conditions would be required before the solution could be adopted. This project is now closed.
Potential for achieving expected benefits	Further experimentation and validation under controlled conditions would be required before the potential for achieving expected benefits could be determined.
Collaborative Partners	ESRI UK
R&D Providers	Augmented Technologies



Project Title	IFI 1411 – eGenius		IFI 1411 – eGenius										
Description of project	The development of a domestic properties common appliances a measurement close to to a mobile device Ap appliances have cont NILM can also be replacement of applia	The development of a prototype Non-Intrusive Load Measurement (NILM) unit for domestic properties that autonomously detects the consumption profile of common appliances and loads in the property from a single voltage and current measurement close to the meter cabinet. In doing so the NILM can communicate to a mobile device App to show the residents in real time and historically how their appliances have contributed to their total consumption and electricity bill. The NILM can also be utilised to identify and make recommendation for the replacement of appliances that have a higher than expected consumption.											
Expenditure for financia year	Internal         £14,102           External         £61,584           Total         £75,686	Exp (IFI)	enditur financi	e in pr al yea	evious rs	Inte Exte <b>Tot</b>	ernal ernal <b>al</b>	£ £ £	0 0 <b>0</b>				
Project Cost	£49,900	Pro for	Projected 2015/16 costs for SPEN				ernal ernal al	f f f	0 0 <b>0</b>				
Technological area and , or issue addressed by project	It is thought that the eGenius NILM can be utilised by DNOs to educate customers, particularly the fuel poor, to understand how each appliance contributes to their electricity bill. In doing so the NILM empowers the customers with the knowledge to make changes that will hopefully lead to a reduction in their consumption.												
Type(s) of innovation	Incremental Significant Technological substitution						Radical						
Involved	No		No			Yes			No				
Expected Benefits of Project	Proof that NILM tech customers of their c makes to their total project it opens the o societal benefits it car	Proof that NILM technology can deliver the type of analysis required to educate customers of their consumption patterns and the contribution each appliance makes to their total electricity bill. If the NILM concept can be proven in this project it opens the door to customer trials of the technology to ascertain what societal benefits it can release.											
Expected Timescale to adoption	2 Years	Dura achie	tion of l eved	benefi	t once			8 Year	S				
				TRL De	evelopm	ent (St	tart – C	Current)					
Probability of Success	25%	1	2	3	4	5	6	7	8	9			
Project NPV	Present Benefits x Pr Costs	obabilit	y of Su	ccess)	– Preser	nt	Not a stage	pplicab	le at th	is			
Project Progress March 2015	As of March 2015 the I delivered the first protot performance in a domest There is presently no fur course of 2015 SPEN will them in the properties of to the project partner wh A decision will be made customer trial planned fo	FI proje ype NIL ic envir ther pla assess SPEN e o is pla by SPI r Q4.	ect is cl Ms and onment anned e the pe employe nning to EN in C	osed. the c xpenc rforma ees. SF conti	The pro orrespon liture or ance of t PEN will nue the 5 on wi	pject p nding this p the NI provid develo hether	partner iTunes project LM pro le feed opmen	s have App to totype back or t the Ni irsue a	succes assess ver ove s by tr these LM po NIA fu	ssfully their er the ialling trials st IFI. unded			



Potential for achieving expected benefits	At the close of the IFI project the potential for NILMs to deliver their expected benefits is still unknown; however, through SPENs ongoing trials it is expected that this will be come much clearer prior to the end of 2015. The eGenius NILM certainly has the ability to identify the consumption profiles of appliances with a simple load pattern and high power draw, i.e. kettle, hair dryer, coffee machine, bottle steriliser. But it is not yet certain how the NILM will perform ascertaining the performance of appliances with a lower consumption (lighting etc.) and appliances with complex load profiles such as washing machines and dishwashers.
Collaborative Partners	SSEPD and Energy Innovation Centre
R&D Providers	Green Running



Project Title	IFI 1412 —	Phase ID										
Description of project	The identif presently a	ication, desk wailable on t	top ar he ma	nd field rket in <sup>-</sup>	evalua the EU	ation of and No	f LV Pł orth Ar	nase Id nerica.	entifica	ition de	evices	
Expenditure for financia year	Internal External	£14,102 £22,599	Expe (IFI)	enditur financi	e in pre al year	evious s	Inte Ext	ernal ernal	f	0		
	Total	130,701					Inte	an	f	0		
Project Cost	£26	701	Proj	ected 2	015/10	6 costs	Fyt	ernal	f	0		
Floject Cost	LSC	,,,01	for S	SPEN			Tot	otal <b>£0</b>				
Technological area and , or issue addressed by project	The identif the LV ne enabling th fault location Present Ph to install t identified a This projec	The identification of the phase that each individual customer is connected to on he LV network can provide benefits for the customer and DNO in terms of enabling the connection of low carbon technologies (LCT) or the acceleration of ault location and restoration. Present Phase Identification equipment utilised by DNOs requires authorised staff to install the equipment and only allows a small section of the network to be dentified at a time before the equipment needs to be relocated. This project is aimed at finding a Phase ID device that:										
	• Do	pes not requi	re aut	horised	staff t	o instal	ll it					
	Covers a large section of the network from one installation point											
	• Ge	enerates inst	ant res	sults at	each p	roperty	/					
Type(s) of innovation	Increm	ental	Sig	nifican	t	Technological substitution						
involved	Ye	S		No			No			Yes		
Expected Benefits of Project	The identif framework operated b Such a de connectivit meter / cut	fication of a partners. N y non-author vice can be y on the ne t out inspecti	Phase With rised s utilise etwork ons.	ID tecl the de taff, ge ed by as an	nnolog vice c neratir DNOs increr	y that o apable ng insta and co mental	can be of be nt resu ontract additie	utilise eing sa ults at t ors to on to	ed by U afely ir the prei map 1 routine	K DNO nstalled mise. the net inspec	s and and work ctions	
Expected Timescale to adoption	1 Ye	ears	Durat achie	ion of l	penefit	once			8 Yeaı	ſS		
					TRL De	velopm	nent (S	tart – C	Current	)		
Probability of Success	75	5%	1	2	3	4	5	6	7	8	9	
Proiect NPV	(Present B	enefits x Prol	babilit	y of Su	ccess) -	- Presei	nt	£50.0	<u>&gt;</u> 00			
-,	Costs							, -				
Project Progress March 2015	This project is Threepwood C of several Pha	now closed. Consulting ha se ID devices	ve nov and th	w comp ney will	leted a be del	a thoro ivering	ugh de their f	sktop a indings	and fiel s in Q3	d evalu 2015.	ation	



	High/Medium.
Potential for achieving expected benefits	Prior to commencing this project SPEN was aware of there being several Phase ID devices available in North America and Europe, but we were unsure how suitable they would be for our specific requirements for an ideal solution.
Collaborative Partners	None
R&D Providers	Threepwood Consulting



Project Title	IFI 1413 – Portable RAFL										
	This proof of concept project aims to investigate the feasibility of a portable Radiometric Arc Fault Locator (RAFL) to identify the location and to facilitate the quicker resolution of arc fault incidents.										
Description of project	This scope of this project will aim to modify an existing partial discharge (PD) monitor, which will then be tested in the field on a poorly performing circuit.										
	The key stages of the project are as follows: - Hardware Modification - Software Modification - Laboratory simulation and factory testing and by on-site installation										
	Internal	£16,182	_				Inte	Internal		0	
Expenditure for financial	External	£92,420	Expe	enditur financi	e in pre al vear	evious	Ext	ernal	£	0	
year	Total	£108,602	(11.1)	manci	ai yeai	3	Tot	al	£	0	
			Duci			<b>C</b>	Inte	ernal	£	25,000	
Project Cost	£77	,864	for 9	ectea ⊿ SPFN	.015/10	o COSTS	Ext	ernal	£	25,000	
			101 5				Tot	al	£	50,000	
Technological area and / or issue addressed by project	<ul> <li>These faults are frustrating, time consuming and costly to locate. Repeated man resetting is an inefficient use of resource. Accumulated Cls and CML and associated penalties they incur are real consequences of an inability to estab the root cause of relatively minor, but frequent incidents.</li> </ul>							(CML) ection ts are staff anual d the ablish			
Type(s) of innovation involved	Increm	ental	Sig	nifican	t	substitution		on	Radical		
	No			Yes			No			No	
	Successful completion of this project will provide a system that will provide the following benefits:         Expected Benefits of Project         - The ability to accurately detect and locate arc faults         - The ability to monitor and trend arc fault occurrence over time         - Faster resolution to fault situations         - A reduction in CI / CML penalties							e			
Expected Benefits of Project											
Expected Timescale to adoption	2 Ye	ars	Durat achie	ion of ved	penefit	once			16 Yea	irs	
					TRL De	velopm	ent (S	tart – C	urrent	)	
Probability of Success	50%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present£0.23M to £0.93M for 8Costsyears										



Project Progress March 2015	Project kick off meeting held in March. Initial design requirements and onsite testing have been partially completed. The project has been transferred over to NIA funding.
Potential for achieving expected benefits	This project is expected to provide all Network Licensees with an understanding whether this technology can successfully provide accurate fault location of OHL networks. SPEN have undertaken Cost Benefit Analysis (CBA) utilising the Ofgem ED1 CBA tool and has identified a number of feasible scenarios and benefits achieved from the use of RAFL as a method to locate OHL arc faults. The CBA identified an 8 year NPV ranging from £0.23M to £0.93M.
Collaborative Partners	Energy innovation Centre
R&D Providers	Elimpus



Project Title	IFI 1414 – PD-VMX									
Description of project	Continuously monito assets and allow for to occurs. The monitored fatality resulting from from within the cabin	Continuously monitoring partial discharge (PD) will provide a health check on assets and allow for targeted investment on problem units before potential failure occurs. The monitored switchgear will reduce the potential risk of serious injury or fatality resulting from a disruptive failure. The PD system will be able to detect PD from within the cabinet, particularly from bushings.								
	Internal £14,102			Internal	£0					
Expenditure for financial	External £43,484	Expenditure in pr	revious	External	£0					
year	Total £57,586	(IFI) IIIalicial yea	15	Total	£0					
		D : 1 2045/4		Internal	£0					
Project Cost	£63,600	Projected 2015/1	l6 costs	External	£0					
				Total	£0					
Technological area and / or issue addressed by project	Currently handheld P switching on higher r consistent measurem interpretation. Fixed I are expensive and do circuit breaker panel solution that will have	Currently handheld PD monitors can be used to manually check PD activity before switching on higher risk assets however it does not give a reliable indication of consistent measurement and is very much down to the users understanding and interpretation. Fixed PD monitoring solutions are available on the market but they are expensive and do not provide the detailed understanding of PD on particular circuit breaker panels. This project aims to develop a low cost PD monitoring solution that will have the ability to monitor individual panels								
Type(s) of innovation	Incremental	Significant	Techn subst	nological titution	Radical					
involved	No	No	١	es No						
Expected Benefits of Project	Successful completion of this project will deliver a prototype of a scalable product capable of detecting, locating and monitoring partial discharge cabinets. This system could then be deployed as both a safety tool and co assessment device helping provide a safer working environment as well time measurement of asset performance.									
	management.	management.								
Expected Timescale to adoption	1 Year	Duration of benefi achieved	t once		16 Years					
		TRL De	evelopme	nt (Start – C	Current)					
Probability of Success	50%	1 2 3	4	5 6	7 8	9				
Project NPV (Present Benefits x Probability of Success) – Present £0.15m for 16 y						S				
T Project Progress March 2015 o sr	he IFI project has supported the development of a prototype unit which will be nstalled at a substation location. The prototype has been developed for VMX witchgear and further work is required to fully evaluate the effectiveness or therwise of the product, and whether it could be a viable option for a large variety of witchgear.									
Potential for T achieving expected h benefits to	The prototype unit has been developed and test extensively in laboratory conditions, nowever until it has been evaluated on site over a representative period of time it is oo early to quantify the potential benefits it may achieve.									



Collaborative Partners	UKPN and Energy Innovation Centre (EIC)
R&D Providers	Elimpus



Project Title	IFI 1416 -	IFI 1416 – ROAMES-LIDAR									
Description of project	A 'proof or Australia th assets. In o to their s encroachm	A 'proof of concept' trial of a LiDAR based aerial surveying solution developed in Australia that generates a virtual world 3D representation of DNO overhead (OHL) assets. In doing so enables DNOs to take accurate measurements from OHL assets to their surrounding environment, identifying ground clearances, vegetation encroachment, pole lean etc.									
Expenditure for financia year	Internal External <b>Total</b>	Internal£14,102InternalExternal£231,131Expenditure in previous (IFI) financial yearsInternal ExternalTotal£245,233Total						f f f	0 0 <b>0</b>		
Project Cost	£24	5,233	Projected 2015/16 costs for SPEN T					ernal ernal al	£150,000 £1,350,000 <b>£1,500,000</b>		
Technological area and or issue addressed by project	/ This project utilised to	ct looks to id replace prese	dentify ent ma	r if aeri nual in:	al sur spectio	veys of ons carri	distril ed ou	oution t perio	OHL as dically l	ssets ca by UK D	an be NOs.
Type(s) of innovation	Increm	iental	Significant Techno substi			nolog stituti	ological titution		Radical		
Involved	N	o		No			Yes		No		
Expected Benefits of Project	Should this about how adoption of manual ins generating work progr	Should this technology proof to be successful, then it potentially has ramifications about how DNOs undertake all OHL asset inspections and work programmes. The adoption of this technology would ultimately lead to a significant reduction of the manual inspections undertaken by UK DNOs on OHL assets, whilst simultaneously generating precise network models that can be utilised within the DNOs other work programmes.								ations s. The of the cously other	
Expected Timescale to adoption	2 Ye	ears	Durat achie	ion of l ved	penefit	once			>8 Yea	rs	
					TRL De	velopm	ent (S	tart – C	Current		
Probability of Success	75	5%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present Costs £2.63m over 8 y							8 years	S		
Project Progress March 2015	As of March 2015 two LiDAR surveys and two ROAMEs virtual world representations of the trial area have been successfully generated by Fugro. These models and the functionality that they offer were assessed. To this end SPEN was impressed by the berformance of the solution to proceed with a larger more comprehensive pilot project. Through NIA_SPEN 0002 Virtual World Asset Management, SPEN will look to thoroughly assess the benefits realised through the adoption of this solution and identify how the solution can be best integrated into present DNO systems for asset management.										
Potential for achieving expected benefits	High, however pilot project is UK.	h, however given the high cost to implement such a solution SPEN believes the NIA of project is essential to ensuring the benefits can be achieved if applied across the									



Collaborative Partners	Fugro Geospatial B.V.
R&D Providers	Fugro Geospatial B.V.



Project Title	IFI 1417 – Keyhole Trenchless Technologies									
	The aim of this project is to create a new trenchless technology unit that can be inserted into the ground via an excavated joint bay, and then drill under the ground rather than open up a trench. The underground drilling will be controlled from above and once installed the service cable will be pulled back through.									
Description of project	This installation approach should result in reduced excavation and reinstatement costs and improved customer service due to the reduced interruption to customers/the public and improved traffic flow at the areas of excavation. The new unit will also decrease the time taken to complete the job, which in turn will reduce cost of labour, and may also allow more jobs to be undertaken.									
	Internal £27,968					Inte	ernal	£	0	
Expenditure for financial	External £316,587	Exp	enditur	e in pre	evious	Ext	ernal	£	0	
year	Total £344,555	(11.1)		ai yeai	3	Tot	al	£	0	
				o 4 = /4	<b>.</b> .	Inte	ernal	£	25,000	
Project Cost	£309,928	for	Jected 2 SPEN	015/10	b COSTS	Ext	ernal	£	25,000	
						Tot	al	£	50,000	
Technological area and /	<ul> <li>Costs of excavatin a service, or insert</li> <li>Improving safety t</li> </ul>	ig and ting a r	the reir new serv	istating vice int	g the gro o a prop	ound erty t exca	when u	ıpgradi	ng/rem	ioving
project		.o emp								
	Reducing the adverse impact to both the customer and the local environment that can result from conventional trench excavation interruption									
Type(s) of innovation	Incremental Significa			:	Techr subs	nolog tituti	ical Radical			
IIIvolveu	No Yes					Yes No				
Expected Benefits of Project	This project is expected to produce cost savings and efficiency improvements for the business. The cost savings are expected to come from reduced excavation and reinstatement costs. Other benefits include improved customer service by reducing installation times and the disruptive impact of open trench excavation.									
Expected Timescale to adoption	1 Years	Dura achie	tion of l eved	penefit	once			10 Yea	rs	
		 TRL Developmen						urrent)		
Probability of Success	75%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Pro	obabili	ty of Su	ccess) ·	– Presen	t	Not ki	nown a	t this st	tage
Project Progress March 2015	The project was initiated at the end of November 2014, when the original equipment provided by Tracto-Technik UK was trialled. This trialling identified development needs such that the equipment might be deployed successfully in the electricity supply industry.									
	The project's notentia			octod	honefite	ic co	ncidar	nd high	20 +h	
Potential for achieving expected benefits	The project's potential to realise expected benefits is considered high, as the Cost Benefit Analysis (CBA) undertaken shows that financial savings have the possibility of being high. Early incorporation into Business-as-Usual (BAU) is anticipated (by 2016) after trialling, evaluation and further modification, as required of the developed unit.									



Collaborative Partners	IQA
R&D Providers	Tracto-Technik UK