




# Angle – DC

Andrew Moon – Lead Innovation Engineer

Future Networks

- TNO and DNO for Southern and Central Scotland
- DNO for Merseyside and North Wales
- 44,000km Overhead Lines
- 65,000km Underground Cables
- Over 3000 substations
- A Total of 3.5 Million Customers



## The Future Networks team are delivering our innovation strategy through;

- Industry leading expertise
- Concentrating on creating a positive and lasting impact on the future of distribution and transmission
- Two major fields of focus – black start and power electronics

### **Black Start**

Black Start since 2015

Range of partners

Built expertise and capabilities

### **Power Electronics**

Implementation across voltages on transmission and distribution networks

## VISOR

Greater visibility of network state and assets

## FITNESS


Efficient and effective digital substation

## Distributed Restart

DERs supporting the network and restoring power

## Synthesis

Advanced analytics and real-time control enabling rapid response to system disturbances



**£13.59m** further **investment** for **SPT**, estimated **£40m** for other GB Transmission business

**£54m investment** in **RIIO-2** Business plan - digital substations - Westfield and Hunterston

**£5m Green Recovery Fund:** Synergy

**2023-SIF:** Black-start from the offshore

## Phoenix


**Synchronous condensers + static compensator** technologies - **manage reduced inertia** and **voltage control** on Transmission Network.

## Angle-DC

Medium Voltage DC (**MVDC**) link to **Anglesey**, increased **renewable generation** integration.

## LV Engine

**Trial** of innovative **Smart Transformers** for the connection of **LCTs**



**£120m investment** in **RIIO-2**

Business plan -  
implementation of  
**synchronous condensers** at  
**Eccles**

**3** further sites planned to roll  
out **LV Engine Technology**  
within **RIIO-ED2**

# Content

## 01 Project Overview

- Project Aims
- Project Structure

## 02 MVDC System Design & Technical Information

- MVDC Converter and DC Link
- Design Standards
- System Protection & Operation
- MVDC Commissioning Tests


## 03 Project Benefits

- Increased Distributed Generation Hosting Capacity
- Reduced Losses

## 04 Lessons Learned

# Project Overview

- **£14.8m Ofgem funded**
- Network Innovation
- Competition project (NIC).
- **Ground-breaking project,**
  - Improve network capacity and performance.
- Forming a Medium Voltage Direct Current (MVDC) link
- Converting an AC interconnector to DC
- Provides Power flow control




## Concept

- 33kVAC cable/OHL circuit utilised for DC operation.
- Control real/reactive power flows, voltage
- Increase in DER capacity.
- Learning from AC to DC Conversion.
- Learning: install, operate and manage a MVDC link.

## AC to DC Conversion


- Symmetrical monopole.
- Existing 2 x paralleled 33kV circuits AC (in green).
- AC-DC converters installed at both sub-stations.




# MVDC Link System Design & Technical Information

- **Operating Voltage +/-27kVDC (54kVDC between poles)**
  - 33kVAC infeed -> 2.1kVAC and connected to each inverter module.
  - Inverter modules input = 2.1kVAC, output = 4.5kVDC.
  - 6 x inverter modules connected in series per pole ( $6 \times 4.5\text{kV} = 27\text{kV}$ )
- **Power Transfer mode (30MVA) between substations**
- **STATCOM mode (+/-15MVAr) voltage support to the 33kVAC busbars.**
- **Inverters/circuit are “pre-charged” to overcome in-rush current.**
- **Poles are mid-point earthed. Earth fault return path.**


# MVDC Station Electrical Layout




# MVDC Station Physical Layout



## Bangor Converter Station



## Llanfair PG Converter Station



## Converter Transformers



- 2 x 17.5 MVA Transformers
- Oil natural Air Natural Cooling
- 33kV AC Input.
- 2.1kV AC Output into Converter Modules

## AC/DC Converters Modules



- 12 Modules Total ( 6 Pos leg, 6 Neg leg)
- 2.1kV AC Input
- 4.5kV AC Output
- IGBT power electronic switches

## DC Reactor



- 10mH Rated Inductance
- Smoothing DC output current
- Space to protect from Electromagnetic field effects

## Pre-Charge Unit




- Pre-charge transformer & disconnecter
- 2.1kV AC pre-charge of the system
- Reduces mag-inrush currents during energisation of converter transformers

## DC Control Room



- Converter Controllers, enabling local operation
- LV Supplies
- Partial Discharge Monitoring
- Telecomms, RTU

## Mid-Point Resistor



- 10 $\Omega$  Banked Resistor, connected to Positive and Negative Legs of DC link
- Provides return path for current during faults.
- Sensor to detect current and operate protection


Item	Standard	Key Findings
Cable/OHL Conversion	IEC 61975	<ul style="list-style-type: none"> <li>• HV pressure tested, cable/OHL intact.</li> <li>• MVDC Commissioning tests – High Power tests, cable/OHL performed well.</li> <li>• Partial Discharge results to follow.</li> </ul>
Harmonics	G5	<ul style="list-style-type: none"> <li>• MVDC Commissioning tests – THD below limits.</li> <li>• No impact above 6<sup>th</sup> Harmonic. Limited harmonic current below 6<sup>th</sup> harmonic.</li> </ul>
Control	IEC 60870	<ul style="list-style-type: none"> <li>• Control of both stations operating as expected.</li> <li>• Control of both converter stations from Bangor via fibre link.</li> <li>• RTU link back to Control Room for remote operation/start-up/shutdown.</li> </ul>
EMC	EN 50121 IEC-TR 62543	<ul style="list-style-type: none"> <li>• No EMC impact on Network Rail assets.</li> <li>• Monitoring continued through first 6 months of operation to detect any voltage issues.</li> </ul>
Protection	IEC 60255	<ul style="list-style-type: none"> <li>• Protection of both AC and DC systems.</li> <li>• During commissioning tests, protection operated as expected.</li> </ul>

# Common Safety Method – Risk Assessment




Results of initial commissioning tests shown below. Tests completed in 3 stages;

- 1) Low Power Steady State Tests
- 2) High Power Transmission Tests
- 3) Step Response Tests




- A Common Safety Method for Risk Evaluation and Assessment (CSM-RA)
- Evaluated the AC to DC conversion at commissioning
- Monitoring showed compliant DC harmonic and Electromagnetic Compatibility
- Negligible maximum harmonic currents above 6<sup>th</sup> harmonic were found



# Project Benefits

DG hosting capacity up to 15% can be achieved in the Anglesey network





Power losses over a day of the network by using MVDC link and the original AC operation



Strategy	Daily Average Power Loss (MW)	Daily Energy Loss (MWh)
AC operation	1.556	37.35
Control strategy for PLR	0.562	13.49
Control strategy for FLB	0.578	13.87
Control strategy for VPI	0.673	16.15
Compromise control strategy 1	0.607	14.58
Compromise control strategy 2	0.613	14.72

# Lessons Learned

## EMC Safety Case

- Complex and challenging study.
- Learning can inform future MVDC systems.

## Cybersecurity

- Cybersecurity constantly changing.
- In-depth and rigorous cybersecurity requirements.

## Station Cooling

- Building Environment is like a data centre.
- CAPEX vs OPEX costs for closed and open systems.
- Volume of Module housing.

## DC Protection

- High Impedance pole to ground faults.

# Questions

