

SIF Alpha Round 2 Project Registration

Date of Submission

Jan 2024

Project Reference Number

10079465

Initial Project Details

Project Title

HyNTS Hybrid Storage

Project Contact

Matthew Hammond

Challenge Area

Preparing for a net zero power system

Strategy Theme

Net zero and the energy system transition

Lead Sector

Gas Transmission

Project Start Date

01/10/2023

Project Duration (Months)

6

Lead Funding Licensee

NGT - National Gas Transmission PLC

Funding Mechanism

SIF Alpha - Round 2

Collaborating Networks

Technology Areas

Hydrogen

Energy Storage

Gas Transmission Networks

Project Summary

The Hybrid Storage System will enable safe and efficient storage of hydrogen on operational sites using an optimised approach to hydrogens physical state against production and demand profiles.

Add Preceding Project(s)

10060432 - Hybrid Storage Systems for site safety and efficiency

Add Third Party Collaborator(s)

Manufacturing Technology Centre

H2GO Power

HydroGenus

Project Budget

£418,949.00

SIF Funding

£375,369.00

Project Approaches and Desired Outcomes

Problem statement

Perception of Problem and Project Evolution

The National Transmission System (NTS) utilizes compression to manage pressures and flows in the pipelines to ensure gas demand can be met. The majority of compressors on the NTS are driven by gas turbines, which are fuelled by natural gas taken from the NTS. These assets produce emissions and waste heat which are currently lost to the atmosphere. National Gas Transmission (NGT) has a number of projects looking at fuelling gas turbines with hydrogen generated from electrolyzers, where storage is a key element to keep the size and CAPEX of the electrolyser unit at cost-effective levels. The Discovery phase of the project has considered combining solid state hydrogen storage with high density but slow release rates with compressed gas storage with high release rates. It was determined that the solid state storage could not support the demands of the gas turbine alone and that some level of compressed gas storage was required. The configuration of the system was optimised based on the demands of the gas turbines however the Alpha phase will also consider the smart operation of the system based on green electricity availability (i.e. weather forecasting).

Innovation Challenge

This project looks to address the challenge of preparing for net zero power systems using novel ways to reliably support low stability systems. Green hydrogen production is a low stability system in that the production is reliant on the weather (wind/solar) and/or constraints in the electricity network. This makes it very hard to predict the alignment of production and demand of hydrogen.

Storage and release of hydrogen within relevant timescales is going to be vital to ensuring a consistent energy source and improved resilience. Compressed gas storage is a method utilized today to support green hydrogen production, however, the space requirements and safety of these systems are limited. Alternative technologies such as solid state or liquid hydrogen storage provide benefits in storage density and safety but have challenges in the release rates of the hydrogen. It is believed that a hybrid storage system of solid and gaseous storage managed by an artificially intelligent management network HyAI could provide a safe and reliable opportunity.

Users of Innovation and their needs

As hydrogen is not yet available in gas networks, localised small scale production of hydrogen could be deployed where decarbonisation of assets and processes is required on a small scale. This project is focusing on the application of hybrid storage systems to NTS gas turbines on compressor stations, however the solution could be applied to any site where hydrogen utilisation would be intermittent and a combination of long and short term storage is required. This could be small industry or businesses.

Previous Innovation Projects

NIA Hydrogen Fuel Gas for NTS Compressors -- this project looked at the opportunity for fueling a gas turbine with hydrogen produced by electrolysis. The findings of this NIA project have been fed into the Waste Heat Recovery project to avoid duplication and repetition of work.

SIF HyNTS Compression Discovery and Alpha -- The SIF HyNTS Compression project is looking at the opportunity to repurpose a compressor unit for hydrogen, including the gas turbine, providing the technical and safety evidence for this. The outputs of HyNTS Compression will feed into the Waste Heat Recovery SIF project Beta phase.

NIA Hydrogen Production Technologies for the NTS -- this project investigated the opportunity of placing various hydrogen production technologies on NTS sites, including pyrolysis and electrolysis.

SIF Electrolyser Efficiency Improvements from Waste Heat Recovery -- determined the feasibility of increasing hydrogen production efficiency through waste heat capture from gas turbines using solid oxide electrolyzers.

Innovation justification

Preparing for a Net Zero Power System

Green hydrogen production is a low stability system in that the production relies on the weather (wind/solar) and/or constraints in the electricity network making it hard to align production and use of hydrogen. Having an efficient optimised storage system means that hydrogen can be produced during periods of high renewable generation and stored, reducing the overall cost of hydrogen.

Learnings from Previous Projects

The NIA project 'Hydrogen Fuel Gas for NTS Compressors' looked at on site hydrogen production and storage options for fuelling gas turbines. It concluded that a compressed gas store of over 11 tonnes would be required alongside a Tier1 COMAH permit which comes with considerable resource and cost to achieve. This has driven the need for an alternative and solid state storage could meet the storage requirements whilst avoiding entering COMAH regulations, as the hydrogen is stored as a chemical compound and the safety requirements for that compound would apply.

Working with Stakeholders

The project has engaged with National Gas Transmission internal teams including Subject Matter Experts in Rotating Machinery, Operations and Policy and Regulation to help define the system requirements, as well as other networks to understand their needs. The project has also engaged with other SIF projects to share knowledge and experience, including UKPN's Connectrolyser and NGT's Waste Heat Recovery projects.

Innovation

This project is innovative in its approach by hybridising solid and gaseous storage to resolve the limitations of the different hydrogen storage systems. The proposed solid state hydrogen storage technology stores hydrogen more efficiently, safely and at a lower cost than compressed gas. The hydrogen forms a chemical bond with the metal forming a metal hydride, meaning the safety requirements would apply to the metal hydride rather than hydrogen itself. The system includes an innovative machine learning platform (HyAI) using reliable algorithms which predict energy generation/storage /demand to optimise operations across the value chain. This project will also consider the opportunity to expand the scale of the solid-state system and utilise novel methods to improve release rates alongside the use of gaseous storage.

State of the Art

For small scale hydrogen storage, the current options include compressed gas storage, liquid storage and carriers such as ammonia. Compressed gas storage is well established and more suited to short term storage but comes with associated safety considerations. Carriers allow hydrogen to be stored as another chemical such as ammonia or liquid organic hydrogen carriers. Liquid allows for easier transport and storage but the efficiencies of these technologies are low due to the high temperatures require to release the hydrogen.

TRL

Currently 4-6, moving to 7

IRL

Currently 1, moving to 4-5

CRL

Currently 1-2, moving to 4-5

Project Size and Scale

The demonstration will take place on a low utilisation compressor station, reducing the CAPEX on equipment and minimising disruption, whilst allowing the increased efficiencies to be demonstrated on an active site. The project will consider different sites on the NTS to better understand the business case and wider roll out of the solution.

BAU

The key technology to be demonstrated is at low TRL (solid state storage 4-6), and funding the demonstration through innovation funding reduces the risk of the project. Additionally, hydrogen activities are not currently funded through business as usual funding.

Counterfactuals

Compressed gas hydrogen storage is an option for our application, but would require additional safety considerations which could be prohibitively costly for both a demonstration and roll out across the network. COMAH permit application fees could be as much as £1m per site, excluding ongoing annual fees.

[Complementary SIF projects.pdf \(opens in a new window\)](#)

(/application/10079465/form/question/33889/forminput/91706/file/564419/download)

Impact and benefits (not scored)

Financial - future reductions in the cost of operating the network

Financial - cost savings per annum on energy bills for consumers

Financial - cost savings per annum for users of network services

Environmental - carbon reduction – direct CO2 savings per annum

Environmental - carbon reduction – indirect CO2 savings per annum

New to market – products

New to market – processes

New to market - services

Impacts and benefits description

Pre-innovation baseline

In order to quantify the financial benefits of a hybrid storage system a baseline of a compressed gas storage system will be compared against the novel design. Consideration of the wider financial and environmental benefits that hybrid storage enables with the use of hydrogen for compression to meet emission reduction targets will also be necessary.

Financial Benefits

Significant upfront and ongoing costs are associated with COMAH certification to store >5t compressed hydrogen. These costs will be further explored as the project progresses but are in the order of £800k initially followed by an additional £150k/year for ongoing interventions per site. If large amounts of hydrogen storage were required across all 12 compressor stations with Avon gas turbines (in order to meet the Medium Combustion Plant (MCP) Directive for low emissions in 2030), this has the potential to cost £9.6m in addition to yearly costs of £1.8m, increasing the network operation costs. It should also be highlighted that there are additional implications for COMAH sites including an increased presence in police patrols and rapid response to perceived threats, therefore an increase in the number of sites classified this way will affect the wider area as well.

At high utilisation individual sites such as those identified in the discovery project, the implementation of on-site hydrogen production via electrolysis with hybrid storage also offers the potential to reduce initial CAPEX costs by £6m from £26.5m to £21.4m when compared to on-site hydrogen production with compressed gas storage only.

More widely, there are currently 30 Avon gas turbines on the NTS which are earmarked for replacement in order to meet the MCP Directive as no alternative low emissions retrofit technology (such as DLE) will be ready by 2030. If these units can be repurposed for hydrogen by 2030 (which would also necessitate adequate hydrogen storage and supply), National Gas could avoid replacing these units at a cost of ~£60m each, or £1.8Bn in total.

Environmental - System Emissions

In 2021, Avon gas turbines at compressor stations emitted around 106,000 tonnes of CO₂ from burning natural gas. If the fuel gas contained 20% vol hydrogen this would decrease emissions by around 7%, or alternatively could eliminate CO₂ completely if 100% hydrogen is used as the fuel gas. In the highest utilisation scenarios, using 100% green hydrogen could result in significant CO₂ emissions savings of up to 12,000t per year per compressor. Using green hydrogen from electrolysis would mean there would be no indirect CO₂ associated with the hydrogen production.

Safety Benefits

Deployment of solid state storage could be safer than having significant compressed gas storage on site, with lower risks and hazards associated with lower operational pressures. Additionally, the ventilation of the units is such that the lower explosive limit (LEL) of hydrogen may not be reached, and the system could avoid being classed as ATEX, which would reduce costs.

Benefit Synergies

A broader understanding of the wider system benefits (for efficient on-site H₂ production and storage) will be achieved through working in conjunction with other SIF projects including HyNTS Waste Heat Recovery, SGNs Carnot Gas Plant application & UKPNs Connectrolyser to ensure alignment and that the value of the synergistic benefits is articulated, as such each energy network is supporting these Alpha submissions to ensure collaboration.

Initial benefits will be seen during the beta phase, once the demonstration site is operational, however most benefits will occur once the system has been deployed across multiple operational sites. We believe this could be achieved through the Project Union timeline of between 2026 and the early 2030s for the gas transmission network.

Teams and resources

Changes to Project Team

Wales and West Utilities are no longer a partner on the project. They had a supporting role in the Discovery phase with no deliverables, and have opted not to continue supporting for the Alpha phase.

We have added HydroGenus to the project who are currently a partner on the Waste Heat Recovery SIF. This will allow for greater overlap between the projects. HydroGenus have a wealth of experience for developing low carbon hydrogen hubs in the UK.

Skills and Expertise

National Gas Transmission (NGT)

are the lead participant in the project and will provide clear direction and insight to the project partners on the project application and proposed benefits. NGT will also provide insight into our Hydrogen strategy and the part the national transmission system must play in the Net Zero future. This is vital in the project team developing their implementation strategy and business case as the project progresses through the delivery phases.

H2GO Power

has a significant track record in the implementation of R&D projects, fusing engineering excellence with robust project management. Their team is composed of experts both in hardware and software technologies and are capable of supporting the development of the proposed technology and adapting it directly to the needs of the project.

The Manufacturing Technology Centre (MTC)

is part of the High Value Manufacturing Catapult and is an independent Research and Technology Organisation. In partnership with industry, academia and other institutions the MTC develops and proves innovative technical processes and technologies in an agile, low risk environment, helping accelerate them through the Technology Readiness Levels (TRL).

UK Power Networks

are the UK's largest electricity distributor delivering power to 8.3 million homes and businesses across London, the east and south east of England. UKPN is responsible for providing electrical demand and generation connections up to 132kV. It is expected that a significant proportion of hydrogen electrolyser requests will connect to the distribution network, and it is therefore suitable for a DNO to be a partner on this project.

Hydrogenus Ltd

are a new partner on the project. They aim to become the leading UK developer for local production of low-carbon hydrogen by electrolysis, with extensive experience in the electricity, hydrogen and water industries, including financial, regulatory, technical, commercial, and operational assignments. All the team have experience in undertaking feasibility studies to inform and prepare for follow-on development projects, some with mature technologies, and some within the innovation space. HydroGenus' team members have a track record in assembling, leading and co-ordinating teams for multi-disciplinary projects such as is proposed in this bid.

Additional Resources and Facilities

H2Go Power will undertake some in-house testing on a laboratory scale to look to improve the pressures and flow rates from the solid state storage. This requires design and build of a small reactor which is reflected in H2Go's materials costs for Alpha. This will be carried out in H2Go's existing facilities, but materials and labour costs are required for the design and build of the reactor for the testing.

Project Plans and Milestones

Project management and delivery

How will you manage your Project effectively?

The Alpha phase will be undertaken through 4 work packages, utilising agile project management methodologies to complete a detailed design by the end of the 6 month period. We will aim to run tasks in parallel and summarise in a concise report to conclude the detailed design phase. Requests for information (RFIs) & actions will be tracked utilising SharePoint with partners to ensure timely/efficient sharing of information.

WP1 - Project Management led by NGT - £14,855.50

This work package will ensure the project meets its projected timing, risk and cost through the Alpha period and will develop the plan for the Beta phase project.

Milestone 1 - Beta application

SC11 - Final report completed and Beta application submitted

WP2 - Business Case & Requirements Development led by NGT - £68,080.50

This work package will develop the key requirements for the system and develop the business case and robust CBA for the system to be deployed.

Milestone 1

-

Business Case

SC1 - Business case and CBA refined

Milestone 2 - Benchmarking

SC2 - Review Global Systems and plans and report this against the planned approach

Milestone 3 - Wider Hydrogen Hub

SC3 - Feed in inputs from UKPN Connectolyser and wider H2 hub development

WP3 - Hybrid Storage System led by H2GO - £217,019.00

This work package develops the detailed design of the solid-state and compressed H2 storage on NTS compression systems and determines the costed development plan for Beta and use case development for NTS deployment.

Milestone 4 - Multiphysics simulation results

SC4 - AI-assisted multiphysics simulations for optimising reactor internal heat transfer to enhance reactor performance

Milestone 5 - Detailed design and simulation report

SC5 - Detailed design of containerised solid-state system including upgrade solid-state reactor & HyAI Simulation Report including presentation of interactive dashboard

Milestone 6 - Benchmarking system

SC6 - Benchmarking additional storage options to support solid state storage

Milestone 7 - Energy model development

SC7 - Incorporation of equipment and ancillaries, energy efficiency optimisation, scenarios for configuration optimisation

Milestone 8 - Electricity supply

SC8 - Options and requirements for electricity supply for electrolyser and storage equipment

WP4 -

System Demonstration led by MTC and supported by NGT - £75,414.00

This work package determines site specifics and associated costs related to electricity connection, systems integration, planning & permitting, demonstration design, build & commissioning and the inspection & testing plan.

Milestone 9 - Design of demonstration

SC9 - Once a system configuration has been determined through the 'Energy Model' activities, MTC will produce a system design that will incorporate major componentry and a high-level pipework layout.

Milestone 10 - System integration on site

SC10 - Equipment packaging and deployment, layout on site, permit requirements, build and test plan.

Risks will be managed as identified via the risk register with appropriate mitigation strategies applied throughout the alpha phase.

Project meetings will record progress in line with the project plan and actions will be tracked to ensure timely decisions can be made. The key risk associated with the project is mitigating the impact of low GT utilisation at the demonstration site to show a valid CBA and business case. By identifying the rollout and number of commercially viable sites on the network to deploy a hybrid storage solution we will avoid sites that require hydrogen production from entering COMAH status. Ongoing associated risks with project management and meeting SIF requirements will be managed by the project team through project setup and delivery. Contracting discussions will be initiated as soon as confirmation of award is confirmed as lessons learnt from the Discovery phase.

Key outputs and dissemination

What are the expected key outputs of your Project and your plan for disseminating them along with any lessons learned?

Objectives and Responsibilities

The Alpha phase will be used to build on the Discovery findings, including finalising the use cases for the demonstration, detailed system design, integration of system on selected site and demonstration and testing plan for Beta phase. Additionally, the business case will continuously be developed as the system develops.

National Gas

will be responsible for finalising the requirements and disseminating this to the project partners through regular project meetings. Additionally, NGT will develop the implementation plan for the system across the NTS. This will be disseminated through internal groups including asset strategy, asset management and appropriate policy teams.

H2Go Power

will be responsible for the detailed design of the solid state storage system and will deliver this as a report with associated engineering drawings and plans to be implemented in the Beta phase. This will be delivered through project meetings and the reports made available for review by other project partners and NGT internal teams.

MTC

will be responsible for benchmarking and selecting additional storage options to support the solid state system, building a full system energy model, incorporation of findings from the SIF Waste Heat Recovery project and optimising the full system efficiency through the energy model. This will be delivered through progress meetings and a final report to be disseminated to project partners and NGT internal teams for review.

MTC

will also deliver the design of the demonstration including layout of equipment and pipework, working closely with NGT to determine the requirements for the demonstration site. This will also include the integration of the system onto the selected site, including transportation and deployment and permit requirements for safe installation and commissioning. This activity will be carried out in consultation with relevant internal NGT teams to support the process and the outputs will be reviewed by NGT teams and partners.

Dissemination of Key Outputs

The above outputs will be compiled by NGT into a single project report which will be uploaded to the Smarter Networks Portal, along with other supporting documentation which has been approved for sharing outside of the project.

Furthermore, the findings from the project will be shared with NGT stakeholders through internal webinars and relevant meetings including Asset Management, Asset Strategy, Policy and Regulation, and Project Union.

National Gas Transmission

will take responsibility for the project dissemination and lessons learnt requirements, which includes creating a communication plan inline with SIF programme requirements, creating LinkedIn posts, and collating the Show and Tell content.

A communications plan will include a LinkedIn post announcing the project at the beginning of the project timescales, and one at the end to announce the project results. The Show and Tell will give the project results an additional opportunity to be disseminated. The final report and Show and Tell slides will be published on the ENA portal.

Additionally, National Gas Transmission will be attending the Energy Innovation Summit during the timeline of the SIF Alpha and will therefore have an opportunity to disseminate about the project on the stand at the event.

Commercials

Intellectual property rights, procurement and contracting (not scored)

What are the Intellectual Property Rights (IPR) arrangements for your project?

For SIF projects, each Project Partner shall own all Foreground IPR that it independently creates as part of the Project, or where it is created jointly then it shall be owned in shares that are in proportion to the work done in its creation. The exact allocation of Foreground IPR ownership will be determined during the contractual negotiations with the Project Partners on the agreement for the project. On creation of Foreground IPR the creator of the IPR will notify the project partners to enable it to be recorded and ownership agreed in line with the contract terms.

Also if the party appoints a sub-contractor, the agreement with that sub-contractor should have similar IP provisions to those in this agreement and which at least achieve the same aims as the agreement regarding IP.

Once the Project is completed, Relevant Background IPR will be licensed for use by the Project Partners in connection with another Project Partners' Foreground IPR solely to the extent necessary to use that Foreground IPR, upon terms to be agreed.

Describe how each Project Partners complies with Chapter 9 SIF Governance Document.

We intend to ensure each Project Partner will comply with Chapter 9 SIF Governance Document through the contractual terms governing the project. However, precisely how this is done will be subject to contractual negotiations with the Project Partners on the agreement for the project.

Commercialisation, route to market and business as usual

How will your idea become business as usual within your network and across the other networks?

Commercialisation and BAU

The Discovery phase has considered the implementation of this system across the UK Gas Transmission network post delivery of the demonstration in the Beta phase. This project could enable safer, more efficient hydrogen storage to support the cost effectiveness of hydrogen deployment on operational sites. It could also provide the opportunity to a wide range of hydrogen users across the country and globally.

We have considered our approach not only based on the Beta demonstration site but other sites including non gas network sites to understand the difference in costs and approach for deploying hybrid storage. The intended demonstration site for Beta has an opportunity beyond the network assets for the industrial and transport hydrogen users in the vicinity which are looking to connect to the hydrogen production unit to help them decarbonise. Additionally, this project will

be demonstrated alongside other SIF projects including NGT's HyNTS Waste Heat Recovery for Electrolysis and UKPN's Connectrolyser to provide a wider systems approach to energy storage and utilisation.

This project will demonstrate the system and validate the predicted benefits. The demonstration is planned to take place on an active site, and therefore will require the necessary changes to physical assets, control systems as well as policy and regulation, which would then be applicable to a large proportion of sites on the NTS. This will require engagement with relevant internal teams including asset strategy, asset management, rotating machinery, control systems and hydrogen. These activities required through Alpha and Beta will stand us in good stead to understand the approach to deploying this solution across the wider network and UK applications.

The Beta demonstration will deliver key evidence which will feed in to our price control business plan and hydrogen projects such as Project Union, enabling this solution to be rolled out across the network.

Commercial Readiness of Partners

MTC have a wealth of experience in supporting manufacturing through research and development, and have previously supported the SHyLo project with the European Marine Energy Centre (EMEC) where H2Go's solid state storage was deployed on a site in Scotland.

H2Go are the owner of the solid state hydrogen storage and the HyAI tool. These technologies have been demonstrated for commercial applications although the TRLs are around 7-8, and this demonstration through the Beta phase will help H2Go reach higher TRL and CRLs.

Our project partners are focussed on delivering a scalable hydrogen storage solution for the future and are dedicated to ensuring cost competitiveness of the technology for wide spread use in the future.

Senior Sponsor Involvement

This project is endorsed across all levels of management. The innovation team will be responsible for the delivery of the project and ensuring value to the business through implementation across the NTS. The project is supported by:

Subject Matter Experts for our operational equipment, ensuring the correct level of evidence is gathered to enable implementation
Operational teams to ensure the required changes to site are met for the demonstration

Policy and Regulation teams to ensure the correct approach in any policy and regulation changes is taken to allow hydrogen production, storage and utilisation on a NGT site

The project has been presented to the senior leadership team and CEO whom are in full support of the project and excited to see the projects come together in Beta as a demonstration of this fantastic opportunity. This work could enable us to ready our network prior to mass hydrogen production and prevent duplicated spend through the transition.

Policy, standards and regulations (not scored)

Do you consider there to be any barriers with respect to meeting the requirements of regulations, policy or standards?

Project regulatory barriers

There are no regulatory barriers that prevent the delivery of the project through Alpha. There are no policy changes required for us to fuel our network equipment with hydrogen and this could be utilised prior to hydrogen being injected into the network to decarbonise emissions from our network compression assets in line with the 2030 MCP emissions requirements.

In Beta we are looking to deploy this project alongside HyNTS Waste Heat Recovery for Electrolysis and Connectrolyser on an operational site which will require permits, early engagement to ensure these are attained will be required through the Alpha phase. As the project will not inject hydrogen into the gas network no derogations will be required for Gas Safety Management Regulation (GSMR), however with hydrogen on an operational site and interacting with network assets we will need approval from the HSE. We have been informed these deviations will take a minimum of 13 weeks and this will be considered in the Beta phase. In the Alpha phase we have a deliverable to review land rights and permits for the hybrid storage system to be situated on our compressor station and manage the COMAH requirements for the Beta demonstration project elements covered by this project. HyNTS Waste Heat Recovery for Electrolysis and Connectrolyser will consider the other elements associated to the electrolyser and electrical connections to the site and feed into the central steering group for the Beta application.

We are actively engaged with the HSE to ensure the NTS safety case for hydrogen and hydrogen blends is ready for Project Union commencing in 2026. This project and its findings will be integrated into this plan to ensure consistency in approach and alignment.

Longer-term regulatory barriers and policy requirements

The deployment of hydrogen on gas networks in the UK has not yet been finalised, however many exploratory demonstrations have been sanctioned across the UK. As we progress past Beta we will need to ensure that the opportunity to duplicate the demonstration is available for other sites. There are several policy and regulatory systems in review around the introduction of hydrogen considering both 100% hydrogen and blended hydrogen. Primary and secondary legislation will need to be updated to enable blends of hydrogen within the network and allow for the development of a 100% hydrogen NTS. Alongside this, rules will need to be agreed, such as the uniform network code (UNC) and GSMR to incorporate hydrogen blending and if required adapted for hydrogen transportation.

This does not directly influence this project as we will not be utilising network hydrogen or injecting into the network, but this is an opportunity for the future.

Evidence creation to influence future policy and regulations

The project will create evidence for the HSE and relevant stakeholders on the deployment of these systems, which will look to follow the approach utilised by the Hydrogen Grid Research and Development (HGR&D) working group. We continue to support Government and Ofgem in gathering the evidence required to deliver policy and regulation that will enable the energy transition through working groups such as HGR&D and Gas Goes Green (GGG). Evidence of our network's capability to support the transition is beginning to be reviewed by the HSE and development of approaches to blending both commercial and technical are underway through these collaborative working groups.

Value for money

What are the Alpha Phase Project costs and how are they proportionate to the Project delivery?

Project Costs and SIF Funding Requested

The total project cost is £418,949 including £41,895 contribution plus £1,685 contribution in kind, and we are requesting £375,369 of funding. The funding is split across the partners as follows:

National Gas Transmission - £71,606 (17%) (£41,895 contribution in kind) requesting £29,711 of SIF funding. Carrying out project management activities, business case and requirements development.

H2Go Power - £150,179 (36%) - solid state storage design and lab scale tests to improve performance.

MTC - £154,414 (37%) - system design, energy efficiency optimisation, demonstration design, manufacture and deployment of system on site.

UKPN - Total project costs = £18,525 (4%), SIF requested = £16,840, Contribution in Kind = £1,685 (9.10%). Supporting the project by providing input from Connectrolyser SIF and looking into electricity connection requirements for system.

HydroGenus Group Ltd. - £24,225 (4%). Supporting the project by providing insights into wider hydrogen hub development, including Connectrolyser project, Waste Heat Recovery and local industrial/transport applications.

The finances of all project partners are included in the milestones summary

(/application/10079465/milestones-summary)

.

Totalcosts (£)

Funding sought (£)

Contribution to project (%)

Contribution to project (£)

Contributions in kind (£)

71,606

29,711

58.51%

41,895

0

150,179

150,179

0.00%

0

0

18,525

16,840

9.10%

1,685

1,685

154,414

154,414

0.00%

0

0

24,225

24,225

0.00%

0

0

Total

£418,949

375,369

43,580

1,685

The split of funding shows that MTC and H2Go will be carrying out most of the work in the Alpha phase, delivering detailed design and costs of the system to be demonstrated in Beta.

Compulsory Contribution

£41,895 contribution will be provided by National Gas Transmission which meets the 10% financial contribution requirements for Alpha. UKPN are providing a contribution in kind of £1,685.

Associated Innovation Projects

Yes (Please remember to upload all required documentation)

No

Supporting documents

File Upload

H2go Final Report Optimisation Of Low Carbon Hydrogen For Compressor Station Redacted V2 (1) - 5.4 MB
Segment 001 of 3002131-DOC-033 Equipment Layout Presentation V1.0_Redacted.pdf - 1.8 MB
Alpha End of Phase Report - HyNTS Hybrid Storage.pdf - 254.4 KB
3002131-DOC-035 D22 - Permit requirements V 1.0.pdf - 2.0 MB
3002131-DOC-022 v1.0 - System Design and Demonstration.pdf - 1.3 MB
3002131-DOC-021 Energy Model Report 1.0_Redacted.pdf - 1.9 MB
3002131-DOC-010 v1.0 - Additional Storage Solutions_Redacted.pdf - 1.7 MB
3002131-DOC-009 - Benchmarking Document 1.0_Redacted.pdf - 1.6 MB
SIF Alpha Round 2 Project Registration 2024-01-17 11_56 (1) - 108.4 KB
SIF Alpha Round 2 Project Registration 2024-01-17 11_56 - 108.2 KB

Documents uploaded where applicable?

